



## TOWN OF RIDGWAY

# STANDARD SPECIFICATION AND TYPICAL DRAWINGS FOR INFRASTRUCTURE CONSTRUCTION

Updated February 2025

These standards, drawings, and supporting reports, plans, files, field data, notes, and other documents and instruments prepared by Consolidated Consulting Services (CCS) as instruments of service shall remain the property of CCS and the Town of Ridgway. The Town and CCS shall retain all common law, statutory, and other reserved rights, including the copyright thereto. These documents may not be used by others or duplicated for any other purpose.

# TABLE OF CONTENTS

## **DIVISION 1 - GENERAL REQUIREMENTS**

1. GENERAL PROVISIONS
2. PURPOSE
3. APPLICABILITY
4. INTERPRETATION
5. AMENDMENTS AND REVISIONS
6. DEFINITIONS AND ABBREVIATIONS
7. ENFORCEMENT
  - 7.01 Authority of Town
  - 7.02 Violations
  - 7.03 Deviations
8. RESPONSIBLE PARTY RESPONSIBILITIES
9. PLANS FOR REVIEW
10. RESPONSIBILITY FOR DESIGN AND CONSTRUCTION
11. EASEMENT REQUIREMENTS
12. PRE-CONSTRUCTION MEETINGS
  - 12.01 Pre-Bid Meeting
  - 12.02 Pre-Construction Meeting
13. NOTIFICATIONS BY RESPONSIBLE PARTY
  - 13.01 Notifications Prior to Work
  - 13.02 Non-Regular Work Hours
  - 13.03 Emergency Notice
  - 13.04 Testing
14. CONTROL OF WORK AND MATERIALS
  - 14.01 Work Hours
  - 14.02 Delivery and Storage of Materials
  - 14.03 Work Conditions
  - 14.04 Defective Materials
  - 14.05 Unacceptable or Authorized Work
  - 14.06 Staking Requirements
  - 14.07 Removal of Abandoned Infrastructure
15. PROTECTION OF FACILITIES, PROPERTY, AND IMPROVEMENTS
  - 15.01 Protection of Existing Facilities and Improvements
  - 15.02 Public Safety and Convenience
16. CONSTRUCTION SAFETY REQUIREMENTS
17. STOP WORK ORDER
18. CHANGES TO APPROVED PLANS
19. RECORD DRAWINGS AND OPERATION AND MAINTENANCE DATA
20. ACCEPTANCE, OPERATION AND MAINTENANCE
21. SERVICE RATES

## **DIVISION 2 – SITE WORK**

### **SECTION 02200 - EXCAVATION, BACKFILL, AND COMPACTION**

#### **1. GENERAL**

- 1.01 Description
- 1.02 Related Work Specified Elsewhere
- 1.03 Measurements and Levels
- 1.04 Conformance Testing
- 1.05 Existing Conditions
- 1.06 Protection of Existing Utilities

#### **2. PRODUCTS**

- 2.01. Submittals
- 2.02. General Use Materials
- 2.03. Bedding and Pipe Zone Materials Classification
- 2.04. Road Construction Materials
- 2.05. Unsuitable Materials
- 2.06. Topsoil
- 2.07. Riprap
- 2.08. Spot Subgrade Reinforcement and Sub-Grade Stabilization
- 2.09. Geotextiles
- 2.10. Capillary Water Barrier Material (CWB)
- 2.11. Seed, Mulch, and Tackifier

#### **3. EXECUTION**

- 3.01. Clearing and Grubbing
- 3.02. Removal of Cleared and Unsuitable Materials
- 3.03. Access Roads and Bypasses
- 3.04. Pavement Cutting
- 3.05. Dust Control
- 3.06. Drainage
- 3.07. Excavation
  - A. Grade Stakes
  - B. Tolerances
  - C. Stockpiling Materials
  - D. Sheeting, Bracing, and Shoring
  - E. Drainage and Groundwater Control
  - F. Use of Explosives
  - G. Sequencing
  - H. Excavation to Grade
  - I. Trench Width
- 3.08. Bedding Backfill, Compaction of Embankment, Pipelines, and Structures
  - A. Pipe Bedding
    - i. Bedding Preparation
    - ii. Placing Bedding Material
  - B. Backfill and Compaction
    - i. Structure and Appurtenance Backfill and Compaction
    - ii. Pipe Zone Compaction
    - iii. Upper Trench Compaction
  - C. Surface Restoration
  - D. Patching

- E. Topsoiling
  - i. Conservation
  - ii. Clearing
  - iii. Placing Topsoil
- F. Revegetation

## SECTION 02712 WATER SYSTEM - MINIMUM DESIGN STANDARDS

1. MATERIALS
2. MINIMUM FLOW
3. LINE SIZE
4. WATER LINE DEPTHS
5. WATER LINE LOOPING
6. VALVE SPACING
7. HYDRANTS
8. SERVICE CONNECTIONS
9. PROXIMITY STATEMENT
10. CROSS CONNECTIONS AND BACKFLOW PREVENTION
11. DISINFECTION AND FLUSHING
12. TESTING

## SECTION 02713 - WATER SYSTEM CONSTRUCTION

1. GENERAL
  - 1.01 Description
  - 1.02 Related Work Specified Elsewhere
  - 1.03 Proximity Statement
2. PRODUCTS
  - 2.01. Ductile Iron Pipe
  - 2.02. Plastic Pipe
  - 2.03. Copper Tubing
  - 2.04. Water Service Materials
    - A. Corporation Valve
    - B. Service Saddle
    - C. Meter Setter
    - D. Meter Can
    - E. Meter Can Lid
    - F. Water Service Pressure Regulator
    - G. Curb Box and Stop
  - 2.05. Gate Valves
  - 2.06. Valve Box
  - 2.07. Butterfly Valve 3" and larger
  - 2.08. Butterfly Valve Electric Actuator
  - 2.09. Fire Hydrants
  - 2.10. Flushing Hydrant
  - 2.11. Yard Hydrant
  - 2.12. Air Valves
  - 2.13. Cross Connection Control Valves
  - 2.14. Miscellaneous Valves
  - 2.15. Bolts and Hardware

- 2.16. Compression Couplings
- 2.17. Tracer Wire and Marking Tape
- 2.18. Insulation
- 2.19. Manholes
- 2.20. Casing Pipe
- 3. EXECUTION
  - 3.01. Field Locations
  - 3.02 Service Disruption
  - 3.03 Receiving, Handling, and Storage
  - 3.04 Alignment and Grade
  - 3.05 Excavation and Trench Preparation
  - 3.06 Pipe Laying
    - A. Lowering Pipe into Trench
    - B. Inspection Before Installation
    - C. Keeping Pipe Clean
    - D. Laying of Pipe
    - E. Sequencing
    - F. Cutting of Pipe
    - G. Connection to and Crossing of Existing Lines
  - 3.07 Water Service Installation
    - A. Service Line Installation and Responsibility
    - B. Meter Lid Elevation
    - C. Curb Stop and Box
  - 3.08 Crossings
  - 3.09 Setting of Fitting, Valves, and Hydrants
    - A. Valves and Valve Boxes
    - B. Hydrants
    - C. Dead Ends
    - D. Thrust Blocks
    - E. Air Valves
    - F. Cross Connection Control Valves
    - G. Vaults
  - 3.10 Bedding and Compaction
  - 3.11 Hydrostatic Testing
  - 3.12 Disinfection of Potable Waterlines
    - A. General
    - B. Pipe Cleaning
    - C. Preliminary Flushing
    - D. Chlorine Application
    - E. Continuous Feed Method
    - F. Tablet Method
    - G. Final Flushing
    - H. Disposal of Super Chlorinated Waters
    - I. Bacteriologic Tests
    - J. Repetition of Procedure
    - K. Disinfecting Existing Mains

CDPHE Low Risk Discharge Guidance 1/15/16

SECTION 02722 SEWER SYSTEM - MINIMUM DESIGN STANDARDS

1. PLAN APPROVAL
2. DESIGN FLOW
3. PIPING DETAILS
  - 3.01 Materials
  - 3.02 Size
  - 3.03 Grades
  - 3.04 Minimum Velocity
  - 3.05 Maximum Slope
  - 3.06 Manhole Spacing and Design
  - 3.07 Flexible Joints near Manhole
  - 3.08 Terminal Manhole
  - 3.09 Underdrains
  - 3.10 Drop Manhole
  - 3.11 Depth of Bury
4. LIFT STATIONS
5. INVERTED SIPHONS
6. SERVICE CONNECTIONS
7. CONSTRUCTION
8. PROTECTION OF WATER SUPPLIES
9. MISCELLANEOUS REQUIREMENTS
10. TESTING

SECTION 02723 SEWER SYSTEM CONSTRUCTION

1. GENERAL
  - 1.01 Related Work Specified Elsewhere
  - 1.02 Description
  - 1.03 Certificate of Compliance
  - 1.04 Reference Standards
2. PRODUCTS
  - 2.01 Pipe Materials
    - A. PVC
    - B. Ductile Iron
    - C. High Density Polyethylene (HDPE) Pipe Perforated
    - D. High Density Polyethylene (HDPE) Pipe
    - E. Steel Casing Pipe
    - F. Cleanout
    - G. Sewer Service Saddles
  - 2.02 Manhole Materials
    - A. Base, Inverts, and Cones
    - B. Markings
    - C. Frame and Cover
    - D. Manhole Steps
    - E. Non-Shrink Grout
    - F. Butyl Rubber Flexible Gasket Material
    - H. Pipe Connections

- I. Geotextile
- 2.03 Tracer Wire and Marking Tape
- 3. EXECUTION
  - 3.01 Handling, and Storage
  - 3.02 Underground Obstruction
  - 3.03 Excavation
  - 3.04 Alignment and Grade
  - 3.05 Laying Sewer Pipe
    - A. Inspection
    - B. Installation Instructions
    - C. Potential Conflicts
    - D. Lowering Pipe into Trench
    - E. Keeping Pipe Clean
    - F. Laying and Joining Pipe
    - G. Crossing Existing Lines
    - H. Cutting of Pipe
    - I. Sequencing
  - 3.06 Pipe Bedding
  - 3.07 Backfill and Compaction
  - 3.08 Manhole Construction and Installation
  - 3.09 Connections to Existing Manholes
  - 3.10 Connection Existing Pipes to New Manholes
  - 3.11 Wyes and Risers
  - 3.12 Service Installations
  - 3.13 Underdrains
  - 3.14 Lift Station and Force Mains
  - 3.15 Field Quality Control (Testing)
    - A. Infiltration Test
    - B. Test for Displacement of Sewers
    - C. Ovalation of Flexible Conduits
    - D. Video Inspection of Line Interior
    - E. Test for Pressure Lines
    - F. Air Test – Gravity Flow Lines
    - G. Manhole Tests
  - 3.16 Inspection Cleaning and Lamping
  - 3.17 Restoration and Cleanup
  - 3.18 Abandonment

Table - Allowable Pressure Drop

## SECTION 03000 – CONCRETE

- 1. GENERAL PROVISIONS
  - 1.01. General
  - 1.02. Reference Documents
  - 1.03. Submittals and Method Statements
  - 1.04. Quality control
- 2. MATERIALS
  - 2.01. General
  - 2.02. Cement



- 2.03. Flyash
- 2.04. Aggregates
- 2.05. Water
- 2.06. Air Entrainment
- 2.07. Admixtures
- 2.08. Flowfill Specifications
- 2.09. Reinforcement
- 2.10. Snap Ties
- 2.11. Water Stop
- 2.12. Expansion Joint Material
- 2.13. Curing Compound
- 2.14. Concrete Sealer
- 3. EXECUTION
  - 3.01. Subgrade Preparation
  - 3.02. Forming
  - 3.03. Slip Form
  - 3.04. Reinforcement
  - 3.05. Concrete Mixing
  - 3.06. Concrete Delivery
  - 3.07. Placement
  - 3.08. Reinforcement
  - 3.09. Consolidation
  - 3.10. Joints
  - 3.11. Finishing
  - 3.12. Curing
  - 3.13. Finishing
  - 3.14. Cold Weather
  - 3.15. Hot Weather
  - 3.16. Inclement Weather
  - 3.17. Protection of Concrete
  - 3.18. Backfilling
  - 3.19. Repairs
  - 3.20. Defaced, Defective and Damaged Concrete
  - 3.21. Sealer
  - 3.22. Acceptance Requirements
  - 3.23. Penalties for non-conformance
  - 3.24. Warranty

**SECTION 03240 - CURB, GUTTER, SIDEWALKS & STREETS MINIMUM DESIGN STANDARDS**

- 1. GENERAL
- 2. GRAVEL STREET CONSTRUCTION
- 3. PAVED STREET CONSTRUCTION
- 4. STREET LAYOUT
- 5. SERVICE LINE INSTALLATION
- 6. DRAINAGE
- 7. MONUMENTATION

SECTION 03250 – STREETS

1. GENERAL
2. CDOT Specifications
3. Street System Design Criteria
4. Staking Requirements
5. Design Element Coordination
6. ADA Compliance
7. Traffic Impact Study
8. Driveway Construction Regulation
9. Angled Parking in Town-Owned Rights-of-Way
10. Drainage
11. Landscaping
12. Deviations
13. Maintenance Responsibility
14. Use of Parking
15. Subgrade Investigation and Pavement Design Report
16. Quality Control
17. Quality Assurance
18. Grade Control
19. Removals, Excavation, Backfilling, and Restoration Specifications
20. Base Course Construction
21. HMA Pavement Materials and Construction
22. Asphalt Delivery and Placement
23. Appurtenances
24. Patching
25. Surface Smoothness
26. Field Quality Control
27. Pavement Markings
28. Cleaning and Protection
29. Final Inspection and Acceptance
30. Signs

POWER AND BURIED WIRES - MINIMUM REQUIREMENTS

GENERAL  
DEPTH OF BURY  
WIRE LOCATIONS  
BEDDING  
MARKING TAPE  
SEPARATION FROM OTHER UTILITIES  
LINE IN PUBLIC RIGHTS OF WAY  
CROSSING OTHER UTILITIES

CROSSINGS

ROADWAY CROSSINGS  
ARROYO AND CANAL CROSSINGS  
OVERHEAD INSULATED CROSSINGS

SLOPE STABILIZATION AND REVEGETATION

PART I - GENERAL

PART II - PRODUCTS

PART III - EXECUTION

BOARDWALK

## TYPICAL DRAWINGS

STANDARD BEDDING DETAIL  
SEWER / SEEP DETAIL  
CASING PIPE DETAIL  
GATE VALVE DETAIL  
FIRE HYDRANT DETAIL  
AIR VACUUM STATION  
BLOWOFF INSTALLATION  
THRUST BLOCK DETAIL (2 pages)  
3/4-1" WATER SERVICE  
1-1/2" – 2" WATER SERVICE  
SERVICE RECONNECTION  
MANHOLE TYPICAL  
DROP MANHOLE (2 pages)  
GRAVITY CLEANOUT ELEVATION  
PRESSURE CLEANOUT PLAN VIEW  
SEWER SERVICE DETAIL  
STORM DRAIN INLET  
STREET DIMENSIONS  
TYPICAL ROAD SECTION WITH PAN  
TYPICAL ROAD SECTION WITH VERTICAL CURB  
TYPICAL GRAVEL STREET  
CUL DE SAC  
CUL DE SAC (ALT)  
CURB, CUTTER, SIDEWALK DETAILS  
SIDEWALK DRAIN BOX  
VALLEY PAN DETAILS  
INTERSECTION DETAILS  
PAVEMENT REMOVAL  
DRIVEWAY DETAILS  
MONUMENT DETAILS  
HANDICAP RAMP (2 pages)  
PARKING LAYOUT  
CROSSING DETAILS