RIDGWAY PLANNING COMMISSION REGULAR MEETING AGENDA

Tuesday, January 10, 2023 5:30 pm

Pursuant to the Town's Electronic Participation Policy, the meeting will be conducted both in person and via a virtual meeting portal. Members of the public may attend in person at the Community Center, located at 201 N. Railroad Street, Ridgway, Colorado 81432, or virtually using the meeting information below.

Join Zoom Meeting

https://us02web.zoom.us/j/88517656693?pwd=cnZMY2tzZkZrV2pIZ2ZNNzZ2dDk0QT09 Meeting ID: 885 1765 6693

Passcode: 970420 To call in dial: 408.638.0968 or 253.215.8782 or 669.900.6833

Written comments can be submitted before the meeting to <u>kchristian@town.ridqway.co.us</u> or delivered to Town Hall Attn: Planning Commission

ROLL CALL: Chairperson: Michelle Montague, Commissioners: John Clark, Jennifer Franz, Bill Liske, Russ Meyer, Jennifer Nelson, and Jack Petruccelli

PUBLIC HEARINGS:

- Continuance Request Application: Sketch Plan; Location: McChesney Minor Subdivision, Lot 2; Zone: Residential (R) and Future Development (FD); Applicant: Chris Hawkins dba Alpine Planning, LLC; Owner: Four Winds Ranch, LLLP & Estate of Bernadine C. Endicott
- Application: An Amended Plat of Lot 15, Parkside Subdivision; Location: Parkside Subdivision, Lot 15; Address: 702 N. Laura St., 704 N. Laura St., and 706 N. Laura St.; Zone: Residential (R); Applicant: Amanda Gerhardt; Owner: Habitat for Humanity of the San Juans
- Application: Variance to allow a 0 ft. side setback for townhomes; Location: Parkside Subdivision, Lot 15; Address: 702 N. Laura St., 704 N. Laura St., and 706 N. Laura St.; Zone: Residential (R); Applicant: Amanda Gerhardt; Owner: Habitat for Humanity of the San Juans

WORK SESSION

4. Update from staff regarding updates to RMC Chapter 7 "Planning and Zoning"

APPROVAL OF MINUTES:

5. Minutes from the Regular meeting of November 29, 2022

OTHER BUSINESS:

6. Updates from Planning Commission members

ADJOURNMENT

AGENDA ITEM #1



To:	Town of Ridgway Planning Commission
Cc:	Preston Neill, Ridgway Town Manager
From:	TJ Dlubac, AICP, Community Planning Strategies, Contracted Town Planner
Date:	January 6, 2023
Subject:	Four Winds Sketch Plan for January 10 th PC Meeting

APPLICATION INFORMATION

Request: Legal:	Approval of a Sketch Plan to create 20 single family residential lots. Lot 2 of McChesney Subdivision, Town of Ridgway and SE 1/4 of SE 1/4 of Section 9and the NE 1/4 of the NE 1/4 of Section 16 all in T45N, R8W of the N.M.P.M. except that portion being described as Lots 25 - 48 and the common ground of Vista Terrace Subdivision, Filing No. 1, Town of Ridgway
Address:	N/A
General Location:	Generally located north of and east of Terrace Drive, east of Highway 550.
Parcel #:	430509400146
Zone District:	Residential (R) District and Future Development (FD)
Current Use	Vacant and one single-family residential unit
Applicant	Chris Hawkins, Alpine Planning
Owner	Four Winds Ranch 1, LLLP and Bernadine C. Endicott


PROJECT REVIEW

BACKGROUND

This application for a Sketch Plan was submitted on April 25, 2022. A completeness review was conducted, and the application was accepted as complete on May 7, 2022 and the applicant submitted updated materials on May 9th.

The application includes Lot 2 McChesney Subdivision (33.09 acre) ("Lot 2") and approximately 9.95 acres of the adjacent property located at 741 Terrace Drive ("Endicott Property"). Lot 2 is 33.09 acres and the Endicott Property is 9.95 acres for a total area of 43.04 acres and is split by the Terrace Drive right-of-way access to Highway 550.

Currently, Lot 2 is zoned Residential, and the Endicott Property is zoned Future Development. The applicant will need to request a rezoning of the Endicott Property pursuant to RMC §7-3-22 and RMC §7-3-23.



Such rezoning must be obtained prior to the final approval of a Preliminary Plat for the property contained within this request.

JUNE 28TH UPDATE

The applicant requested that the Planning Commission continue the public hearing for this application until their regular meeting on August 30, 2022 to allow the applicant to continue working through issues identified through staff's review of the application.

Town of Ridgway Four Winds Sketch Plan January 10, 2023 Page 2 of 2

AUGUST 30TH UPDATE

At its regularly scheduled meeting on August 30, 2022, the Town of Ridgway Planning Commission voted to continue the Sketch Plan for the Four Winds Subdivision to the December Planning Commission meeting (which may be held in January 2023 due to holidays) at the request of the owner's representative. The vote passed 6-0. The Commissioners continued the application to allow time for the development team to further address the comments and topics discussed in the meeting in coordination with town staff. A summary of those topics is below:

- 1. Safety concerns at the intersection of Terrace Drive and HWY 550 for vehicles, pedestrians, and cyclists.
- 2. Lack of secondary access to Vista Terrace Subdivision.
- 3. Reduce the proposed density and number of accessory dwelling units.
- 4. Visual impact of development along the ridgeline.
- 5. Preference to connect to sanitary sewer services to serve this project rather than OWTS.
- 6. The project is located outside of the Initial Growth Boundary (IGB) as identified in the 2019 Master Plan.
- 7. CPW's concerns with the impact the development could have on wildlife habitat.
- 8. Concerns brought up in the Four Winds Sketch Plan, 2nd Review Comments letter.
- 9. Other topics and discussions that were brought up and identified in the hearing.

JANUARY 6TH UPDATE

Since the August meeting, the development team and Town staff have been working to address comments brought up in the August meeting. Despite efforts, the applicant team and town staff were unable to fully address all items. In an email received on January 4, 2023, the owner's representative requested continuance of the application to the Planning Commission's January 31, 2023 meeting.

Additionally, the Town has received multiple public comments associated with this application. The individuals who provided comments are listed below and their comments are attached to this staff report.

- 1. Stephen McComb, December 29, 2022
- 2. Pam Foyster, December 29, 2022
- 3. Matt Gawlowski, December 30, 2022
- 4. Stephen McComb, December 31, 2022
- 5. Jack and Karen Kay, January 3, 2023

STAFF RECOMMENDATION

Staff agrees with the applicant's request to continue the public hearing for this application until the Planning Commission's regular meeting on January 31, 2023.

ATTACHMENTS

- 1. Request to Continue
- 2. Public Comments





TJ Dlubac <tdlubac@planstrategize.com>

Four Winds Subdivision Continuance

1 message

Christopher Hawkins <chris@alpineplanningllc.com>

Wed, Jan 4, 2023 at 1:02 PM

To: Preston Neill <pneill@town.ridgway.co.us>

Cc: TJ Dlubac <tdlubac@planstrategize.com>, Eric Faust <Eric@phillytrans.us>, Tim Currin <tim@ouraybrokers.com>, "dquigley@buckhornengineering.com" <dquigley@buckhornengineering.com>, "reed@dwmk.com" <reed@dwmk.com>

Preston,

Please accept this email as my client's formal request to continue the Four Winds Subdivision to the January 31st Planning Commission meeting.

Thank you.

Chris Hawkins, AICP

Alpine Planning, LLC

(970) 964-7927

Alpineplanningllc.com





This electronic mail transmission and any accompanying documents contain information belonging to the sender which may be confidential and legally privileged. This information is intended only for the use of the individual or entity to whom this electronic mail transmission was sent, as indicated above. Any disclosure, copying, distribution, or action taken in reliance on the contents of the information contained in this transmission is strictly prohibited. If you have received this transmission in error, please delete the message and notify us by calling 970.964.7927 or emailing chris@alpineplanningllc.com

Stephen R. McComb 290 Terrace Drive PO Box 1247 Ridgway, CO 81432

Mr. Preston Neill Town Manager Ridgway, CO 81432

RE: Four Winds Proposed Development Water Issues

Dear Mr. Neill,

I would appreciate it if you would add this letter into the packet designated for the January 30th Planning Commission meeting under the Four Winds project agenda item. I realize that I have sent this question to you in the past rather informally, but I wanted to make sure it was included in the project meeting packet.

Water Capacity

Background:

The Vista Terrace neighborhood is on town water, and the proposed development plans on using town water as well. To support the neighborhood, the town pumps town water to a water tank on the top of the ridge NE of the Vista Terrace Subdivision. The developer will enhance the water capacity by building a second water tank up on the ridge that is tied into the original tank.

<u>Issues</u>:

In reviewing the Four Winds Subdivision Sketch Review dated June 27, 2022, I think I may have found what looks like
a mathematical error regarding the new water storage tank size. On page 6 the following calculation is made
regarding the proposed total water tank capacity being proposed:

Water Tank Sizing Calculations

20 lots x 350GPD x 1.6 PeakDayFactor = 11,200 GPD 11,200 GPD + 750 GPM x 60 minutes = 56,200 Gallons 56,200 Gallons - 18,000 Gallons of Existing Town Storage = 38,200 Gallons Required

My questions are:

- a. Why was the estimated water usage per lot per day reduced from 450 GPD (April 2022 Sketch Plan) down to 350 GPD (June 2022 Sketch Plan). This is a 22% reduction.
- b. Why is the 18,000 gallon existing tank storage taken away from the 56,200 Gallons in this calculation? It seems to me that you would use the 56,200 Gallons as the amount needed on top of the existing 18,000 Gallons.
- 2. What about water pressure needed to support the above mentioned full build out? I have been told that the pumping station currently in place uses a 2 phase system. Is adding in 120+ people to this system going to overtax the pressure system?
- The Vista Terrace Subdivision currently pays a 10% surcharge on our water bill for our unique water supply system. Any increases in this surcharge mandated by the Town of Ridgway to support additions and maintenance of this water system should be paid by the developer, not the current residents.

Respectfully,

Stephen R. McComb 290 Terrace Drive 602-770-6199 smccomb63@gmail.com

Comments to the Planning Commission regarding Four Winds Proposal

To the members of the Planning Commission,

I am writing in regards to the updated proposal for the Four Winds subdivision. I will focus on the Master Plan, and their unfortunate interpretation of the Initial Growth Boundary (IGB).

The IGB is intended to promote "urban levels of development" in the core of Ridgway, with higher density close to roads and amenities. I have witnessed urban and suburban sprawl in other small mountain towns, and it creates increase in traffic and congestion. Growth is inevitable, and the Master Plan is a sound document that many in our community contributed to. We will face additional traffic and infrastructure challenges as our population grows, but we are not ready for that level of complexity.

I do not appreciate the aggressive tone of the developers referring to "takings of property rights". If they are threatening a lawsuit, that is contrary to the culture of this community, and not welcome here. The developers want to blend the UGB and IGB, in order to give the impression that they are the same thing. I have witnessed multiple developments where developers bulldozed and bullied their way into a town, with profits as their only motive. In most cases, the neighborhood suffers. I submit that the Lena Street project did not meet expectations, and certainly does not blend in with the town, or support workforce housing at an affordable level.

The developers are comparing their project to the River Sage subdivision. That is a completely different design, and not a valid comparison to the Four Winds Project. River Sage homes are spread out, with large amounts of space between houses, allowing for visual impression of open space. While the Four Winds plan shows adequate size and open space on paper, the lots are much smaller, clustered together, and create a high density footprint that is incompatible with the rest of the Vista Terrace neighborhood. Additionally, the number and size of the proposed houses compound the visual disturbance, as well as an increase in traffic on the only road in or out of Vista Terrace.

The property has always been assumed to be future development; that is not in dispute. It is the responsibility and job of the Commission to help Ridgway grow as the citizens have stated their values in the Master Plan. To borrow the developer's own quote from the 2011 Land Use Plan:

"Promote a sustainable and *complementary* (italics added) development pattern with the rural landscape outside of the Initial Growth Boundary, but within the Urban Growth Boundary/Urban Growth Management Area and Area of Influence."

The updated Master Plan clarifies this to reflect the needs and values of the residents:

GOAL COM-1: Maintain Ridgway as a community that is accessible to a range of income levels, ages, and households. POLICY COM-2.3: Resident-Occupied Housing Support strategies that help maintain resident occupied housing in Ridgway, rather than housing occupied by secondhome owners.

POLICY CHR-1.1: Neighborhood Character Encourage the development of neighborhoods that enhance and reflect the character of Ridgway through quality design, cohesive materials, and integration of natural features. GOAL CHR-3: Promote Ridgway's identity as a ranching and agricultural community and preserve the rural character of landscapes surrounding Ridgway.

Comments to the Planning Commission regarding Four Winds Proposal

The developments currently underway in Ridgway will help the community meet two goals: workforce housing, and development/growth in logical areas that are capable of handling increased density and traffic. I think the Planning Commission should hold off on all multiple dwelling development for another six months, or until the new projects have time to mature and see what needs have been met, and what is needed in the next few years.

An option for the developers would be to purchase a different parcel in the county, or another parcel of the Endicott estate (east or south side) so they could spread out and be less constrained by geography and a small finite space. They would have to install their own infrastructure and would have less impact on town resources.

On a different note, the proposed emergency exit east of Vista Terrace is a joke. It would not be plowed, and no one would be able to get up it in the winter. Many would not have the vehicle to get up and over even in the summer unless it was a maintained road.

Thank you for your consideration on this important project.

Respectfully submitted,

Pam Foyster 435 Terrace Drive Ridgway, CO 81432



TJ Dlubac <tdlubac@planstrategize.com>

RE: Four Winds subdivision

1 message

Preston Neill cpreill@town.ridgway.co.us>
To: Matthew Gawlowski <mattgawlowski@icloud.com>
Cc: TJ Dlubac <tdlubac@planstrategize.com>

Sat, Dec 31, 2022 at 8:10 AM

Hi Matt,

I'm confirming receipt of your email. Thank you for taking the time to pen your thoughts and concerns related to the proposed Four Winds Subdivision. Your letter will be included in the Planning Commission packets for both the January 10th and January 31st Planning Commission meetings.

All the best,

Preston Neill Ridgway Town Manager 970-626-5308 ext. 212 (O) | 970-318-0081 (C) pneill@town.ridgway.co.us www.colorado.gov/ridgway

-----Original Message-----From: Matthew Gawlowski <mattgawlowski@icloud.com> Sent: Friday, December 30, 2022 11:29 AM To: Preston Neill <pneill@town.ridgway.co.us> Subject: Four Winds subdivision

Hi Preston,

I own a house in Vista Terrace, and am writing regarding the latest proposal by Four Winds for development in this neighborhood.

1. Since the development would, for all intents and purposes, be an extension of this neighborhood, it should be required to comply with all covenants and amendments that govern this neighborhood. Any development plan should specifically reference those documents and require compliance.

2. I am concerned about the wildlife impact (I doubt our elk will return if that subdivision is built!) and do not view the proposed conservation easement as a fair tradeoff. However, I recognize the right to develop land, and just ask that above average steps be taken to mitigate any impact.

3. No one is happy with the 550 interchange and this development will surely make that worse. I think lowering the speed limit to 45mph there will go a long ways towards addressing that, though I recognize this is out of the city's hands. I ask that, if this development proceeds, both the city and developer petition CDOT for an urgent review and change of speed limits and additional signage along that section.

4. I am concerned about water pressure, especially in event of emergency, and ask that the city place stringent requirements on the developer on this detail.

5. The proposed emergency egress has the *potential* to address the need of a greatly expanded neighborhood, but I fear as written, it will fall short. There are some specific changes I hope the city would consider requiring:
This egress must be built and maintained to accommodate ANY street legal vehicle in the neighborhood (it should not require high clearance or four wheel drive, for example).

- This egress must be maintained year round (at developer's expense, not the existing Vista Terrace residents) to ensure its function as an emergency egress. I suspect that would entail, at a minimum, grading and snow removal (especially as it appears to be on a forested north-facing slope?).

- To ensure compliance with maintenance requirements and the road's suitability for use in emergencies, the entirety of the egress should be open to pedestrian traffic at all times. This would allow us to have peace of mind that the road is maintained and ready for use, should an emergency arise.

I fear that without these conditions existing in a legally-binding form, this emergency egress would be a short term solution at best, and not serve the neighborhood in the future if/when it's actually needed. I also feel these conditions would not place an undue burden on the developer, as the future maintenance costs could be shared by the land owners in the Four Winds development and road deterioration would not be excessive for something only open to infrequent pedestrian traffic (just minimal erosion due to precipitation and runoff).

Thanks, Matt Gawlowski Stephen R. McComb 290 Terrace Drive PO Box 1247 Ridgway, CO 81432

Mr. Preston Neill Town Manager Ridgway, CO 81432

RE: Four Winds Development Actions Response Letter Dated November 20, 2022

Dear Mr. Neill,

I would appreciate this letter be added to the packet for the upcoming January 31st Planning Commission meeting under the Four Winds agenda item.

I have concerns about the following Four Winds responses to action items generated from the August 30th Planning Commission meeting:

1. Terrace Drive – US Highway 550 Intersection

Background:

Currently, there is a single entrance-exit from the Vista Terrace Subdivision. This intersection is already a little tentative based on entering traffic that is moving in both directions at 60 miles plus per hour. The proposed development plans on using this one access/egress, and have no plans to create another entrance-exit from this neighborhood, even though their plans call for an additional 120 people (not including ADUs) to be based in the neighborhood. The developer funded traffic study indicates there is no need for further infrastructure at the highway intersection, but suggests the highway speed be reduced to 45 MPH for safety purposes.

Response Letter Issue:

After attending the August 30th Planning Commission meeting, it was apparent that Four Winds was directed to work on a full secondary access/egress from the neighborhood to relieve the danger and congestion from the current single access/egress. Four Winds has responded to this action with only a "rough, emergency only" egress to be used to offset a fire emergency. This does <u>not</u> meet the intent of the action from the August 30th meeting where Four Winds was directed to come up with a secondary access/egress that would relieve the serious congestion at the highway intersection brought about by a 30% increase in the number of lots in the neighborhood. The proposed open space bike/walking trail exiting at this very highway intersection only exacerbates the need for a true secondary access/egress. The increased congestion at the highway intersection brought about by the proposed development will put extra pressure on people gaining access or exiting to take chances they wouldn't normally take in order to not hold up people behind them.

I cannot over emphasize enough just how concerned the neighborhood is regarding this subject. This intersection will become a nightmare for those that live here if this development goes through as planned. No one wants to have a horrific accident occur at this intersection so I implore you to ensure that a true, secondary access/egress requirement is mandated as part of this application. In this regard, I can think of no higher calling a local government has than the protection and safety of its citizens.

Note: See recent accident photo on next page.



Intersection Accident on 12/18/22

2. Use of Septic Systems

The addition of 20 septic systems in the Four Winds development is a concern based on the slope of the terrain and the soil type. The fear is that there will develop unwanted drainage at the bottom (south side) of the project. See the attached picture on the next page. This was taken by Jack Fay at the beginning of October 2022, after a rainstorm. The result of the storm was standing water on the south side of Terrace Drive located at the bottom of the Four Winds proposed development. This standing water lasted for weeks. The question is can you add 20 septic systems to this location and not turn the low point into a large, unwanted swamp? What will this drainage do to the stability of Terrace Drive at this location?



Open Water Caused by Rainfall Only

3. Vistas Visual Impact

Background:

Ouray County's Board of Commissioners developed Visual Impact Regulations back in 1986. The document that currently exists was revised in 2019. The purpose of the document is to preserve the scenic beauty, rural setting, and the dominating influence of the natural environment of Ouray County. If this document is upheld, I believe that this proposed development, especially the northwestern lots, will not meet the requirements of this document. The homes on these lots will be easily visible from Highway 550 within 1.5 miles of the ridge.

Response Letter Issue:

Future homes on lots #4-7 will be visible from Highway 550, and as a result do not comply with the intent of the Ouray County's Visual Impact Regulations. They will impact the natural beauty of the ridgeline as one enters Ridgway from the north. The developer's contention that these lots will not break the blue skyline based on a higher ridge to the east does not change the fact that they will ruin that natural ridgeline closer to the highway. The developer also states that because this development is located in the town limits of Ridgway, they are not bound by the Ouray County regulation. If Ridgway truly considers itself a progressive community, as outlined in the 2019 Master Plan, I don't see how we cannot abide by such a logical document. If not, I can assure you that more "McMansions" will be built to maximize their views, but undermine the beauty of our location. The argument that several current homes in Vista Terrace are visible from Highway 550 south of town does not have merit because policies and regulations evolve over time, and you can't rationalize current construction by what was done in the past.

4. Reducing Number of Lots and ADU's

The developer has reduced the number of ADU's allowed from 20 down to 5. It is important to note that the adding in ADU's was a recommendation only to lot buyers, and not a requirement. This action item of finding out a way to reduce the overall number of lots in this development to prevent a suburban type clustering of homes, as well as reduce the impacts on this location in general is still open. The developer's response to the action of reducing the number of lots in the development was that this would make it "financially infeasible". In my opinion, this financial infeasibility should not be looked at as the Town's issue to resolve, but as a Planning Commission action request denied by the developer.

5. Wildlife

Background:

The proposed development is right in the middle of a wildlife winter grazing corridor. I have watched this for 6 years and there is no denying that fact. Deer, elk, wild turkeys, coyotes, and other smaller animals use this corridor consistently to graze, sleep, and make their way across the highway to the river for water. The analysis letter from CPW indicates that there is no doubt that this wildlife grazing area will be impacted. The proposed development states they will not allow perimeter fencing in order to allow wildlife access through the corridor. However, they also are going to mandate dog fences to stop them from chasing wildlife.

Response Letter Issue:

Even though CPW indicated that they will not block this development due to wildlife impacts, they also state that wildlife will most certainly be impacted in this corridor. In my opinion, the concept of animal fencing as a mitigation for wildlife disruption is not valid because wild animals are afraid of dog barking as well as being chased, and the fences themselves, as well as the homes, act as a barrier to wildlife traffic through this corridor. There is no indication by the developer of limiting the number of pets per lot, and this is problematic. This neighborhood loves the wildlife we are blessed to see on an ongoing basis. It is one of the aspects of living in this location that makes it so special. Forcing this development into this neighborhood will dramatically impact the feel and flavor of Vista Terrace from a wildlife point of view, as well as general aesthetics. The developer's statement that he plans on turning 500 acres of his land elsewhere into a conservation easement that is highly suitable for elk is admirable. However, he is not willing to tie it to this development so it loses its power to offset loses imposed by the Four Winds development. It is also pertinent to note that the developer would receive financial benefit from such a conservation easement.

6. Initial Growth Boundary (IGB):

This project is outside of the Ridgway IGB, which the town, via the Ridgway Master Plan, encourages housing development for the next 10-20 years. The developer is taking a rather cavalier attitude towards this concern, and attempts to lecture the town on the legalities of property rights, as well as the <u>"arbitrary</u>" placement of this location as outside of the IGB. In my opinion, the town does have the right to evaluate a project on a host of issues including it being outside of the IGB.

The following personal comments are not directly related to the developer's responses to the August 30th action items, but I feel are applicable to this project in general:

- A. <u>The Vista Terrace neighborhood overwhelmingly does not want this development to come to fruition.</u> I base this opinion on the number of letters the town has received from residents of this neighborhood regarding the project, the large attendance at a neighborhood meeting on this subject earlier this year, neighborhood attendance at the Planning Commission meetings on this project, and conversations and email correspondence during 2022. It is a very unpopular project that will change forever the open and rural feel of the neighborhood. The neighborhood also has a number of critical issue concerns associated with safety, water capacity and pressure, density, visual impacts, drainage, road damage, and wildlife.
- B. The developer has stated that this project is "marginally profitable". As a result, he consistently evaluates issues and action items associated with making this project a solid and safe development that is harmonious with the surroundings in this financial light. He has adopted an "I can't because" attitude in order to make the project feasible. Three examples of this are: first, the safety concerns surrounding not supplying a full secondary access/egress from the neighborhood...he can't because the project is surrounded by private land and it would be too expensive. Second, the request to reduce the number of lots...he can't because it is economically infeasible. Third, the project is outside of the IGB...the developer says it doesn't matter because the town doesn't have the right to prohibit this project on those grounds.

In summary, I believe the town has the right to reject this proposed development based on the above issues. In fairness to all concerned, if the full secondary access/egress cannot be included in this application, then it should be rejected to save the town and the developer time and money.

Once again, I very much appreciate the opportunity to give my input to the Town of Ridgway Planning Commission!

Respectfully,

Stephen R. McComb 290 Terrace Drive 602-770-6199 / smccomb63@gmail.com



TJ Dlubac <tdlubac@planstrategize.com>

Re: Four Winds Subdivison

1 message

JACK KAREN FAY <jkrfay@msn.com> To: Preston Neill <pneill@town.ridgway.co.us> Cc: TJ Dlubac <tdlubac@planstrategize.com>

Sounds great, thank you!

From: Preston Neill <pneill@town.ridgway.co.us> Sent: Wednesday, January 4, 2023 5:26 AM To: JACK KAREN FAY <jkrfay@msn.com> Cc: TJ Dlubac <tdlubac@planstrategize.com> Subject: RE: Four Winds Subdivison

Hi Jack and Karen,

I'm confirming receipt of your email and photos. Thank you for taking the time to pen your thoughts and concerns related to the proposed Four Winds Subdivision. Your email and photos will t

All the best,

Preston Neill

Ridgway Town Manager


970-626-5308 ext. 212 (O) | 970-318-0081 (C)

pneill@town.ridgway.co.us


www.colorado.gov/ridgway




From: JACK KAREN FAY <jkrfay@msn.com> Sent: Tuesday, January 3, 2023 2:45 PM To: Preston Neill <pneill@town.ridgway.co.us> Subject: Re: Four Winds Subdivison











1/6/23, 12:29 AM

Hi Preston, Happy New Year,

Here are a few pix of the wildlife as we have enjoyed over the years, here in Vista Terrace.

The herd of elk is just below Steve McCombs house where lot #2 might be, the nice bucks are just north of my home, where lot 14 will be and the other pi We are hoping that the planning committee will reject this Four Winds subdivision, because of the water issue --the traffic issue and the loss of tranquility. It is almost the middle of winter now and there is not very much snow on the Sneffles Range,---and we all know that water is the main issue here in Vista 7 This is not the place for a high density development.

Thank you,

Jack and Karen Fay

From: Preston Neill cneill@town.ridgway.co.us>
Sent: Wednesday, May 25, 2022 11:46 PM
To: JACK KAREN FAY jkrfay@msn.com>
Subject: RE: Four Winds Subdivison

Jack and Karen,

I'm confirming receipt of your email. Thank you for taking the time to pen your thoughts and concerns as they relate to the proposal for Four Winds Subdivision. Your email will be included in t website on Friday afternoon.

All the best,

Preston Neill, Town Manager

970-626-5308 ext. 212 (O) | 970-318-0081 (C)

pneill@town.ridgway.co.us

www.colorado.gov/ridgway



From: JACK KAREN FAY <jkrfay@msn.com> Sent: Wednesday, May 25, 2022 5:13 PM To: Preston Neill coup

Preston, In regards to the proposed "Four Winds" Subdivision, We are very concerned about the water, increased traffic and wild life.

Please give these issues your utmost attention.

Thank you,

Jack and Karen Fay

475 Terrace Dr

Ridgway Co

AGENDA ITEM #2 & #3



То:	Town of Ridgway Planning Commission
Cc:	Preston Neill, Ridgway Town Manager
From:	TJ Dlubac, AICP, Community Planning Strategies, Contracted Town Planner
Date:	January 6, 2023
Subject:	Plat Amendment and Variance Requests for 702, 704, and 706 N. Laura Street for the January 10 th Planning Commission meeting.
APPLICATION IN	FORMATION
Requests:	 A variance to allow a side setback of 0 feet for the south side of Lot 15A. (Sec. 7-3-21(A) of the RMC)
	2) A variance to allow a side setback of 0 feet for both sides of Lot 15B. (Sec. 7-3-21(A) of the RMC)
	 A variance to allow a side setback of 0 feet for the north side of Lot 15C. (Sec. 7-3-21(A) of the RMC)
	 Approval of a plat amendment for the Amended Plat of Lot 15, Parkside Subdivision. (Sec. 7-4-5(C) of the RMC)
Legal:	Lot 15, Parkside Subdivision
Address:	702, 704, and 706 N. Laura Street, Ridgway CO 81432
General Location	North of N. Railroad Avenue and east of and adjacent to N. Laura Street
Parcel #:	430508414015
Zone District:	R Low Density Residential District
Current Use:	Three single-family attached townhomes (triplex)
Applicant:	Amanda Gerhardt, Executive Director of Habitat for Humanity of the San Juans
Owner:	Habitat for Humanity of the San Juans

PROJECT REVIEW

BACKGROUND

The parcel was originally platted as Parkside Subdivision (Rec. #197315). This plat created 23 residential lots and one open space tract. Six of the lots created were noted as allowing two or three singlefamily equivalents. A notation on Lot 15 states "3 Single Family Equivalents". This note is meant to allow up to three single family dwelling units on the parcel. The zoning district, R Low Density Residential, does not allow more than two dwelling units as a use by right and three units is a Conditional Use Permit. Therefore, the intent of this statement was to allow three units on this one parcel.



Figure 1. Zoning and property location

Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 2 of 10

Lot 15 is bordered on two sides by streets; Laura Street to the west and North Railroad Street to the south. Furthermore, there is a drainage and utility easement (Rec. #197315) overlaying the southern 50' of this lot, and a utility and drainage easement (Rec. #197315) along the eastern ten feet of the lot.

Lot 15 has a total lot area of 21,529 square feet (0.494 ac.). The minimum lot size for the R District is 6,000 square feet for single family and duplex uses and 10,000 square feet for all other uses.

The applicant received a building permit in 2020 (BP2020-038) for three single-family dwelling units, a triplex, on Lot 15. The project has been under construction since the permit was issued and is nearing completion. The owner would like to create three separate parcels to allow each Townhouse unit to be sold separately. Therefore, a plat amendment is needed to create three separate parcels. Additionally, since the R Zone District has minimum side setbacks, and no provisions to allow for a townhome lot, variances for reduced minimum side setbacks would be needed to allow for zero-foot setbacks along the interior property lines dividing the dwelling units.


Additionally, Note 6 of Parkside Subdivision states Lot 15 as having affordable housing provisions and requiring three single-family dwelling units. Habitat for Humanity, to the Town's knowledge at this time, is in compliance with these provisions.

Furthermore, Plat Note 7 of Parkside Subdivision, as amended by Amendment 1 to the Parkside Subdivision, Reception #221300, clarified that ADUs are not allowed on Lot 15 and that three units are required. The note further explains that no occupancy permit shall be issued unless all three units are under construction. Again, the provisions of the amended note 7 are complied with by the application and the owner.

REQUESTS

The applicant wishes to further Lot 15, Parkside subdivide Subdivision, into three separate lots so each of the three units permitted on the Lot 15 pursuant to Note 7 may be sold separately. The three townhome units have already been permitted and constructed, and this request is to create a townhome plat that allows each unit, and the associated real property of the lot, to be sold individually.

Furthermore, since the shared party wall property lines do not meet the minimum side setbacks of the R Zone District, variances to reduce these setbacks to 0' are being requested concurrently.





Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 3 of 10

NOTICES AND PUBLIC COMMENTS

The applicant has submitted a hearing application, associated fees, final plat materials, and other required support materials for this public hearing to the Town. The property and hearing have been noticed and posted by the Town in accordance with RMC §7-3-23(D).

Property owners directly to the west of this property have reached out to Town staff to inquiry into the applications. During a conversation with a neighbor, Karen Day, it was mentioned that the property owners were installing a privacy fence across the drainage easement to the east of Lot 15 (west of Ms. Day's home). The concern of impeding water flows in the drainage easement was discussed. <u>NOTE:</u> To address this concern, staff has made a comment in the review letter that no fence can be constructed to impede the flow of the drainage easement. Furthermore, staff is requesting, in the review letter, that a note be placed on the plat stating that the follow of any drainage easement shall not be impeded by any construction, installation, or improvement.

CODE REQUIREMENTS

RMC §7-3-15 DIMENSIONAL AND OFF-STREET PARKING REQUIREMENTS

(A) Dimensional Requirements: Tabulated Requirements for Uses by Right.

Zone/Use	Width	Lot Size	Max. Lot		Set	backs		Hoight
Zone/Use	wiath	LOI SIZE	Coverage	Front	Rear	Side	Corner	Height
R / Single-Family	<i>50′</i>	6,000sf	50%	15′	8'	5′	7.5′	27'
R /All Others	50′	10,000sf	40%	15′	8'	8'	7.5′	27'

RMC §7-3-21 VARIANCES AND APPEALS

- (A) The Planning Commission may grant a variance from the Dimensional Requirements, Sign Regulations, Design or Performance Standards, and other provisions of these regulations not related to "use", and excluding Off-Street Parking Requirements, following the review procedure of Subsection 7-3-23, provided that the criteria of this Subsection will be met. Variances shall be granted only if all the following criteria are met:
 - (1) There are practical difficulties or unnecessary hardships in the way of carrying out the strict letter of the zoning ordinance, and
 - (2) The spirit of the ordinance will be observed, the public health, safety, and welfare secured, and substantial justice is done by granting the variance.

RMC §7-4-10 Replats and Amended Plats

(B) Amended plats of subdivision plats previously approved by the Town, or parts of such plats, which do not make or require a material change in the extent, location, or type of public improvements and easements provided, and are consistent with the Design Standards of these Regulations may be submitted, approved and recorded in accordance with the provisions of this Subsection in lieu of other procedures provided for subdivision by these regulations, if all required improvements are in and available to serve each lot.

RMC §7-4-5(C) FINAL PLAT:

RMC §7-4-5(C)(8)(b): The Planning Commission shall determine the following are met in order to recommend approval, with or without conditions, of the replat to the Town Council:

(i) The Town has received a reproducible mylar properly executed by all parties except Town officials, the original subdivision improvements agreement properly executed by the Subdivider



Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 4 of 10

accompanied by required security, and copies of properly executed corporate documents and covenants;

- *(ii)* Compliance with all Planning Commission conditions of approval except those subject to a good faith dispute;
- (iii) Payment of all costs due to date pursuant to 7-4-12(B), recording fees, development excise taxes, tap fees and other amounts due the Town.

ANALYSIS

2019 MASTER PLAN & FUTURE LAND USE PLAN

This parcel is identified as *Single-Family Neighborhood* on the Future Land Use Map of the 2019 Master Plan. This anticipates the following land uses and development patterns:

Maximum Density / Height	2 to 8 du/ac; 2.5 stories
Primary Uses:	Single-family homes and duplexes.
Supporting Uses	Parks and recreational facilities, community gardens, and civic and government facilities. Accessory dwellings where permitted.
Characteristics	 Single-Family Neighborhoods are made up primarily of single-family homes, with a small number of duplexes and smaller multi-family building mixed in, oftentimes near transitions between different land uses. Accessory dwelling units are encouraged where permitted. The neighborhoods should incorporate open space into the overall design to provide recreational opportunities to residents and/or preserve wildlife habitat or environmentally sensitive lands. While streets may not follow a grid pattern, connections to existing adjacent developments or areas should be provided for pedestrians and bicyclists to promote walkability.

This property and abutting properties on the north, east, and west are designated as Single-Family Neighborhood on the Future Land Use Plan. Property to the south is designated Employment.

The requests are in general conformance with the recommendations, goals, and policies of the 2019 Master Plan. Below are some highlights:

- <u>Policy COM-1.1: Workforce Housing</u>: Partner with surrounding jurisdictions to provide housing for those employees working in Ouray County.
- <u>Policy COM-1.2: Private Sector Responsibilities:</u> Acknowledge the role of the private sector (and nonprivates) as a necessary partner in addressing the community's affordable and workforce housing needs.



Figure 3. Future Land Use Plan

• <u>Policy COM-1.3: Public-Private Partnerships:</u> Explore opportunities to partner with private and non-profit developers on the construction of affordable and workforce housing.



Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 5 of 10

- <u>Goal COM-2</u>: Encourage a diversity of housing options that meet the needs of residents.
- <u>Policy Com-2.1: Diversity of Housing Types:</u> Encourage the development of a variety of housing sizes, types, tenure types, densities, and prices.
- <u>Policy COM-2.2: Housing Options:</u> Support the development of a range of housing options in Ridgway, including but not limited to townhomes.
- <u>Policy COM-2.3: Resident-Occupied Housing</u>: Support strategies that maintain residentoccupied housing in Ridgway.
- GOAL CHR-1: Support vibrant, diverse, safe, and well-connected neighborhoods.
- <u>Policy CHR-1.1: Neighborhood Character</u>: Encourage the development of neighborhoods that enhance and reflect the character of Ridgway through quality design.
- <u>Policy CHR-1.2: Neighborhood Walkability and Bikeability</u>: Enhance walkability and bikeability within existing neighborhoods and between other areas of town.
- GOAL GRO-1: Manage growth and development in order to maintain Ridgway's small town character, support a diverse community, and create employment opportunities.
- <u>Policy GRO-1.1: Directed Growth:</u> Direct growth to occur in a concentric fashion from the core outward, in order to promote efficient and sustainable Town services, strengthen the Historic Town Core and existing neighborhoods, and preserve the rural character of the surrounding landscape.
- <u>Policy GRO-1.4: Underutilized Areas</u>: Encourage infill development on vacant parcels and the redevelopment or adaptive reuse of or underutilized parcels or structures in the Historic Town Core of other areas where infrastructure and services are already in place.
- <u>Policy GRO-1.5: Design of New Development</u>: Ensure new development and infill/redevelopment is compatible with the surrounding area or neighborhood.
- *Policy GRO-1.7: Transitions:* Ensure smooth transitions and/or compatibility between distinct land uses.
- <u>Goal GRO-2</u>: Ensure public infrastructure, utilities, facilities, and services are sufficient to meet the needs of resident's and businesses as the town grows.
- <u>Policy GRO-2.2: Adequate Public Facilities:</u> Proposed development should demonstrate that town facilities and infrastructure have the capacity to serve the development.
- <u>Policy GRO-4.7: Connectivity of New Development</u>: Encourage new development to connect to existing biking and pedestrian facilities throughout the town.

LAND USES

The property currently has a triplex. The triplex / townhouse is allowed by Conditional Use Permit in the R Low Density Residential District and since the plat notes explicitly allow for the development of Lot 15 with three dwelling units, the uses are permitted on this property.

DIMENSIONAL STANDARDS

Section §7-3-15(A) sets forth the required dimensional standards which shall be met for various uses within each zone district. For the R Low Density Residential District, the following standards apply to uses other than single-family and duplex uses. Therefore, the following apply to the overall lot:



Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 6 of 10

Standard	Requirement	Overall
Min. Lot Width	50′	145.63′
Min. Lot Size	10,000sf	21,529sf
Max. Lot Coverage	40% <i>(8,611.6sf)</i>	15.7% <i>(3,369.58sf)</i>
Min. Front Setback	15′	16.76′
Min. Rear Setback	8′	22.31′
Min. Side Setback	8′	NW: 8′ SE: 55′
Max. Side on Corner Lot	7.5′	N/A
Structure Height	27′	~24.5′

The following table shows the dimensional standards for the single family dwelling lots and how the proposed lots compare to those standards.


Standard	Poquiromont	Proposed					
Standard Min. Lot Width Min. Lot Size Max. Lot Coverage Min. Front Setback Min. Rear Setback	Requirement	Lot 15A	Lot 15B	Lot 15C			
Min. Lot Width	Overall width	39.22′	37.17′	69.28′			
Min. Lot Size	Overall area	3,839sf	3,114sf	15,514sf			
Max. Lot Coverage	50%	~29.8%	~36.7%	~7.4%			
Min. Front Setback	15′	N. Laura: 16.76'	N. Laura: 17.92'	N. Laura: 20'			
Min. Rear Setback	8′	22.31′	25.37′	28.36′			
Min. Side Setback	8′	N: 8′ S: 0′	N: 0′ S: 0′	N: 0′ S: 55′			
Max. Side on Corner Lot	7.5′	N/A	N/A	55′			
Structure Height	27′	~24.5′	~24.5′	~24.5′			

ACCESS & PARKING

All three townhome lots will have direct access via individual private driveways onto N. Laura Street. Each unit has a garage and room for at least one parking space in the driveway, not impeding the sidewalk. The RMC requires 2 spaces per single-family or duplex unit and 1 space per each other type of dwelling unit, therefore, this project provides the minimum required off-street parking.



Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 7 of 10



UTILITIES


No proposed changes to existing utilities have been proposed or are required by this request. All improvements are already in place.

ARCHITECTURAL REVIEW

Sec. 6-6-5 of the RMC sets forth architectural standards for residential uses. This project must meet the following standards:

(1) Provide relief and contrast to the building's front and side street elevations incorporating solids and voids to break up plain wall surfaces.

There are multiple relief and contrasts in the building's front elevation as shown in the image of the articulations and setbacks of the front façade.



(2) Provide variation of building mass and height, responding to the existing development context and adjacent zoning districts.

In addition to the articulations and setbacks in the front façade, the building massing is broken up with materials and additional features as indicated on the front elevations below.



Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 8 of 10




Figure 6. Front Elevation

(3) Garage doors shall not dominate the front elevation.

As can be seen in the elevation above, garage doors do not dominate the front elevation.

(4) No two detached Single-family dwellings, Duplex dwelling structures, Townhome, Triplex dwelling structures, or Fourplex dwelling structures of substantially similar elevations shall be located adjacent to each other.

The design elements of the front façade change for the middle unit to provide a change in elevation between the middle and end unit.

LANDSCAPING

The applicant included the required landscape plan with the application materials. This project was permitted before the current landscape regulations. However, for purposes of understanding how the proposed landscaping plan fits with the regulations, the following table is provided:

	Lot	15A	Lot	15B	Lot	15C	Overall
	Required	Provided	Required	Provided	Required	Provided	Overall
Lot Size	3,83	39sf	3,1	L4sf	15,5	14sf	22,467sf
Min. Req. Landscape Area (50%)	1,919.5sf	Unknown*	1,557sf	Unknown*	7,757sf	Unknown*	11,233.5sf
Min. % Live ground cover (20%)	384sf	Unknown*	312sf	Unknown*	1,552sf	Unknown*	2,246.7sf
Min. % non-live ground cover (30%)	576sf	Unknown*	468sf	Unknown*	2,322sf	Unknown*	3,370sf
Min. # of Trees (1 per 2,000sf)	1	3	1	1	4	7	6
Min. # of Shrubs (1 per 3,000sf)	1	10	1	11	3	20	4
Front Yard Landscaping (25%)	480sf	Unknown*	390sf	Unknown*	1,940sf	Unknown*	2,809sf

* These calculations are unknown because the project was originally developed and submitted under the previous landscape regulations and with the recent updates to the standards, these calculations were needed.

All in all, following the review of the submitted landscaping plan, it does appear to meet the intent of the landscape regulations and the RMC, therefore, staff is supportive of the landscape plan as submitted with a few recommendations to ensure no turf is being used and that the minimum non-live ground cover is being provided. These are mentioned in the attached comment letter and can be discussed further with the applicant and Planning Commission, if needed.



Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 9 of 10

STAFF RECOMMENDATION

Following a review of the application materials against the applicable RMC requirements, staff recommends approval of the variance requests and the amended plat with conditions intended to tie each of the approvals together so no one request is approved unless all are approved. The recommended motion with alternatives is provided in the next section of the staff report.

The proposed order of motions is purposeful to ensure a clean and clear record. Therefore, the motions shall be made and acted upon in the order listed below.

RECOMMENDED MOTIONS - VARIANCES

Request #1 -Lot 15A: "I move to approve an 8-foot variance to allow a zero-foot side setback on the south property line for Lot 15A, Amended Plat of Lot 15 Parkside Subdivision in the R Low Density Residential District finding that the criteria set forth in Section 7-3-21 of the RMC have been met and with the following conditions:

- 1) Address all comments in the Planning Review Comment Letter dated January 6, 2023, to the satisfaction of Town Staff prior to the Amended Plat being recorded with the Ouray County Clerk and Recorder.
- 2) The Ridgway Town Council approves the Amended Plat of Lot 15, Parkside Subdivision."

Alternative Motion:

"I move to deny the request to reduce the side setback on the south property line for Lot 15A, Amended Plat of Lot 15 Parkside Subdivision in the R Low Density Residential District finding that the criteria _____ of the approval criteria set forth in Section 7-3-21(A) of the RMC have not been met."

- (1) There are practical difficulties or unnecessary hardships in the way of carrying out the strict letter of the zoning ordinance, and
- (2) The spirit of the ordinance will be observed, the public health, safety, and welfare secured and substantial justice done by granting the variance.

Request #2 -Lot 15B: "I move to approve an 8-foot variance to allow a zero-foot side setback on the north and south property lines for Lot 15B, Amended Plat of Lot 15 Parkside Subdivision in the R Low Density Residential District finding that the criteria set forth in Section 7-3-21 of the RMC have been met and with the following conditions:

- 1) Address all comments in the Planning Review Comment Letter dated January 6, 2023, to the satisfaction of Town Staff prior to the Amended Plat being recorded with the Ouray County Clerk and Recorder.
- 2) The Ridgway Town Council approves the Amended Plat of Lot 15, Parkside Subdivision."

Alternative Motion:

"I move to deny the request to reduce the side setback on the north and south property line for Lot 15B, Amended Plat of Lot 15 Parkside Subdivision in the R Low Density Residential District finding that the criteria _____ of the approval criteria set forth in Section 7-3-21(A) of the RMC have not been met."

- (1) There are practical difficulties or unnecessary hardships in the way of carrying out the strict letter of the zoning ordinance, and
- (2) The spirit of the ordinance will be observed, the public health, safety, and welfare secured and substantial justice done by granting the variance.



Town of Ridgway Habitat For Humanity Plat Amendment & Variances January 6, 2023 Page 10 of 10

Request #3 -Lot 15C: "I move to approve an 8-foot variance to allow a zero-foot side setback on the north property lines for Lot 15C, Amended Plat of Lot 15 Parkside Subdivision in the R Low Density Residential District finding that the criteria set forth in Section 7-3-21 of the RMC have been met and with the following conditions:

- 1) Address all comments in the Planning Review Comment Letter dated January 6, 2023, to the satisfaction of Town Staff prior to the Amended Plat being recorded with the Ouray County Clerk and Recorder.
- 2) The Ridgway Town Council approves the Amended Plat of Lot 15, Parkside Subdivision."

Alternative Motion:

"I move to deny the request to reduce the side setback on the north property line for Lot 15C, Amended Plat of Lot 15 Parkside Subdivision in the R Low Density Residential District finding that the criteria ______ of the approval criteria set forth in Section 7-3-21(A) of the RMC have not been met."

- (1) There are practical difficulties or unnecessary hardships in the way of carrying out the strict letter of the zoning ordinance, and
- (2) The spirit of the ordinance will be observed, the public health, safety, and welfare secured and substantial justice done by granting the variance.

RECOMMENDED MOTIONS – PLAT AMENDMENT

"I move to recommend approval of the Amended Plat of Lot 15 Parkside Subdivision to the Town of Ridgway Town Council, subject to the conditions below, finding that the criteria set forth in Section 7-4-5 and 7-4-10 of the RMC have been met and with the following condition:

1) Address all comments in the Planning Review Comment Letter dated January 6, 2023.

Alternative Motion:


"I move to deny the Amended Plat of Lot 15 Parkside Subdivision finding that the criteria set forth in Section 7-4-5 and 7-4-10 of the RMC have been met:

- 1) The plat amendment is not substantially consistent with the preliminary plat as approved.
- The plat amendment does not contain all the required information listed in Section 7-4-5(C)(3)
- 3) The plat amendment does not conform to the R Low Density Residential District uses and standards.

ATTACHMENTS

- 1. Application and Support Materials
- 2. Planning Review Comment Letter Dated January 6, 2023





Applicant and owner shall be jointly and severally responsible for legal, engineering, planning, administrative and miscellaneous fees, including recording costs, if incurred. (R.M.C. 7-3-25(B) and 7-4-12(B)). Water and sewer tap fees and development excise taxes are due at approval of final plats

1



TOWN HALL PO Box 10 | 201 N. Railroad Street | Ridgway, Colorado 81432 | 970.626.5308 | www.town.ridgway.co.us

Attachments Required

For All Applications

K Evidence of ownership or written notarized consent of legal owner(s).

🔯 Information proving compliance with applicable criteria (see the Ridgway Municipal Code for criteria), this may include a narrative, site plans, and/or arch tectural drawings drawn to scale.

For Conditional Uses

The site plan shall show the location of building(s), abutting streets, all dimensions, off-street parking requirements, and landscaping

Architectural drawings shall include elevations and details of building(s).

For Changes in Nonconforming Use

Description of existing non conformity

For Variances

🔀 The site plan shall show the details of the variance request and existing uses w thin 100 ft. of property

For Rezonings

Legal description, current zoning, and requested zoning of property

For Subdivisions

All requirements established by Municipal Code Section 7-4

Sketch plan submitta s shall be submitted at least 21 days prior to the Planning Commission hearing at which the applicant wishes to have the application considered

Pretiminary plat submittals shall be submitted at least 30 days prior to the Planning Commission hearing at which the applicant wishes to have the application considered.

Final plat submittals shall be submitted at least 30 days prior to the Planning Comm ssion hearing at which the applicant wishes to have the application considered.

Please note that incomplete applications will be rejected. Contact with a Planning Commission or Town Council member regarding your application constitutes ex parte communication and could disqualify that Commissioner or Councilor from participating in your hearing. Please contact staff with any questions.

Applicant Signature

Owner Signature

8/8/2022 Date

2



10.00

TOWN HALL PO Box 10 || 201 N. Railroad Street || Ridgway, Colorado 81432 || 970.626.5308 www.town.ridgway.co.us

TOWN OF RIDGWAY, COLORADO ACKNOWLEDGMENT OF FEES AND COSTS

mardt A. Gerhardt ("Applicant") and ("Owner") do hereby acknowledge that with the filing of an application, or seeking Town review under Chapter 7, Section 3 or Section 4 of the Town of Ridgway Municipal Code, that it is subject to the requisite fees and costs associated with such action, in accordance with 7-3-20 and 7-4-12, including out-of-pocket legal fees and/or engineering fees.

Applicant and Owner acknowledge that no plat shall be recorded, improvement accepted, lien released, building permit issued, tap approved or final approval action taken until all fees then due are paid to the Town.

Applicant and Owner acknowledge that the Town may suspend review of submittals, inspection of improvements, and processing of a subdivision, as it deems appropriate, unless all amounts are paid as due.

Applicant and Owner further acknowledges that unpaid fees may be certified to the Ouray County Treasurer for collection as delinquent charges against the property concerned.

Acknowledged this _8th day of _August

APPLICANT.

er hord authorized signer Amanda (print name)

PROPERTY OWNER:

Gerhardt authorized signer Amanda (print name)

Property Reports	- Review all Informa	tion	http	s://dola.colorado.	gov/dpt_exemption		ew.js
					2-11		
15-DPT-EX Form 970-C Rev 01/08			State of Colorado Depertment of Local Affeirs Division of Property Texation			1313 Sherman Danver, CO Phone 303-864 TOD 303-864	90203 -7780
			2020 MPT PROPERTY REPO CHOOLS/CHARITABLE		:	43050841	1052 01 4015 Junay
Filing Fee If Submitted To	day:\$75.00	··· ··································					
forfeited if the annual report	r before 04/15/2020 a filing fee of \$ t is not filed by 07/01/2020 . To reg/ application after forfeiture, and v	ain the exemption from the fo	rfeiture date, you will have to fil	le a new application and petitik	on the State Board of Equals	0.00 Exemption will be zation for a waiver of the t	ling
PLEASE NOTE: There will The processing and mercha the transaction amount. To	be a processing fee added to the finant fee for credit card transactions is reduce these processing fees on mate of Visa, Mastercard, and America	Ung fee to cover the costs of is 2.25% on the total transact nultiple reports, it is suggester	electronic processing. You hav on amount plus an additional \$	e the option of using a credit o 10,75. For eCheck transaction	and (Vise, Mastercard, Amer s, the merchant and processi	ing tee is \$1.00, regarcies	IS OT
1, Owner's Name and Mal	ling Address:						
	iformation:		Currently:		Change To:	÷.	
Name of Owner:		HABITAT FOR HUMANITY	OF THE SAN JUANS				
Address 2:		PO BOX 162 1601 N TOWNSEND AVE					
Owner's Address: City		MONTROSE					
State:		CO					
Zip Code:		81402-0162					
3. Legal Description and I	Property Location:						
	nformation:		Currently:		Change To	:	
Legal Description:	genaten.	SUBD PARKSIDE SUBDI	VISION LOT 15 AFFORDABL	E HOUSING S			
		9 T: 45 R: 9					
Address:		400 N LAURA ST, RIDGW	'AY				
4. Estimated Exempt Valu	es Per DPT Records:						
Ir	nformation:		Currently:		Change To	1	
Estimated Land Value:				\$90,000.00			
Estimated Buildings Val	GRI						SO DC
Estimated Personal Pro	p. Value:					· · · ·	\$0.00
5. Contact Information fo	r Organization:						
Name:	Dwane Reed						
Daytime Phone Number	÷ 9702529303						
Email Address:	dwane@buildinglives.org						
6. Is "Charitable NON-RE	SIDENTIAL purposes" an accura	te depiction of the primary	use of this property?				No
Explanation of why the a Affordable houseing for low	bove description is not an accur w income	ate depiction of this proper	ty:				
7. Description and Usage	ef Property:	id sould-defendence from a second of the last weight a second s	fammi e a na del anterna manteri e la Adde della Lay a manamana dana di su ber		a na fa anna an	na, maa aa katikeeggaange o maan amaadatii 10-10	
List of eac	ch seperate building:		er en gesegte ogte annære an mærerelser vederære 1910 - 19 og en spænne av en en en vederelse i Andre og en er	Property is used for:	na dha anan bar 1914 (bart an 1-1) a sa anna an an ar ar ar ar ar bha tha tha anna a		
Habitat for Humanity of t		vacani land	an dependence in the second state of the secon	ning of particular and the second secon			
9. Charitable Non-Reside	Intial Purposes:						
A. Describe your charita	ble activities as they relate to the r the purpose of affordable housing	e use of this property: for low income					
B. Who benefits from yo families in need							
	ulch owner intends to construct o	or rehabilitate residential pr	operty to sell to a low-incom	e applicant?			
Yes				the second s			
Yes	Inyone Other Than the Owner:						
Yes		ser of Uses:	Hours of Use:	Amount of Area L	:(Hps ni) beel	Income Received:	

Total Square Footage of Improvements (buildings) on this parcel:

1 of 1

3/12/2020, 2:17 PM

10213 RECEIPT DATE. 0 8 22 No. 655783 Payment 500.00 500.00 N.H. 0 Sa \$500.00 RECEIVED FROM. ions we 8 end Λ 0 2 th DOLLARS ¥ Marin at d nend CASH ACCOUNT CHECK # 1021 PAYMENT FROM_ MONEY ORDER OCREDIT CARD TO BAL. DUE BY 3-11

2UIV









We build strength, stability, self-reliance *and* shelter.

11/04/2022


Attention: Town of Ridgway, Planning Commission Amended Letter


Habitat for Humanity of the San Juans (HFHSJ) respectfully requests an informal sketch plan review as part of our process for the requested hearing for variance and plot amendment for our current triplex project located at 702, 704, & 706 N. Laura St for a total of 3 proposed dwellings on the basis of affordability. Our variance request is centered on the fact that our middle unit within the Triplex is 0 feet from the two end units. This was done on the basis of affordability to keep costs reasonable as we work to bring these units on to the affordable housing stock leading to the reason why we are requesting this variance.

Attached is the required information for this request. Please do not hesitate to contact us with any questions or additional information needed to complete this request. Thank you for your time and consideration in this matter.

Best Regards,

Amanda Gerhardt, M.B.A. Executive Director Habitat for Humanity of the San Juans 970-252-9303 ext. 1





CERTIFICATE OF OWNERSHIP DEDICATION

Known all persons by these presents that we, the undersigned being the owners of certain lands in Ouray County, Colorado, described as Lot 15, Parkside Subdivision, Ouray County, Colorado, have caused same to be laid out and platted as shown on this plat under the name and style of Amended Plat of Lot 15 Parkside Subdivision.

Executed this	day of		2022	
Owner: Habitat for Humanity of	of the San Juans			
Ву:			Date:	
Printed Name:				
Title:				
STATE OF COLORADO)			
) ss. COUNTY OF)			
The foregoing Owner Certifica	ate was acknowledged before me	this day	/ of	, A.D. 2022,
by	as th	e		of Habitat for Humanity of the San Juans
Witness my hand and official	seal.			
			My Commision Exp	ires:

Notary Public

SURVEYOR'S CERTIFICATE

I, Jeremiah D. Harness, a Registered Land Surveyor in the State of Colorado, hereby certify that this Amended Plat of Lot 15 Parkside Subdivision was prepared under my direction and supervision and that said survey is accurate to the best of my knowledge, conforms to all the requirements of the Colorado Revised Statutes, and all applicable Town of Ridgway regulations, and that all required monuments have been set as shown. There are no roads, pipelines, irrigation ditches or other easements or rights- of-way in evidence or known to me to exist on or across said property except as shown on this plat. I certify that I have made the survey represented by this plat and that this plat accurately represents said survey, and conforms to all applicable requirements of the City Subdivision Regulations and applicable law. I further certify that all monuments shown hereon actually exist and their positions are as shown.

Jeremiah D. Harness Colorado Registered Lan Registration No. 38758 Date:	d Surveyor				
	RECORDER'S CERTIFICAT	<u>E</u>			
	This Amended plat of Lot 15 Parkside Su	ıbdivision was file	d for record in the	office of the Clerk and Recorder of Oura	y County at
<	m. on the day of		, 20		
	Reception No		by		
	County Clerk & Recorder	,	Deputy		
		PART	PAR SITUATED TOWNS	NDED PLAT OF LOT 1 KSIDE SUBDIVISION IN THE SE ¹ / ₄ SECTION 8 AND SW ¹ / ₄ SECTIO SHIP 45 NORTH, RANGE 8 WEST, NMPM ADDITION TO THE TOWN OF RIDGWAY, F ITY OF OURAY, STATE OF COLORADO	N 9
		PLAT DATE: PROJ. #	11/03/2022 22-201-SUR		V
		CAD FILE: 22-20	1-SUR LOT15 SIDE SUB.dwg	ENGINEERING	
		DRAFTER:	JDH	jrease@buckhornengineering.com	South Park Avenue
		FEILD DATE:	10/18/2022	Montre	ose, Colorado 81401
4	1.5" CAP LS 16840	FIELD CREW: AREA:	JDH 1.31 ACRES	CLIENT:	970-249-6828 DRAWING NUMBER
		CLOSURE:	CLOSURE	HABITAT FOR HUMANITY OF THE SAN JUANS	V-1 1 OF 1

Energy Usage Notes

Item	Insulation Value	Total Value	Project: Hal
Frame walls and rim joist	R 21	R 24	Project Loc
Window in Frame Walls and Basement	Low-E double glazed - 0.35	max U-value	Owner: Hat
Doors in Frame Walls and Basement	R 2.86		Owner Add
Ceilings or Rafters	R 49 or R38 with 12" energ	y heel (cellulose or fiberglass)	Project Des
Air Infiltration	Prescriptive Air Sealing		
Walls to Garage or Unheated Buffer Spaces	R 19	R 21	Applicable (
Heated Basement Areas	R 19		Internationa
Basement Window to Floor Area	10 % max		Internationa
Floors over Unheated Spaces	R 30		Internationa
Floors over Unvented Spaces with insulated walls	None		Internationa
Crawl Space Walls (unvented)	R 21		Internationa
Cantilever Floors	R 38	R40	National El
Slabs in Heated Areas (except garages)	R 10		Town of Ri
Heat in the slab/Slab edges with heat in slab	R 10/R15		
Exposed slab edges	R 7.5 - R 10		
Slabs in Unheated Area	0		Jurisdiction
Space Heating System Performance			NAME: To
Gas furnaces/Gas Boiler:	\geq 90% AFUE Note: Habita	t housing must comply with Energy Star standards	ADDRESS:
Dedicated Snow Melt systems:	≥ 90% AFUE	8 I J I S	BUILDING
Ducts: Inside envelope, outside conditioned space	R5		PHONE #:
Outside building envelope	R8		
Gas Log Sets in Masonry Fireplaces		side combustion air or automatic	Fire Suppre
	flue damper as approved by		Sprinklered
Gas Water Heater Performance:		itat housing must comply with Energy Star standards	opinitered
Water heating Piping	Heat traps		Building Co
Setback Thermostat (programmable)	Required (except for in-floo	or heat)	Type VB
Notes:			Occupancy

The R values given above are the total R values. The R values of different materials are added together including air films, air spaces and building materials. The R value is reduced by the effects of thermal bridging through framing. For instance, unless special methods or rigid insulation sheathing are used, the R value for walls must be decreased due to thermal bridging. Multiply the R value of ceilings at the depth of the framing members by .94 and the wall by .87.

Green Building Standards

- Exterior air-infiltration barrier
- Foam sill sealer beneath sill plates Energy heels on all roof trusses (12" min. when using fiberglass or cellulose, 7" min. when spray foam is applied.
- Timers or motion sensors for bath and laundry exhaust fans
- Formaldehyde free insulation Insulating blankets required for hot water heaters. unless the storage tank already has a high R-value (at least R-24). Insulating •
- blankets should be R-11 minimum.
- No hot air ducts allowed in exterior walls unless a minimum of R-10 insulation is installed on the exterior side of the duct. The insulation must be installed in an air tight manner
- Carbon monoxide (hard-wired) detectors required near the door betweend the residence and the garage (if there is an attached garage) and near the mechanical room. Must be installed per manufacturer's installation instructions
- Attached garages must be isolated from the dwelling with extensive air-sealing practices Insulated headers, min R-10, wherever possible. Steel headers must be provided with insulation on both the exterior & interior
- sides of the steel. All hot water re-circulation systems must be provided with a timer or an aquastat and manual on/off switch. Piping must be insulated (1/2)" thick wall foam insulation minimum or equivalent)
- Hot water piping in unconditioned spaces requires R-6 insulation (boilers and domestic water)
- All asphalt shingle roofing shall have a minimum 30 year advertised lifespan and be installed according to that criteria. All low • slope roofs (less than 3 inches vertical and 12 inches horizontal) including thermoset, thermoplastic, modified asphalt and asphalt built-up roofing applications, shall be a minimum 20 year advertised installation standard and completely installed under that criteria. All metal-sheet roofing shall have a minimum 24 gaugr for bare sheet products or metal of 26 gauge for surface protected metal and 26 gauge for shingle products. Other roofing materials approved by the International Code Council with a minimum 30 year Manufacturer's Replacement Warranty installed according to the approved recommendation may be accepted in lieu of these requirements. (Ord 5-2012)
- Return air ducts are required (panned framing cavities are prohibited)
- Class C or F fly ash concrete must be used in all cement mixes, excluding garages an exterior uses Range hoods are required and must be ducted to exterior, unless allowed an exemption by the building department under
- certain design conditions Paper covered gypsum board must be raised 1/2 inch above concrete slabs.
- 3 stud exterior corners must be capable of being insulated.
- Ladder-backed framing or alternate must be at all partition wall connections.
- Exterior walls of fireplaces shall comply with minimum wall R-value, R-21 • All bath or shower rooms shall have an exhaust fan ducted to outside Skylight shafts and knee walls must be air sealed and • insulated to the same level as the exterior walls. Insulation on attic knee walls of skylight shafts shall be encapsulated on all 6 sides of the enclosure
- Insulate under and around bathtubs must be to prescriptive code requirements.
- Openings to unconditioned space must be fully sealed.
- Crawlspace wall insulation must be permanently attached to the walls. Exposed earth in crawlspaces must be covered with • continuous vapor retarder with overlapping joints taped or sealed with mastic.
- Windows & Doors: Caulking, gasketing, adhesive flashing tape, foam sealant, or weather-stripping must be installed forming a complete air barrier.
- Band/rim joists must be insulated and air sealed.
- Recessed light fixtures must be "Air-Tight" I.C. rated in all building envelope ceilings. 4"minimum depth of insulation must be • maintained between the light fixture and exterior sheathing. Recessed light fixtures are strongly recommended to be "Air-Tight" I.C. rated for interior ceilings to improve air quality and to reduce airflow through the building envelope. Recessed step lights are not permitted in exterior building walls, except where fully encased in stone or concrete, or with •
- sufficient remaining wall insulation to maintain the required wall R-value
- A functioning passive or active radon mitigation system shall be installed in all new structures Zero/Low VOC finishes (paint, flooring, cabinetry, etc.) are strongly encouraged. VOC Homeowner awareness sheet must be •
- signed by the Homeowner and included in sale of home documents
- Ground Snowmelt System Requirements:
- a. Snow-melt areas must not exceed 1000 sq. ft. Increase is allowed for demonstrated genuine safety issues or if the structure achieves a 50 or less HERS rating, 30% more free snow-melt area is allowed. Requests for greater than 1000 sq. ft. of snow melt may be considered at the discretion of the Building Official if energy used for the system comes from on-site renewable energy sources
- b. Electric snowmelt is not permitted
- c. Snowmelt systems must include both moisture and temperature sensors to control snowmelt operation d. Idling snowmelt systems are not permitted
- e. Under the slab insulation of at least R-10 is required
- Space heating and cooling system equipment shall be sized according to heating and cooling loads calculated using the latest versions of ACCA Manuals J and S, ASHRAE 2001 Handbook of Fundamentals, or an equivalent computation procedure. Applicable also to additions and renovations where new HVAC equipment is installed
- Duct system is sized, designed, and installed according to ACCA manual D or equivalent
- Ducts are sealed with UL 181 tape, low-toxic mastic (FDA, USDA, & EPA-approved), gaskets, or an approved system as •
- required by the IRC (Section M1601.3.1) or IMC (Section 603.9) to reduce leakage Ducts external to conditioned airspace (i.e. through crawlspace or attics) must have insulation R-8 or greater
- All furnace ducts must be air tight and sealed with commercial grade mastic and fiberglass mesh. Ducts are to be sealed • substantially airtight with tapes (not duct tape) mastics or gasketing. Fiberglass ducts that expose fibers to the air stream are not
- permitted Multi-boiler systems must be provided with a staging device and outdoor reset
- Programmable digital thermostats required
- Windows must demonstrate 0.3 cfm per sq. ft. maximum allowable air leakage
- Note: Tight home construction requires a source of ventilation air supply; ANSI/ASHRAE Standard 62.2 2007 ("Ventilation and Acceptable Indoor Air Quality in Low-Rise Residential Buildings") is the national ventilation standard. It is highly recommended that an Energy Recovery Ventilator (ERV) or Heat Recovery Ventilator (HRV) be installed to in all residences

7. 8. 9. 10. 11.

1.

2.

24.

Code Notes

Project: Habitat For Humanity Triplex Project Location: N. Laura St., Ridgway, CO 81432 Owner: Habitat For Humanity of the San Juans Owner Addresss: 1601 N. Townsend Ave, Montrose, CO 81401 Project Description / Scope: Project will consist of (3) 1985 s.f. single family homes.

Applicable Codes: International Building Code (IBC) 2006 Ed. International Mechanical Code (IMC) 2006 Ed.

International Plumbing Code (IMP) 2006 Ed.

International Energy Conservation Code (IECC) 2006 Ed. International Fire Code (IFC) 2006 Ed.

National Electric Code (NEC) Current Edition Fown of Ridgway Prescriptive Energy Code and Green Building Standardd

urisdictional Building Department: NAME: Town of Ridgway ADDRESS: N. Laura St, Ridgway, CO

BUILDING OFFICIAL: Mike Gill PHONE #:970-626-5308 x216

Fire Suppression prinklered Buildings

Building Construction Type

Occupancy Classification

Type R3

Climatic and Geographic Design Criteria

Climate Zone: 6 Ground Snow Load: 65 Lbs/Sq. Ft.

Wind Speed: 90 mph, 3 second gusts Seismic Design Category: C

Weathering: Severe Frost Line Depth: 40 inches

Termite: Slight Decay: Slight

Winter Design Temperature: -16 degrees F

Ice Shield: Yes Flood Hazards: Ridgway Municipal Code Subsection 6-2-6 Air Freezing Index: 3000 (BF/days)

Mean Annual Temperature: 43 degrees F

General Notes

DO NOT SCALE THESE DRAWINGS. Verify all dimensions and conditions. Any variation shall be brought to the attention of the architect and designer.

Dimensions and conditions at the job site shall be verified by all contractors. It is the responsibility of the contractor to examine the existing conditions prior to submitting bids to the owner since proposals must take into consideration all such conditions which may affect the work. Discrepancies in the drawings or between the drawings and actual field conditions shall be reported to the architect. Corrected drawings or instructions shall be issued by the architect prior to the commencement of the work.

This project shall comply with applicable local building codes. In the absence of any governing building code, this project will comply with IBC 2003. It is the responsibility of anyone supplying labor, materials, or both to bring to the attention of the architect any discrepancies or conflicts between requirements of these codes and the drawings.

All dimensions are to face of foundation or wood frame studs or centerline of column or rough opening unl noted. Rough openings not dimensioned can be assumed to be centered in the wall or set at minimum jamb width $(4 \ 1/2")$ minimum, 6" preferred). Refer to window/door schedule for door and window rough opening sizes. General Contractor to refer to subdivision plans for specific utility easements and other pertinent information.

General Contractor to coordinate and field verify utility connections, their routing, depth, meter locations and other associated items. General Contractor to coordinate top of foundation wall elevations with information indicated in these plans and with final

Unless otherwise noted on the site/grading plan, provide positive drainage away from the foundation. All site grading should blend naturally with existing grades using a maximum slope of 2:1. The fill slope at the lower level of the building

will need to have a grade not exceeding 2:1 slope. The contractors shall provide the designer, architect and owner with a list of heating, cooling, water heater and lighting systems or solar devices installed in the building and instructions on how to use and maintain them efficiently. All warranties of all materials and equipment are to be delivered to the owner at completion of construction. The details shown are intended to further illustrate the visual design concept and minimum weather protection for this project. The general contractor shall incorporate the requirements of the local building codes, structural considerations, trade association manuals, publications and recommendations, and the manufacturer's written instructions for complete construction details. All possible field conditions which may be encountered are not necessarily described. Field conditions encountered which require clarification shall be brought to the architect's and designer's attention.

Mechanical ventilation for toilet compartments, bathrooms, and laundry rooms shall be capable of providing 5 air changes per hour or per local building code. Exhaust vent for clothes dryer to be vented to the outside. The duct shall be per manufacturer's instructions.

Vent all exhaust fans to exterior. Provide rain caps and flashing as required.

Center toilets in the space provided or a minimum of 15" (18" preferred) from vertical surfaces at sides.

Door between R-3 and U-1 occupancies to be 1 3/8" solid core, self closing and tight fitting.

All surfaces in garage adjacent to habitable space to be insulated and finished with 5/8" type 'X' gypsum board from foundation to underside of roof sheathing. All beams, columns, and structural members to be wrapped with 5/8" type 'X' gypsum board.

All exterior doors leading to unheated areas to be weather-stripped and have thresholds. Flash all exterior openings, roof/wall intersections, valleys, and material transitions with metal flashing material. All

materials shall have a matte, non-reflective finish Egress windows to have a maximum sill height of 44", minimum vertical opening of 24", minimum horizontal opening of

20" and a minimum of 5-7 square feet of open area.

Tempered glazing is required at locations that meet all of the following criteria: Witihin a 24" arc of a door

Within 18" of a floor or tub deck

All shower and bathtub enclosures

Windows with an individual pane greater than 9 square feet


All wood in direct contact with concrete to be pressure treated or redwood or cedar, including posts and stairs. Provide water resistant gypsum board at walls in utility rooms and bathrooms that do not receive ceramic tile finish. All surfaces finished with ceramic tile to be backed with cement board.

Truss manufacturer to provide truss layout and profiles to the structural engineer and architect for review and coordination.

Such work shall be based on both the architectural and structural drawings. Dimensions shown for trusses on section sheets are to be used as general guides and shall be verified by the truss manufacturer.

Cabinet design and their related drawings are to be provided by others, Cabinets shown are provided to illustrate the intent of the overall design.

25. All plumbing fixtures must be low flow, per Town regulations. A copy of the manufacturer's specification sheet for each fixture type may be required by the building department for verification.





Bayport Collection Dark Sky 7 3/4" High Outdoor Wall Light Style # M5911

- 7 3/4" high x 7" wide. Extends 8" from the wall.
- · Bayport Collection outdoor wall light from Designers Fountain.
- · Bronze finish over cast aluminum construction.

· Wet location outdoor rated.

- · Dark Sky compliant.
- · With an industrial or barn light look.

NOTE: FIXTURE WILL HAVE A 15W LED LAMP WITH 800 LUMEN OUTPUT. Exterior Lighting Fixture

Area Calculations

Main Level Second Level Garage Area Total

Ridgway, CO

(3) x 626 s.f. = 1878 s.f. (3) x 958 s.f. = 2874 s.f. (3) x 401 s.f. = 1203 s.f. (3) x 1985 s.f. = 5955 s.f.

REVISIONS

MOTLEY ARCHITECTVRE & DEFIGN		PROJEC PHASE ISSUE: ISSUE I
915 S. 10th St.	=	
Montrose, CO 81401 p: (970) 249-1980 motleyarc.com		Cov
		SHEET
	+ +	1
Habitat for Humanity Triplex		
✓ ⊥	1 1	1


CT NO: DATE:

H4H-3P-RI CD-Review 6/29/20

ver


NAME

SHEET NUMBER



					Typical Ur	nit Room Fini	ish Schedule			
		Fle	oors		W	alls		Се	eilings	
								Ceiling		
Number	Name	Floor Finish	Base Finish	North Wall	East Wall	South Wall	Wall Finish	Material	Ceiling Finish	Comments
					-					
100	Garage			PT	РТ	PT	РТ	GWB	РТ	
101	Living	СРТ	WD	РТ	PT	PT	РТ	GWB	РТ	
102	Kitchen/Dining	EWD	WD	РТ	РТ	PT	РТ	GWB	РТ	
103	Toilet	СТ	WD	РТ	РТ	PT	РТ	GWB	РТ	
104	Storage	SV	WD	РТ	РТ	PT	РТ	GWB	РТ	
201	Bedroom 1	СРТ	WD	РТ	РТ	PT	РТ	GWB	РТ	
202	Bathroom	СТ	WD	РТ	РТ	РТ	РТ	GWB	РТ	
203	Bedroom 2	СРТ	WD	РТ	РТ	РТ	РТ	GWB	РТ	
204	Laundry	SV	WD	РТ	РТ	РТ	РТ	GWB	РТ	
205	Bonus Room	СРТ	WD	РТ	РТ	РТ	РТ	GWB	РТ	

FINISHES LEGEND: CPT - Carpet, CT - Ceramic Tile, EWD - Engineered Wood Floor, GWB - Gypsum Board, PT - Paint, SV- Sheet Vinyl, WD - Painted Wood Base Trim




2 Second Floor 1/4" = 1'-0"

				Туріс	cal Unit Door Schedule
Door			Doo	r Finish	
Number	Width	Height	Panel	Frame	Comments
100A	10' - 0"	8' - 0''	WD	WD	Fiberglass Overhead Garage Door
100B	3' - 0"	6' - 8"	WD	WD	
101A	3' - 0"	6' - 8"	WD	WD	Clad Exterior Door w/ glass half-lite
101B	2' - 6"	6' - 8"	WD	WD	
101C	3' - 0"	6' - 8"	WD	WD	
102	3' - 0"	6' - 8"	WD	WD	Clad Exterior Door w/ glass half-lite
103	2' - 6"	6' - 8"	WD	WD	Clad Exterior Door w/ glass half-lite
111	6' - 0"	6' - 8"	WD	WD	Bi-pass closet door
201	2' - 6"	6' - 8"	WD	WD	
202	2' - 6"	6' - 8"	WD	WD	
203A	2' - 6"	6' - 8"	WD	WD	
203B	2' - 6"	6' - 8"	WD	WD	Bi-fold closet door
204	2' - 6"	6' - 8"	WD	WD	
205A	2' - 6"	6' - 8"	WD	WD	
205B	2' - 6"	6' - 8"	WD	WD	
205C	2' - 6"	6' - 8"	WD	WD	
205D	2' - 6"	6' - 8"	WD	WD	
205E	2' - 6"	6' - 8"	WD	WD	

DOOR NOTES:


All doors to have level handles
 All glazing in doors to be double glazed, tempered, and Low-E






Keynote Number A


В	
С	
D	
Е	
F	
G	




Description
Recessed Can Light
Ceiling Mounted Light Flxture
Exterior Wall Light
Linear 1'x4' LED Ceiling Mounted Light
Bathroom Wall Light
Vent Fan
Recessed Can Light (H2O Rated)

MOTLEY ARCHITECTVRE & DEFIGN 915 S. Tenth St. Montrose, CO 81401 p: (970) 249-1980 f: (970) 797-6811 www.motleyarc.com STAMP © Motley Architecture & Design Humanity for Ť **C**X Habita rip PROJECT NO: H4H-3P-RI PHASE: CD-Review ISSUE: С 6/29/20 ISSUE DATE: Lighting Plan SHEET NAME A2.2 Sheet Number










SHEET NUMBER





6/29/2020 9:59:39 AM
















6/29/2020 9:59:41 AM




















7 Kitchen North 1/2" = 1'-0"













4 Toilet 1/2" = 1'-0"




8 Kitchen South 1/2" = 1'-0"





Ab SHEET NUMBER



1 South 3/16" = 1'-0"








Window Schedule								
	Unit	Size						
Mark	Width	Height	Туре	Comments				
1	2' - 0"	3' - 6"	Casement	Mulled with adjacent see elevations				
2	2' - 6"	3' - 6"	Fixed	Mulled with adjacent see elevations				
3	2' - 0"	3' - 6"	Casement	Mulled with adjacent see elevations				
4	2' - 0"	3' - 6"	Casement	Mulled with adjacent see elevations				
5	2' - 6"	3' - 6"	Fixed	Mulled with adjacent see elevations				
6	2' - 0"	3' - 6"	Casement	Mulled with adjacent see elevations				
7	2' - 0"	3' - 6"	Casement	Mulled with adjacent see elevations				
8	2' - 6"	3' - 6"	Fixed	Mulled with adjacent see elevations				
9	2' - 0"	3' - 6"	Casement	Mulled with adjacent see elevations				
10	2' - 0"	2' - 0"	Casement	· · · · · · · · · · · · · · · · · · ·				
11	2' - 4"	3' - 0"	Casement					
12	2' - 4"	3' - 0"	Casement					
13	2' - 4"	3' - 0"	Casement					
14	2' - 4"	3' - 0"	Casement					
15	2' - 4"	3' - 0"	Casement					
16	2' - 4"	3' - 0"	Casement					
17	2' - 4"	3' - 0"	Casement					
18	2' - 4"	3' - 0"	Casement					
19	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
20	4' - 3"	3' - 5 1/2"	Casement	Egress Window				
21	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
22	2' - 6 1/2"	4' - 6"	Casement	Egress Window				
23	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
25	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
26	2' - 6 1/2"	4' - 6"	Casement	Egress Window				
27	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
29	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
30	2' - 6 1/2"	4' - 6"	Casement	Egress Window				
31	2' - 0"	2' - 0"	Casement					
32	2' - 6 1/2"	4' - 6"	Casement	Egress Window				
33	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
34	2' - 6 1/2"	3' - 5 1/2"						
35	2' - 6 1/2"	4' - 6"	Casement	Egress Window				
36	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
37	2' - 6 1/2"	3' - 5 1/2"						
38	2' - 6 1/2"	4' - 6"	Casement	Egress Window				
39	2' - 6 1/2"	3' - 5 1/2"	Casement	Egress Window				
40	2' - 6 1/2"	3' - 5 1/2"						
41	2' - 6 1/2"	3' - 5 1/2"	Casement					
51	4' - 3"	3' - 5 1/2"	Casement	Egress Window				
54	4' - 3"	3' - 5 1/2"	Casement	8				

	۲ ۲ ۲ ۲ ۲ ۲ ۲ ۲ ۲ 1 <th1< th=""> <th1< th=""> <th1< th=""> <th1< th=""></th1<></th1<></th1<></th1<>
-	STAMP © Motley Architecture & Design
	Habitat for Humanity Triplex
	PROJECT NO: H4H-3P-RI PHASE: CD-Review ISSUE: C ISSUE DATE: 6/29/20
=	Schedule SHEET NAME

A SHEET NUMBER


Note: All window 7'-0" above structural floor sheathing unless noted otherwise on A7.1



3 Partial Plan - Fire Riser Closet 1/4" = 1'-0"

					Typical Ur	nit Room Fin	ish Schedule			
		Fle	oors		W	alls		Ce	eilings	
Number	Name	Floor Finish	Base Finish	North Wall	East Wall	South Wall	Wall Finish	Ceiling Material	Ceiling Finish	Comments
100	Garage			PT	РТ	РТ	PT	GWB	PT	
101	Living	СРТ	WD	РТ	РТ	РТ	РТ	GWB	РТ	
102	Kitchen/Dining	EWD	WD	РТ	РТ	РТ	РТ	GWB	РТ	
103	Toilet	СТ	WD	РТ	РТ	РТ	РТ	GWB	РТ	
104	Storage	SV	WD	РТ	РТ	РТ	PT	GWB	РТ	
201	Bedroom 1	СРТ	WD	РТ	PT	РТ	РТ	GWB	РТ	
202	Bathroom	СТ	WD	РТ	РТ	РТ	PT	GWB	РТ	
203	Bedroom 2	СРТ	WD	РТ	РТ	РТ	РТ	GWB	РТ	
204	Laundry	SV	WD	РТ	PT	РТ	PT	GWB	РТ	
205	Bonus Room	СРТ	WD	РТ	РТ	РТ	РТ	GWB	PT	

FINISHES LEGEND: CPT - Carpet, CT - Ceramic Tile, EWD - Engineered Wood Floor, GWB - Gypsum Board, PT - Paint, SV- Sheet Vinyl, WD - Painted Wood Base Trim




2 Second Floor 1/4" = 1'-0"


				Тури	cal Unit Door Schedule
Door			Doo	r Finish	
Number	Width	Height	Panel	Frame	Comments
1001	4.01 01	01 01	WD	WUD	
100A	10' - 0"	8' - 0"	WD	WD	Fiberglass Overhead Garage Door
100B	3' - 0"	6' - 8"	WD	WD	
101A	3' - 0"	6' - 8"	WD	WD	Clad Exterior Door w/ glass half-lite
101B	2' - 6"	6' - 8"	WD	WD	
101C	3' - 0"	6' - 8"	WD	WD	
102	3' - 0"	6' - 8"	WD	WD	Clad Exterior Door w/ glass half-lite
103	2' - 6"	6' - 8"	WD	WD	Clad Exterior Door w/ glass half-lite
111	6' - 0"	6' - 8"	WD	WD	Bi-pass closet door
201	2' - 6"	6' - 8"	WD	WD	
202	2' - 6"	6' - 8"	WD	WD	
203A	2' - 6"	6' - 8"	WD	WD	
203B	2' - 6"	6' - 8"	WD	WD	Bi-fold closet door
204	2' - 6"	6' - 8"	WD	WD	
205A	2' - 6"	6' - 8"	WD	WD	
205B	2' - 6"	6' - 8"	WD	WD	
205C	2' - 6"	6' - 8"	WD	WD	
205D	2' - 6"	6' - 8"	WD	WD	
205E	2' - 6"	6' - 8"	WD	WD	

DOOR	NOTES:
1.	All doors to have level handles
2.	All glazing in doors to be double glazed, tempered,


l, and Low-E

















PERMIT SET NOT FOR CONSTRUCTION 09/29/2020 5:32:02 PM

SPAN	SPECIFIED H
≤12'	(2) 1.75" x 9.5" VI 2.0 2800
≤3'-8"	(2) 2" x 10" HEN SELECT STRU
	≤12'


-(14) FLOOR JOISTS, 11-7/8" BCI 6000 1.8 @16" O/C, MAX SPAN = 14'-0"


-FB1, 1.75"x11-7/8" VERSA-LAM 2.0 2800 DF

-FB2, 1.75"x11-7/8" VERSA-LAM 2.0 2800 DF

-LOAD BEARING WALL

-FB3, 1.75"x11-7/8" VERSA-LAM 2.0 2800 DF






<u>SITE LEGEND:</u>

	REFERENCE	NOTES SCHEDULE	
	SYMBOL	DESCRIPTION	QTY
		BASE BID: STEEL LANDSCAPE EDGER "COL-MET" MFG., BROWN POWDERCOAT FINISH. INSTALL PER MFG RECOMMENDATIONS WITH LAP JOINTS AND STAKES. SEE THE DETAIL, SHEET L8.1.	118 LF
	SYMBOL	DESCRIPTION	QTY
	2	BASE BID: 1"-3" WASHED ROUND GRAVEL STONE 3" DEEP OVER LANDSCAPE FABRIC.	2,921 S
	3	BASE BID: 6 FT. CEDAR SCREEN FENCE. INSTALL PER INDUSTRY STANDARDS BY EXPERIENCED FENCE CONTRACTOR. LOCATE WHERE SHOWN ALONG PROPERTY LINE AND BETWEEN UNITS.	302 LF
		ADD ALTERNATE: BACKYARD STEEL EDGER "COL-MET" MFG, BROWN POWDERCOAT FINISH, 4" WIDE X 1/8" THICK. INSTALL WITH PROPER LAP JOINTS AND STAKES.	183 LF
0 0 0 0	5	ADD ALTERNATE: CONCRETE BACK PATIO 10 FT. X 20 FT.	603 SF
	6	ADD ALTERNATE: BACKYARD 1"-3" WASHED ROUND GRAVEL STONE 3" DEEP OVER LANDSCAPE FABRIC	2,597 S

LANDSCAPE LEGEND:

PLANT SCHEDULE					
TREES	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	REMARKS
•	ACE BOX	2	ACER NEGUNDO `SENSATION` SENSATION MAPLE	1.5" CALIPER	30` TALL, 25` SPREAD, RED FALL COLOR
	PIC G22	4	PICEA PUNGENS `GLAUCA` COLORADO BLUE SPRUCE	6`-8` B&B	40` TALL, 15` SPREAD, BLUE EVERGREEN
	POP NMN	5	POPULUS TREMULOIDES `CLUMP FORM` CLUMP FORM QUAKING ASPEN	5 GALLON	40 FT TALL, 12 FT SPREAD, MULTI-STEM. YELLOW FALL COLOR
DECIDUOUS SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	REMARKS
S	COR ISA	3	CORNUS SERICEA `ISANTI` ISANTI REDOSIER DOGWOOD	5 GALLON	5` TALL, 6` SPREAD, RED TWIGS
\odot	POT POT	18	POTENTILLA FRUTICOSA `GOLDFINGER` GOLDFINGER POTENTILLA	5 GALLON	3 FT TALL, 3 FT SPREAD, YELLOW SUMMER FLOWERS.
E The	PRU PAW	5	PRUNUS BESSEYI `PAWNEE BUTTES` PAWNEE BUTTES SAND CHERRY	5 GALLON	2` TALL, 5` SPREAD, WHITE SUMMER FLOWERS, RED FALL COLOR
EVERGREEN SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	REMARKS
	JUN BRO	14	JUNIPERUS SABINA `BROADMOOR` BROADMOOR JUNIPER	5 GALLON	2` TALL, 6` SPREAD, HORIZONTAL GREEN EVERGREEN
GROUND COVERS	CODE	QTY	BOTANICAL / COMMON NAME	CONT	REMARKS
	TURF	1,169 SF	ADD ALTERNATE: IRRIGAGED TURF SEED	-	"DROUGHT STAR" DROUGHT TOLERANT KENTUCKY BLUE GRASS TURF SEED MIX. SEED AT 100-150 LBS/ACRE PER THE SUPPLIER RECOMMENDATIONS.
	MEADOW	10,963 SF	NON-IRRIGATED MEADOW GRASS (EXISTING TO REMAIN)	-	EXISTING NATIVE DROUGHT-TOLERANT MEADOW GRASS TO REMAIN. OVERSEED BARE OR DISTURBED AREAS AS NEEDED WITH FOOTHILLS MEADOW GRASS SEED MIX PER THE SUPPLIER`S RECOMMENDATIONS.



TOWN OF RIDGWAY REQUIREMENTS:	
RESIDENTIAL REQUIRES 50% COVERAGE OF LIVE MATERIAL ON 80% OF SITE. NO MORE THAN 10% STONE MULCH SHOWING IN FRONT AND SIDE YARDS. ONLY LOW LANDSCAPE ALLOWED IN CORNER SITE TRIANGLE.	
A MINIMUM OF 1 TREE PER 2,000 SF OF GROSS LOT AREA SHALL BE PROVIDED. 21,529 SF DIVIDED BY 2,000 = 10.7 REQUIRED TREES MINIMUM. 11 TREES PROVIDED TOTAL.	
NORTH LAURA STREET: 1 TREE EVERY 25 LF OF FRONT YARD FRONTAGE = 6 REQUIRED TREES = 6 PROVIDED 1 SHRUB PER EVERY 10 LF = 15 SHRUBS REQUIRED = 20 PROVIDED	
NORTH RAILROAD STREET: 1 TREE EVERY 50 LF OF SIDE YARD FRONTATE= 4 REQUIRED TREES = 4 PROVIDED 1 SHRUB PER EVERY 10 LF = 20 SHRUBS REQUIRED = 20 PROVIDED	
EXISTING DRAINAGE WAY: TO REMAIN UNDISTURBED. NATIVE GRASS TO REMAIN	
<u>FINAL_TOTALS:</u> 11 NEW TREES PROVIDED 40 SHRUBS PROVIDED	

والمغدي	
REVISIONS	BY
UPDATED CIVIL & ARCH BASES	9/2/20
Contraction of the second s	


Julee Wolverton, Landscape Architect



61945 Nighthawk Road Montrose, CO 81403 office: 970.249.9392 mobile: 970.417.1779 julee@juleewolverton.com



LANDSCAPE DETAILS:



LANDSCAPE NOTES:

1. THE OWNER AND GENERAL CONTRACTOR SHALL ENSURE THAT THE LANDSCAPE PLAN IS COORDINATED WITH THE PLANS PREPARED BY OTHER CONSULTANTS SO THAT THE PROPOSED GRADING, STORM DRAINAGE, EXTERIOR LIGHTING OR OTHER CONSTRUCTION DOES NOT CONFLICT WITH NOR PRECLUDE INSTALLATION OF MAINTENANCE OF LANDSCAPE ELEMENTS AS DESIGNATED ON THIS PLAN.

2. INSTALL A NEW UNDERGROUND AUTOMATIC IRRIGATION SYSTEM. IF DOMESTIC WATER IS USED. INSTALL A BACKFLOW PREVENTER WITH LOCKABLE ENCLOSURE. IF DITCH IRRIGATION WATER IS USED, INSTALL A PUMP WITH FILTER. AN AUTOMATIC IRRIGATION CONTROLLER SHALL BE INSTALLED FOR THE NEW SYSTEM. TURF GRASS AREAS SHALL BE IRRIGATED USING POP-UP SPRAY OR ROTOR TYPE HEADS. ALL SHRUBS AND TREES SHALL BE IRRIGATED USING DRIP/BUBBLER IRRIGATION. MEADOW GRASS IS EXISTING AND IS NON-IRRIGATED.

3. TOPSOIL SHALL BE IMPORTED FROM ON-SITE EXCAVATION AREAS INTO ALL OF THE LANDSCAPE AREAS TO BE PLANTED WITH TREES, SHRUBS, AND SOD. THERE SHALL BE A MINIMUM OF 8" OF TOPSOIL IN ALL SHRUB BED AREAS AND SOD GRASS AREAS.

4. SOIL PREPARATION FOR GRASS AREAS SHALL BE ORGANIC MATTER (100% DECOMPOSED WOOD CHIPS) APPLIED AT A RATE OF 3-5 CY/1000 SF., AND TILLED TO A DEPTH OF 6"-8", AND FINE GRADED.

6. WHEN INSTALLING EACH PLANT, PLANT MIX SHALL BE COMPRISED OF 1 PART SOIL CONDITIONER (DECOMPOSED BARK MULCH OR "BACK-TO-EARTH" ACIDIFIER PRODUCT) TO 2 PARTS TOPSOIL. OVER EXCAVATE THE PLANTING HOLES TWO TIMES THE DIAMETER OF THE ROOTBALL. FILL WITH PLANT MIX. ROOTING HORMONE SUCH AS INDOL 3 BUTERIC ACID SHALL BE USED FOR ALL TREES & SHRUBS.

7. ALL SHRUB BED AREAS SHALL BE SEPARATED FROM GRASS AREAS BY A STEEL LANDSCAPE EDGER. 3" DEEP MULCH SHALL BE PLACED OVER WEED BARRIER FABRIC.

8. SHRUB BEDS SHALL HAVE "DEWITT PRO 5" WEED BARRIER FABRIC OR APPROVED EQUAL INSTALLED UNDER MULCH UNLESS NOTED OTHERWISE -OVERLAP SEAMS MIN. 4" AND ATTACH FABRIC IN PLACE WITH 8" LONG STAPLES AT MAX. 4' O.C.

9. WHEN PLANTING TREES OR SHRUBS: THOROUGHLY SOAK PLANTING HOLE WHILE BACKFILLING. PRUNE DEAD OR DAMAGED BRANCHES IMMEDIATELY AFTER PLANTING. FERTILIZE WITH AGRIFORM 21 GRAM PLANT TABLETS, 20–10–5. 6 TABLETS PER TREE, AND 3 PER SHRUB.

10. SHREDDED CEDAR BARK MULCH SHALL BE PLACED AROUND THE DRIPLINE OF EACH PLANT TO MAINTAIN MOISTURE, 4 FT. DIAMETER AROUND TREES, AND 2 FT. DIAMETER AROUND SHRUBS. DO NOT LET BARK MULCH TOUCH THE BASE AND STEM OF EACH PLANT - KEEP CLEAR 2".

11. ALL DECIDUOUS TREES SHALL BE STAKED WITH (2) 6 FT. T-POSTS. ALL EVERGREEN TREES SHALL BE STAKED WITH (3) 2 FT. T-POSTS. ALL POSTS SHALL BE GUYED TO THE TREE WITH 12 GA. WIRE ENCASED IN RUBBER HOSE.

12. ALL TREES WITHIN THE SIGHT TRIANGLES SHALL BE LIMBED UP TO A HEIGHT OF 8 FT. AS THE TREE GROWS, AND THIS CLEARANCE SHALL BE MAINTAINED.

13. LOCATE AND MARK LOCATIONS OF ALL UTILITIES PRIOR TO COMMENCING WORK. DO NOT PLANT ANY TREES OR SHRUBS DIRECTLY OVER BURIED UTILITY LINES, OR ANY TREES UNDER OVERHEAD UTILITY LINES.

14. PLANT MATERIAL WAS CHOSEN FOR ITS SPECIFIC VARIETY, HEIGHT, AND COLOR. ANY PLANT MATERIAL SUBSTITUTIONS MUST BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION.


15. ALL PLANT MATERIAL SHALL BE GROWN IN A NURSERY IN ACCORDANCE WITH PROPER HORTICULTURAL PRACTICE. PLANS SHALL BE HEALTHY, WELL-BRANCHED, AND VIGOROUS WITH A GROWTH HABIT NORMAL TO THE SPECIES AND VARIETY, AND FREE OF DISEASES, INSECTS, AND INJURIES.

16. CONTRACTOR TO WARRANTY IRRIGATION SYSTEM AND ALL PLANT MATERIAL FOR A PERIOD OF ONE YEAR. REPLACE ANY DEAD OR DYING PLANTS DURING THAT ONE-YEAR WARRANTY PERIOD.

REVISIONS	BY
UPDATED CIVIL & ARCH BASES	9/2/20




61945 Nighthawk Road Montrose, CO 81403 office: 970.249.9392 mobile: 970.417.1779 julee@juleewolverton.con



LANDSCAPE NOTES & DETAILS

SHEET No.

L-2



				2	ð	ğ
				WOILD	AENTS	RE SUPPRESSION
N 10 ¹⁰³³				BELV DATE DATE DESCRIPTION	1 08/06/20 REVISED PER TOWN	e 08/25/20 REVISED BUILI
LOT 15 AREAS AL AREA OF PROPERTY ILDING COVERAGE CKS AND PORCHES W CONCRETE STING ON-SITE SIDEWALKS AL PERVIOUS AREA	21,529.00 3,101.39 268.19 902.19 785.69	CRESPER0.4940.0710.0060.0210.0180.378	CENTAGE 100% 14.41% 1.25% 4.19% 3.65% 76.51%			
PERVIOUS AREAS	5,057.45	0.116	23.49%			
SITE NEW CONC	198.20	0.005				LAURA STREET TRIPLEX SITE PLAN RIDGWAY, COLORADO
	PROPOSED	RIGHT-OF- ROAD CENT EASEMENT PROPERTY CONTOURS CONTOURS ASPHALT CONCRETE GRAVEL SIGN FENCE	ERLINE LINE MAJOR	PRC DAT DRA CHE	JEC ⁻ E FTEF CKE	T 7122.75084.01 06/18/2020 R CH

SHEET INDEX


SHEET NO.	TITLE
C-1	COVER SHEET
C-2	EXISTING CONDITIONS / DEMOLITION PLAN
C-3	SITE PLAN
C-4	UTILITY PLAN
C-5	GRADING AND EROSION CONTROL PLAN
D-1	DETAILS



VICINITY MAP N.T.S.

HABITAT FOR HUMANITY LAURA STREET TRIPLEX RIDGWAY, COLORADO PROJECT NO. 7122.75084.01

PREPARED BY:



PREPARED FOR:

HABITAT FOR HUMANITY OF THE SAN JUANS ERICA MADISON, EXECUTIVE DIRECTOR PHONE: 970-252-9303 X 5 Email: ERICA@BUILDINGLIVES.ORG 1601 N. TOWNSEND AVE MONTROSE, CO 81401





	<u>END</u>	
EXISTING	PROPOSED	
		RIGHT-OF-WAY LINE ROAD CENTERLINE EASEMENT
— — — <i>-8455- — — —</i>	8475	PROPERTY LINE CONTOURS MAJOR CONTOURS MINOR
	in in in	ASPHALT
		CONCRETE
		GRAVEL
····· x x	• × ×	SIGN FENCE
⊳ 0	•	SANITARY SEWER SER SANITARY CLEANOUT
		SANITARY LINE END C
©ss	9 s	SANITARY SEWER MAN SANITARY SEWER LINE
₩ ₩	₩ ₩	WATER MANHOLE
W	W	WATER VAULT
\bowtie	X	WATER VALVE
đ		FIRE HYDRANT
⊄ ₩	K W	FIRE DEPARTMENT CO WATER METER
0	0	WATER SERVICE OR C
— w —	— w —	
Ø	ø	UTILITY POLE
((GUY WIRE
	OE	
	E	
	© ————————————————————————————————————	COMMUNICATIONS BOX
	F0	
	G	
D	D	STORM DRAIN MANHO
>	>	CULVERT END
	SD	
—D—D—		DITCH
X.X%	X.X%	DRAINAGE ARROW
FG 7500.00	FG 7500.00	SPOT ELEVATION


<u>LEGEND</u>


ROPERTY LINE ONTOURS MAJOR NTOURS MINOR PHALT **NCRETE** AVEL NCE NITARY SEWER SERVICE NITARY CLEANOUT NITARY LINE END CAP NITARY SEWER MANHOLE NITARY SEWER LINE TER MANHOLE TER VAULT TER VALVE E HYDRANT DEPARTMENT CONNECT TER METER TER SERVICE OR CURB STOP TER LINE ILITY POLE WIRE ECTRIC LINE OVERHEAD ECTRIC LINE UNDERGROUND MMUNICATIONS BOX MMUNICATIONS LINE BER OPTICS s line ORM DRAIN MANHOLE JLVERT END ORM DRAIN LINE ГCH RAINAGE ARROW POT ELEVATION

PROJECT	7122.75084.01
DATE	06/18/2020
DRAFTER	СН
CHECKED	DQ





PRELIMINARY NOT FOR CONSTRUCTION






				2	ð	ğ
				WOILD	AENTS	RE SUPPRESSION
N 10 ¹⁰³³				BELV DATE DATE DESCRIPTION	1 08/06/20 REVISED PER TOWN	e 08/25/20 REVISED BUILI
LOT 15 AREAS AL AREA OF PROPERTY ILDING COVERAGE CKS AND PORCHES W CONCRETE STING ON-SITE SIDEWALKS AL PERVIOUS AREA	21,529.00 3,101.39 268.19 902.19 785.69	CRESPER0.4940.0710.0060.0210.0180.378	CENTAGE 100% 14.41% 1.25% 4.19% 3.65% 76.51%			
PERVIOUS AREAS	5,057.45	0.116	23.49%			
SITE NEW CONC	198.20	0.005				LAURA STREET TRIPLEX SITE PLAN RIDGWAY, COLORADO
	PROPOSED	RIGHT-OF- ROAD CENT EASEMENT PROPERTY CONTOURS CONTOURS ASPHALT CONCRETE GRAVEL SIGN FENCE	ERLINE LINE MAJOR	PRC DAT DRA CHE	JEC ⁻ E FTEF CKE	T 7122.75084.01 06/18/2020 R CH







22\75084-01\65CAD\MC-CB-75084 HABITAT.dwg PLOT DATE 2020-8-25 16:15 SAVED DATE 2020-08-25 16:14 USER: chamma



General Information

TOWN HALL PO Box 10 | 201 N. Railroad Street | Ridgway, Colorado 81432 | 970.626.5308 | www.town.ridgway.co.us

Fire Suppression Tap Application

Marcani and		
Officia	Use Only	
Date Receiv	red: 8-9-7-1	2
nitials:	0,	

Applicant Name Habitat for Humanity of the San Juans			
	er of Record		
N Laura S	treet 702,704,	706 N. Laura S	
Filing	Lot 15	Block	
Tap Size Re	Tap Size Requested (diameter in inches) 2.5"		
)	Juans Enginer) N Laura S Filing Tap Size Re	Juans Engineer of Record N Laura Street 702, 704, Filing Lot 15	

Excavation and Encroachment Permit Application with fee and bond, payable to the Town of Ridgway

Copy of completed fire flow test demonstrating sufficient fire flow for the proposed suppression system

Letter from the fire suppression system Professional Engineer indicating required tap size with supporting documentation

\$500.00 fire suppression tap fee, payable to the Town of Ridgway

The applicant understands that this permit, when issued, constitutes an agreement between the Town of Ridgway and the property owner under the following terms and conditions:

- 1. **Fire Suppression Tap Application:** This application, with all requisite documents and fees, as defined below, must be submitted to the Town prior to excavating in the right-of-way or performing the tap.
- 2. **State Permits Required:** All fire suppression systems require approval through the State. Applicant is responsible for coordinating all State requirements for a fire suppression system.
- 3. Encroachment and Excavation Permit Application: Applicant is responsible for excavation to the main water line, tapping the water line, backfill & re-compaction of the trench in the Town's right-ow-way. To excavate into the Town right-of-way for access to the main water line an Encroachment and Excavation application must be completed & approved, with applicable fees & bond paid to the Town. The Applicant must apply for and receive an Encroachment and Excavation permit from the Town and is subject to all terms & conditions of the executed permit.
- 4. Engineered Fire Suppression System: The Applicant must submit an engineered Fire Suppression System Plan indicating the size of the tap and Pressure Reducing Valve (if applicable), required. Any tap greater than ½ the size of the main water line to be tapped must be installed with a "tee" in the main. Taps smaller than ½ the diameter may be installed by "hot" tap or a "tee". Should it be necessary to shut off the main, Applicant shall



Applicant Signature

TOWN HALL PO Box 10 1 201 N. Railroad Street 1 Ridgway, Colorado 81432 | 970.626.5308 | www.town.ridgway.co.us

provide notices to impacted water users consistent with the Town's standards. Applicant shall work with impacted water users to mitigate the impacts.

- 5. Fire Flow Test: Applicant shall arrange for and pay any applicable fees for a fire flow test. The Town Public Works Department must be contacted to schedule this test that ensures sufficient water flow for the proposed suppression system. A representative of the Town must be present to observe the flow test.
- 6. Work in Town Right-of-Way and Making the Tap: A representative of the Town must be present to observe all activities in the right-of-way or easement, including observation of the tap installation. In addition, a certified state inspector must also be present to approve the underground water supply line from the main water line to the riser. The Applicant is responsible for coordinating these activities with the Town and the appropriate state officials. The Applicant is also responsible for reimbursing the Town for out-of-pocket expenditures.
- 7. Safety Devices: The grantee of this permit is responsible (at his expense) for compliance with the Manual on Uniform Traffic Control Devices (MUTCD), including all lights, flares, barricades, walkways, covers and other safety devices that are required by Town and State law to properly protect the public during the progress of all work under this permit.
- 8. Standard Specifications: The minimum specification for materials to be used, the method of installation and all conditions of use for all enlargements or attachments to the Town owned utility systems are governed by the Town Standards for these systems as though the same were incorporated herein. Copies of these regulations the are available upon request. The applicant, if not the property owner, certifies by the signature noted below that he is an authorized agent for the owner and will inform the owner of the terms of this agreement, including the is an authorized agent for the owner and will inform the owner of the terms of this agreement, including compliance when in the owner of the terms of this agreement, including the is an authorized agent for the owner and will inform the owner of the terms of this agreement, including the is an authorized agent for the owner and will inform the owner of the terms of this agreement, including the is an authorized agent for the owner and will inform the owner of the terms of this agreement, including compliance with the Ridgway Municipal Code, which he/she has made in the owner's behalf.

08/04/2020	Digitally signed by Erica L. Madison Date: 2020.08.04 11:06:29 -06'00'	NIAGISON	Erica L.
	Digitally signed by Erica L. Madison	acciperv	

eteO

	.bəbəən ٲi ,əvibV ϱn		int is also required to purchase	
22.22.01		72,201 # y>>y)	_009 s	Jotal Fees Due
				Size of Fire Suppression/ Water Tap Required
tnən	New 🗌 Replacen	Service Status:	sidential 🛐 Business	Type of Service:
				Vficial Use Only

Rec \$9/22

Land Title Guarantee Company

Date:February 02, 2017



HABITAT FOR HUMANITY OF THE SAN JUANS P.O. BOX 162 MONTROSE, CO 81402 colleen@buildinglives.org

Subject: Attached Title Policy OX85004389.2136365 for 400 N LAURA ST, RIDGWAY, CO 81432

Enclosed please find the Owner's Title Insurance Policy for your purchase of the property listed above.

This title policy is the final step in your real estate transaction, and we want to take a moment to remind you of its importance. Please review all information in this document carefully and be sure to safeguard this policy along with your other legal documents.

Your owner's policy insures you as long as you own the property and requires no additional premium payments.

Please feel free to contact any member of our staff if you have questions or concerns regarding your policy, or you may contact the Final Policy Department at Phone: 303-850-4158 or Email Address: finals@ltgc.com

As a Colorado-owned and operated title company for over 45 years, with offices throughout the state, we take pride in serving our customers one transaction at a time. We sincerely appreciate your business and welcome the opportunity to assist you with any future real estate needs. Not only will Land Title be able to provide you with the title services quickly and professionally, but you may also be entitled to a discount on title premiums if you sell or refinance the property described in the enclosed policy.

Thank you for giving us the opportunity to work with you on this transaction. We look forward to serving you again in the future.


Sincerely,

Land Title Guarantee Company

30-71-3 betqoba YOLJO9 S'RENWO NOTALOOSSA BUTTT DIAL NADIREMA

το.06.ροίιςγ.ρg2.οπ.οd

Copyright 2006-2015 American Land Title Association. All rights reserved. The use of this form is restricted to ALTA licensees and ALTA members in good standing as of the date of



(b) The lies of real service races or assessments imposed on the Tride by a governmental authority due or payable, but unpaid.
(c) Any encroachment, encumbrance, violation, variation, or adverse circumstance affecting the Tride that would be disclosed by an accurate and (c) Any encroachment, encroachment, encroachment, encroachment, encroachment or adverse circumstance affecting the Tride that would be disclosed by an accurate and encomplete land survey of the Land. The term "encroachments of existing improvements located on the Land onto adjoining land, and encroachments onto the Land of existing improvements of existing inprovements located on the Land onto adjoining land. means authorized by law; or (vii) a defective judicial or administrative proceeding.

(vi) a document not properly filed, recorded, or indexed in the Public Records including failure to perform those acts by electronic

perform those acts necessary to create a document by electronic means authorized by law; (v) a document executed under a falsified, expired, or otherwise invalid power of attorney;

(iii) a document affecting Title not properly created, executed, witnessed, sealed, acknowledged, notarized, or delivered; (iv) failure to authorized a transfer or conveyance;


(i) forgery, fraud, undue influence, duress, incompetency, incapacity, or impersonation; (ii) failure of any person or Entity to have Any defect in the Title caused by (a) A defect in the Title covered Risk includes but is not limited to insurance against loss from (a) A defect in the Title caused by

Title being vested other than as stated in Schedule A.

the Amount of Insurance, sustained or incurred by the Insured by reason of:

"Company", insures, as of Date of Policy and, to the extent stated in Covered Risks 9 and 10, after Date of Policy, against loss or damage, not exceeding

SUBJECT TO THE EXCLUSIONS FROM COVERAGE, THE EXCEPTIONS FROM COVERAGE CONTRINED IN SCHEDULE B AND THE CONDITIONS, OLD REPUBLIC NATIONAL TITLE INSURANCE COMPANY, & Minnesola corporation, (the



т

COVERED RISKS

AUNDER THIS POLICY MUST BE GIVEN TO THE COMPANY AT THE ADDRESS SHOWN IN SECTION 18 OF THE CONDITIONS

OWNER'S POLICY OF TITLE INSURANCE

EXCLUSIONS FROM COVERAGE

The following matters are expressly excluded from the coverage of this policy, and the Company will not pay loss or damage, costs, attorneys' fees, or expenses that arise by reason of:

(a) Any law, ordinance, permit, or governmental regulation (including those relating to building and zoning) restricting, regulating, prohibiting or relating to 1.

(i) the occupancy, use, or enjoyment of the Land;
 (ii) the character, dimensions, or location of any improvement erected on the Land;

- (iii) the subdivision of land; or
- (iv) environmental protection:
- provided under Covered Risk 5.
- (b) Any governmental police power. This Exclusion 1(b) does not modify or limit the coverage provided under Covered Risk 6. Rights of eminent domain. This Exclusion does not modify or limit the coverage provided under Covered Risk 7 or 8. Defects, liens, encumbrances, adverse claims, or other matters 2.
- З.
 - (a) created, suffered, assumed, or agreed to by the insured Claimant:
 - (b) not Known to the Company, not recorded in the Public Records at Date of Policy, but Known to the Insured Claimant and not disclosed in writing to the Company by the Insured Claimant prior to the date the Insured Claimant became an Insured under this policy;
 - (c) resulting in no loss or damage to the Insured Claimant:

 - (d) attaching or created subsequent to Date of Policy (however, this does not modify or limit the coverage provided under Covered Risk 9 and 10); or
 (e) resulting in loss or damage that would not have been sustained if the Insured Claimant had paid value for the Title.
 4. Any claim, by reason of the operation of federal bankruptcy, state insolvency, or similar creditors' rights laws, that the transaction vesting the Title as shown in Schedule A, is
- in Schedule A, is
 (a) a fraudulent conveyance or fraudulent transfer; or
 (b) a preferential transfer for any reason not stated in Covered Risk 9 of this policy.
 Any lien on the Title for real estate taxes or assessments imposed by governmental authority and created or attaching between Date of Policy and the date of recording of the deed or other instrument of transfer in the Public Records that vests Title as shown in Schedule A. 5.

CONDITIONS

1. DEFINITION OF TERMS

- (a) "Amount of Insurance": The amount stated in Schedule A, as may be increased or decreased by endorsement to this policy, increased by Section 8(b) or (b) "Date of Policy": The date designated as "Date of Policy" in Schedule A.
- (b) "Date of Policy": The date designated as "Date of Policy" in Schedule A.
 (c) "Entity": A corporation, partnership, trust, limited liability company, or other similar legal entity.
 (d) "Insured": The Insured named in Schedule A.

(i) The term "Insured" also includes

(A) successors to the Title of the Insured by operation of law as distinguished from purchase, including heirs, devisees, survivors,

(a) successors to an insured by dissolution, merger, consolidation, distribution, or reorganization; (C) successors to an insured by its conversion to another kind of Entity:

(D) a grantee of an Insured under a deed delivered without payment of actual valuable consideration conveying the Title
 (1) if the stock, shares, memberships, or other equity interests of the grantee are wholly-owned by the named Insured,
 (2) if the grantee wholly owns the named Insured,

(3) if the grantee is wholly-owned by an affiliated Entity of the named Insured, provided the affiliated Entity and the named Insured are

wholly-owned by the same person or Entity, or

(4) if the grantee is a trustee or beneficiary of a trust created by a written instrument established by the Insured named in Schedule A for estate planning purposes

(ii) With regard to (A), (B), (C), and (D) reserving, however, all rights and defensed as to any successor that the Company would have had

(e) "Insured Claimant": An Insured claiming loss or damage.
 (f) "Knowledge" or "Known": Actual knowledge, not constructive knowledge or notice that may be imputed to an Insured by reason of the Public Records or any other records that impart constructive notice of matters affecting the Title.

any other records that impart constructive notice of matters affecting the Title. (g) "Land": The land described in Schedule A, and affixed improvements that by law constitute real property. The term "Land" does not include any property beyond the lines of the area described in Schedule A, nor any right, title, interest, estate, or easement in abutting streets, roads, avenue, alleys, lanes, ways, or waterways, but this does not modify or limit the extent that a right of access to and from the Land is insured by this policy. (h) "Mortgage": Mortgage, deed of trust, trust deed, or other security instrument, including one evidenced by electronic means authorized by law. (i) "Public Records": Records established under state statutes at Date of Policy for the purpose of imparting constructive notice of matters relating to real property to purchasers for value and without. Knowledge. With respect to Covered Risk 5(d), "Public Records" shall also include environmental protection (i) "Title": The estate or interest described in Schedule and is located.

(i) "Title"

(i) "Title": The estate or interest described in Schedule A. "Unmarketable Title": Title affected by an alleged or apparent matter that would permit a prospective purchaser or lessee of the Title or lender on the Title to be released from the obligation to purchase, lease, or lend if there is a contractual condition requiring the delivery of marketable title. 2. CONTINUATION OF INSURANCE

The coverage of this policy shall continue in force as of Date of Policy in favor of an Insured, but only so long as the Insured retains an estate or interest in the Land, or holds an obligation secured by a purchase money Mortgage given by a purchaser from the Insured, or only so long as the Insured shall have liability by reason of warranties in any transfer or conveyance of the Title. This policy shall not continue in force in favor of any purchaser from the Insured of either (i) an estate or interest in the Land, or (ii) an obligation secured by a purchase money Mortgage given to the Insured. 3. NOTICE OF CLAIM TO BE GIVEN BY INSURED CLAIMANT

The Insured shall notify the Company promptly in writing (i) in case of any litigation as set forth in Section 5(a) of these Conditions, (ii) in case Knowledge shall come to an Insured hereunder of any claim of title or interest that is adverse to the Title, as insured, and that might cause loss or damage for which the Company may be liable by virtue of this policy, or (iii) if the Title, as insured, is rejected as Unmarketable Title. If the Company is prejudiced by the failure of the Insured Claimant to provide prompt notice, the Company's liability to the Insured Claimant under the policy shall be reduced to the extent of the prejudice.

In the event the Company is unable to determine the amount of loss or damage, the Company may, at its option, require as a condition of payment that the Insured Claimant furnish a signed proof of loss. The proof of loss must describe the defect, lien, encumbrance, or other matter insured against by this policy that constitutes the basis of loss or damage and shall state, to the extent possible, the basis of calculating the amount of the loss or damage.

5. DEFENSE AND PROSECUTION OF ACTIONS

5. DEFENSE AND PROSECUTION OF ACTIONS
(a) Upon written request by the Insured, and subject to the options contained in Section 7 of these Conditions, the Company, at its own cost and without unreasonable delay, shall provide for the defense of an Insured in litigation in which any third party asserts a claim covered by this policy adverse to the Insured. This obligation is limited to only those stated causes of action alleging matters insured against by this policy. The Company shall have the right to select counsel of its choice (subject to the right of the Insured to object for reasonable cause) to represent the Insured as to those stated causes of action. It shall not be liable for and will not pay the fees of any other counsel. The Company will not pay any fees, costs, or expenses incurred by the Insured in the defense of those causes of action that allege matters not

Tee, ACDITICATION Either the Company or the Insured may demand that the claim or controversy shall be submitted to arbitration pursuant to the Title Insurance Arbitration Rules of the Either the Company or the Insured may demand that the claim or controversy shall be no joinder or consolidation with claims or controversies of other persons. American Late Association ("Rules"). Except as provided in the Rules, there shall be no joinder or consolidation with claims or controversies of other persons. American late Association ("Rules"). Except as provided in the Rules, there shall be no joinder or consolidation with claims or controversies of spoicy provision, or to any other controversy or claim anising out of the inanscripe guing is to this policy. All shiftshele in connection with its issuance or the breach of a policy provision, or to any other controversy or claim anising out of the inaureaction giving is a to this policy. All shiftshele matters when the Amount of Insurance is in excess of \$2,000,000 or less shall be arbitrated at the option of either the Company or the Insured. Arbitrable matters when the Monunt of Insurance is in excess of \$2,000,000 or less shall be arbitrated to by both the Company and the Insured. Arbitration pursant to this policy and mount of Insurance is in excess of \$2,000,000 or less shall be and the option of either the Company and the Insured. Arbitration pursant to the mount of Insurance is in excess of \$2,000,000 shall be arbitrated only when agreed to by both the Company and the Insured. Arbitration pursant to the mount of Insurance is in excess of \$2,000,000 shall be arbitrated only when agreed to by both the Company and the Insured. Arbitration pursant to the adrift and the Sume of the Building upon the parties. Judgment upon the award tendered by the Arbitration (s) may be entered in any count of competent jurisdiction. **NOITAATIBAA .41**

(b) The Company's right of subrogation includes the rights of the Insured to indemnities, guaranties, other policies of insurance, or bonds, notwithstanding any terms or conditions contained in those instruments that address subrogation rights.

(a) Whenever the Company shall have scaled and paid a claim under this policy, it shall be subrogated and entitled to the rights of the Insured Claimant in the Title and all onter rights and remedies in respect to the claim that the Insured Claimant has against any person or property, to the extent of the amount of any loss, costs, all onter rights and remedies in respect to the claim that the Insured Claimant has against any person or property, to the extent of the amount of any loss, costs, allowers and remedies in respect to the claim that the Insured Claimant has against any person or property, to the extent of the Insured Claimant shall execute documents to evidence the transfer to the Company of these rights and remedies. The Insured Claimant is any uncoling these rights and remedies. The Insured Claimant shall permit the Company to sue, compromise, or settle in the name of the Insured Claimant and to use the Insured Claimant is any transaction or lingation involving these rights and remedies. The Insured Claimant shall permit the Company to sue, compromise, or settle in the name of the Insured Claimant is any transaction or lingation involving these rights and remedies. If a payment on account of a claim does not fully cover the loss of the Insured Claimant and to use the Insured Claimant and in any transaction or lingation involving these rights and remedies. If a payment on account of a claim does not fully cover the loss of the Insured Claimant and the company to sue, componise, or settle in the ranse of the Insured Claimant and to use the Insured Claimant and the company that the Insured Claimant and the company to sue, compromise, or settle in the name of the Insured Claimant and to use the Insured Claimant and the convert of the Insured Claimant and the convert of the Insured Claimant and the convert of the Insured Claimant and the convert and the Insured Claimant and the convert of the Insured Claimant and the convert of the Insured Claimant and the convert and the convert and the claimant and

When liability and the extent of loss or damage have been definitely fixed in accordance with these Conditions, the payment shall be made within 30 days. 13. RIGHTS OF RECOVERY UPON PAYMENT OR SETTLEMENT 12. PAYMENT OF LOSS

The known of insurance shall be reduced by any amount the Company pays under any policy insuring a Morigage to which exception is taken in Schedule B or to which the insured has agreed, assumed, or taken subject, or which is executed by an insured after Date of Policy and which is a charge or lien on the Title, and the amount so paid shall be deemed a payment to the insured under this policy. ΕΙΑΒΙLITY ΝΟΝΟυΜυλΑΤΙΛΕ

nder this policy, except payments made for costs, attorneys' fees, and expenses, shall reduce the Amount of Insurance by the amount of the payment. consent of the Company. 10. REDUCTION OF INSURANCE; REDUCTION OR TERMINATION OF LIABILITY

(a) If the Company establisher the Title, or removes the alleged defect, lien, or encumbrance, or cures the lack of a right of access to or from the Land, or cures the claim is the Title, or removes the alleged defect, lien, or encumbrance, or cures the lack of a right of access to or from the Land, or cures the claim is to bugations with respect to that matter and shall not be liable for any instance by any method, including litigation by the Company stability for loss or damage until there (c) The Company stability for loss or damage to the Insured.
 (b) In the event of any litigation, including litigation by the Company or with the Company's consent, the Company shall have no liability for loss or damage until there is a final determination by a court of company or with the Company's consent, the Company shall have no liability for loss or damage until there (c) The Company shall not be liable for loss or damage to the Insured.

Claimant or as of the date it is settled and paid. (c) In addition to the extent of liability under (a) and (b), the Company will also pay those costs, attorneys' fees, and expenses incurred in accordance with Sections 5 and 7 of these Conditions. (a) If the Company externations are extent of liability under (b), the Company will also pay those costs, attorneys' fees, and expenses incurred in accordance with (b) If the Company externations are extent of the Company will also pay those costs, attorneys' fees, and expenses incurred in accordance with (b) If the Company establishes the Tailo are extent of the Company will also pay those costs, attorneys' fees, and expenses incurred in accordance with (c) If the Company establishes the Tailo are extented in a context of the company establishes the Tailo are extented in a context of the Company establishes the Tailo are extented in accordance with the the company establishes the Tailo are extented in a context of the extented in a context of the extented in accordance with a context of the extented in a context of the extented in accordance with a context of the extent of the extented in accordance with a context of the extente

(ii) the difference between the value of the Title as insured and the value of the Title subject to the risk insured against by this policy. (b) If the Company pursues its rights under Section 5 of these Conditions and is unsuccessful in establishing the Title, as insured,

(i) the Amount of Insurance: or

This policy is a contract of indemnity against actual monetary loss or damage sustained or incurred by the Insured Claimant who has suffered. loss or damage by reason of matters insured against by this policy. (a) The extert of liability of the Company for loss or damage under this policy shall not exceed the lesser of (a) The extert of liability of the Company for loss or damage by reason. 8. DETERMINATION AND EXTENT OF LIABILITY

A AND EXTENT OF LIABILITY defend, prosecute, or continue any litigation. Upon the exercise by the Company of either of the options provided for in subsections (b)(i) or (ii), the Company's obligations to the Insured under the restricted of the company's obligations to the instruction to the the desired of the company's obligations to the instruction of the company's obligations to the instruction of the company's obligations to the company's obligations to the company of the company's obligations to the company of the company's obligations to the instruction of the company's obligations to the instructions to the company's obligations to the company's obligations to the company of the company's obligations to the company to the company's obligations to the company's obligati Ked of bay.

(ii) To pay or otherwise settle with the Insured Claimant that were authorized by the Company up to the time of payment and that the Company is obligated to pay; or (iii) To pay or otherwise settle with the Insured Claimant the loss or damage provided for under this policy, together with any costs, attorneys' (ies, and expensed incurred by the Insured Claimant that were authorized by the Company up to the time of payment and that the Company is obligated to pay

(a) To Pay or Tender Payment of the Amount of Insurance.
 (b) To Pay or Tender Payment of the Amount of Insurance.
 To pay or tender payment of the Amount of Insurance.
 To pay or tender payment of the Amount of Insurance.
 To pay or tender payment of the Amount of Insurance.
 To pay or tender payment of the Amount of Insurance.
 To pay or tender payment of the Amount of Insurance.
 To pay or tender payment of the Amount of Insurance under this policy, other than to make the payment is obligated to pay. Upon the exercise by the Company to the Insured under this policy, other than to make the payment that were authorized by the Company to the Insured that the Company is obligated to pay. Upon the exercise (b) To Pay or Othernhaic settle with outling any liability or obligation to defend, prosecute, or continue any litigation.
 (b) To Pay or Othernhaise Settle with Other parties for or in the name of an Insured Claimant.
 (b) To Pay or Othernhaise Settle with Other parties for or in the name of an Insured Claimant.
 (c) To Pay or othernhaise settle with other parties for or in the name of an Insured Claimant.
 (d) To Pay or othernhaise settle with other parties for or in the name of an Insured Claimant.
 (e) To Pay or othernhaise settle with other parties for or in the name of an Insured Claimant.
 (f) To Pay or othernhaise settle with other parties for or in the name of an Insured Claimant.
 (f) To Pay or othernhaise settle with other parties for or in the name of an Insured Claimant.
 (h) To Pay or othernhaise settle with other parties for or in the name of an Insured Claimant.
 (h) To Pay or othernhaise settle with other parties for or in the name of an Insured Claimant.

In case of a claim under this policy, the Company shall have the following additional options:

the matter or matters requiring such cooperation. (b) The Company may reasonably require the Insured Claimant to submit to examination under oath by any authorized representative of the Company and to produce for examination, Inspection, and copying, at such reasonable innes and places as may be designated by the authorized representative of the Company, all records, in whatever medium maintained, including pooks, ledgers, checks, memorands, correspondence, reports, e-mails, disks, lapse, and videos whether bearing a date before prant that reasonably perain to the loss or damage. Further, if requested by any authorized representative of the Company, the Insured Claimant shall prant that reasonably perain to the loss or damage. Further, if requested by any authorized representative of the Company, the Insured Claimant shall prant that reasonably perain to the loss or damage. Further, if requested by any authorized representative of the Company to examine that reasonably perain to the loss or damage. All information to the company in the administration of the claim. Failure of the Insured Claimant to prant that reasonably perain to the reasonable judgment of the Company, to examine inspect, and copy all of the company pursuant to prant that reasonably perain to the loss or damage. All information, or great permission to secure reasonably necessary information from third parties as about to be disclosed to other unless, in the reasonably requested information, or great permission to secure reasonably necessary information from third parties about the disclosed to other unless. In the reasonably requested information, or great permission to secure reasonably necessary information from third parties as the administration under this policy, the Company shall have the following additional options: To **PATIONS TO PAY OR OTHERWINE SETTLE CLAIMS; TERMINATION OF LIABILITY PATIONS TO PAY OR OTHERWINE SETTLE CLAIMS;** Termination is a claim under this policy, the Company shall have the following additional o

(a) In all cases where this policy permits or requires the Company to prosecute or provide for the defense of any action or proceeding and any appeals, the Insured shall secure to the Company the right to so prosecute or provide defense in the action or proceeding, including the right to use, at its option, the name of the Insured for this purpose. Whenever requested by the Company, the Insured, at the Company's expense, shall give the Company all reasonable and (i) in securing evidence, obtaining witnesses, prosecuting or defending the action or proceeding, or effecting settlement, and (ii) in any other lawful act that in the optinion of the Company may be witnesses, prosecuting or defending the action or proceeding, or effecting settlement, and (ii) in any other lawful act that in the optinion of the company may be metherses, prosecuting or defending the action or proceeding, or effecting settlement, and (ii) in any other lawful act that in the optinion of the company may be metherses, prosecuting or defending the action or proceeding, or effecting action to the lower to funcish the required cooperation, the Company's obligation to the Insured under the policy shall terminate, including any liability or obligation to defend, prosecute, or continue any litigation, with regard to the matter required cooperation.

insured against by this policy. (b) The Company shall have the right, in addition to the options contained in Section 7 of these Conditions, at its own cost, to institute and prosecute any action of the proceeding or to do any other act that in its option may be necessary or desirable to establish the Title, as insured, or to prevent or reduce loss or damage to the proceeding or to do any other act that in its option may be necessary or desirable to establish the Title, as insured, or to prevent or reduce loss or damage to the proceeding or to do any other act that in its option may be necessary or desirable to esterise its rights under this subsection, it must to so diligenly. (c) Whenever the Company may take any appropriate action under the terms of this policy, whether or not it shall be liable to the Insured. The exercise of these rights shall be under the ting subsection, it must to so diligenly. (c) Whenever the Company brings an action or asserts a defense as required or permitted by this policy, the Company may pursue the liugation to a final determination in the company prover the Company brings on a significant or and it expressly reserves the right, in its sole discretion, to appeal any adverse judgment or order. (c) Whenever the Company brings an action or asserts a defense as required or permitted by this policy, the Company may pursue the liugation to a final determination in a compresent jurisdiction, and it expressly reserves the right, in its sole discretion, to appeal any adverse judgment or order. (a) the company brings and any appropriate action or asserts a defense as required or permitted by this policy, the Company may pursue the liugation to a final determination is a final determination. (b) the company adverse judgment or order to endore or any action or note: (c) Whenever the Company provide the report.

15. LIABILITY LIMITED TO THIS POLICY; POLICY ENTIRE CONTRACT

(a) This policy together with all endorsements, if any, attached to it by the Company is the entire policy and contract between the Insured and the Company. In interpreting any provision of this policy, this policy shall be construed as a whole.
(b) Any claim or loss or damage that arises out of the status of the Title or by any action asserting such claim shall be restricted to this policy.
(c) Any amendment of or endorsement to this policy must be in writing and authenticated by an authorized person, or expressly incorporated by Schedule A of this policy.
(d) Each endorsement to this policy issued at any time is made a part of this policy and is subject to all of its terms and provisions. Except as the endorsement expressly states, it does not (i) modify any of the terms and provisions of the policy, (ii) modify any prior endorsement, (iii) extend the Date of Policy, or (iv) increase the Amount of Insurance. Insura

16. SEVERABILITY

In the event any provision of this policy, in whole or in part, is held invalid or unenforceable under applicable law, the policy shall be deemed not to include that provision or such part held to be invalid, but all other provisions shall remain in full force and effect.

17. CHOICE OF LAW; FORUM

(a) Choice of Law; The Insured acknowledges the Company has underwritten the risks covered by this policy and determined the premium charged therefor in reliance upon the law affecting interests in real property and applicable to the interpretation, rights, remedies, or enforcement of policies of title insurance of the jurisdiction where the Land is located.

Therefore, the court or an arbitrator shall apply the law of the jurisdiction where the Land is located to determine the validity of claims against the Title that are adverse to the Insured and to interpret and enforce the terms of this policy. In neither case shall the court or arbitrator apply its conflicts of law principles to determine the

(b) Choice of Forum; Any litigation or other proceeding brought by the Insured against the Company must be filed only in a state or federal court within the United States of America or its territories having appropriate jurisdiction. 18. NOTICES, WHERE SENT

Any notice of claim and any other notice or statement in writing required to be given to the Company under this policy must be given to the Company at: 400 Second Avenue South, Minneapolis, Minnesota 55401, (612) 371-1111.

ANTI-FRAUD STATEMENT: Pursuant to CRS 10-1-128(6)(a), it is unlawful to knowingly provide false, incomplete, or misleading facts or information to an insurance company for the purpose of defrauding or attempting to defraud the company. Penalties may include imprisonment, fines, denial of insurance and civil damages. Any insurance company or agent of an insurance company who knowingly provides false, incomplete, or misleading facts or information to a policyholder or claimant for the purpose of defrauding or attempting to defraud the policyholder or claimant with regard to a settlement or award payable from insurance proceeds shall be reported to the Colorado division of insurance within the department of regulatory agencies.

This anti-fraud statement is affixed to and made a part of this policy.

AMERICAN LAND TITLE ASSOCIATION OWNER'S POLICY Adopted 6-17-06 Copyright 2006-2015 American Land Title Association. All rights reserved. ao.06.policy.cover.odt

Land Title Guarantee Company Representing Old Republic National Title Insurance Company

A slubsdoz

Policy Number: OX85004389.2136365

Order Number: OU 85004389

00.002,88\$::muomA

400 N LAURA ST, RIDGWAY, CO 81432 Property Address:

1. Policy Date:

December 27, 2016 at 5:00 P.M.

2. Name of Insured:

SNAUL NAS 3HT 3O YTINAMUH SO3 TATIBAH

this policy is: 3. The estate or interest in the Land described or referred to in this Schedule and which is covered by

A FEE SIMPLE

4. Title to the estate or interest covered by this policy at the date is vested in:

SNAUL NAS 3HT 30 YTINAMUH 903 TATIBAH

5. The Land referred to in this Policy is described as follows:

LOT 15, PARKSIDE SUBDIVISION, COUNTY OF OURAY, STATE OF COLORADO.

This Policy Valid only if Schedule B is attached.

Land Title Guarantee Company Representing Old Republic National Title Insurance Company (Schedule B) Policy Number OX85004389,2136365 Order Number 85004389 THIS POLICY DOES NOT INSURE AGAINST LOSS OR DAMAGE BY REASON OF THE FOLLOWING: ANY FACTS, RIGHTS, INTERESTS, OR CLAIMS THEREOF, NOT SHOWN BY THE PUBLIC RECORDS BUT 1) THAT COULD BE ASCERTAINED BY AN INSPECTION OF THE LAND OR THAT MAY BE ASSERTED BY PERSONS IN POSSESSION OF THE LAND. EASEMENTS, LIENS OR ENCUMBRANCES, OR CLAIMS THEREOF, NOT SHOWN BY THE PUBLIC RECORDS. ANY ENCROACHMENT, ENCUMBRANCE, VIOLATION, VARIATION, OR ADVERSE CIRCUMSTANCE 3) AFFECTING THE TITLE THAT WOULD BE DISCLOSED BY AN ACCURATE AND COMPLETE LAND SURVEY OF THE LAND AND NOT SHOWN BY THE PUBLIC RECORDS. ANY LIEN, OR RIGHT TO A LIEN, FOR SERVICES, LABOR OR MATERIAL HERETOFORE OR HEREAFTER 4) FURNISHED, IMPOSED BY LAW AND NOT SHOWN BY THE PUBLIC RECORDS. (A) UNPATENTED MINING CLAIMS; (B) RESERVATIONS OR EXCEPTIONS IN PATENTS OR IN ACTS 5) AUTHORIZING THE ISSUANCE THEREOF; (C) WATER RIGHTS, CLAIMS OR TITLE TO WATER. TAXES AND ASSESSMENTS FOR THE YEAR 2016 AND SUBSEQUENT YEARS. 6) SUBJECT TO ANY VESTED AND ACCRUED WATER RIGHTS FOR MINING, AGRICULTURAL. 7) MANUFACTURING, OR OTHER PURPOSES, AND RIGHTS TO DITCHES AND RESERVOIRS USED IN CONNECTION WITH SUCH WATER RIGHTS, ALSO SUBJECT TO THE RIGHT OF THE PROPRIETOR OF A VEIN OR LODE TO EXTRACT AND REMOVE HIS ORE THEREFROM, SHOULD THE SAME BE FOUND TO INTERSECT THE PREMISES HEREBY GRANTED IN UNITED STATES PATENT RECORDED AUGUST 7, 1891 IN BOOK 8 AT PAGE 454 AND RECORDED MARCH 7, 1916 IN BOOK 64 AT PAGE 458. RESERVATION OF INTEREST IN OIL, GAS AND MINERAL RIGHTS BY CORA CARMICHAEL, ROBERTA WILLIAMS AND CLIEVE CARMICHAEL IN DEED RECORDED DECEMBER 26, 1961 IN BOOK 162 AT PAGE 191. SUBJECT TO NOTICE CONCERNING UNDERGROUND FACILITIES OF SAN MIGUEL POWER <u>9</u>} ASSOCIATION RECORDED JUNE 22, 1993 IN BOOK 227 AT PAGE 145. TERMS AND CONDITIONS OF THE OURAY COUNTY WEED MANAGEMENT RESOLUTION RECORDED 10) AUGUST 8, 1997 AT RECEPTION NO. 164857. TERMS, CONDITIONS, STIPULATIONS, OBLIGATIONS AND PROVISIONS OF GRANT OF DRAINAGE 11) EASEMENT BETWEEN KOLOWICH GROUP, INC. AND RIDGWAY LIGHT INDUSTRIAL, LLC AND RIDGWAY RIVER RANCHES, LLC, A COLORADO LIMITED LIABILITY COMPANY RECORDED DECEMBER 11, 2001 AT RECEPTION NO. 176400. EASEMENTS, CONDITIONS, COVENANTS, RESTRICTIONS, RESERVATIONS, PROVISIONS AND NOTES 12) ON THE RECORDED PLAT OF RIVER PARK RIDGWAY BUSINESS PARK FILING NO. 1 RECORDED DECEMBER 18, 2001 AT RECEPTION NO. 176459. EASEMENTS, CONDITIONS, COVENANTS, RESTRICTIONS, RESERVATIONS, PROVISIONS AND NOTES 13) ON THE RECORDED PLAT OF ANNEXATION PLAT TO TOWN OF RIDGWAY RECORDED APRIL 9, 2003 AT RECEPTION NO. 180714. ORDINANCE #03-04 OF THE TOWN OF RIDGWAY FOR ANNEXATION OF THE SCHOOL ADDITION 14)RECORDED APRIL 17, 2003 AT RECEPTION NO. 180715.

\$45,000.00 RECORDED DECEMBER 27, 2016, UNDER RECEPTION NO. 217644. THE PUBLIC TRUSTEE OF OURAY COUNTY FOR THE USE OF ALPINE BANK TO SECURE THE SUM OF 23) DEED OF TRUST DATED DECEMBER 21, 2016, FROM HABITAT FOR HUMANITY OF THE SAN JUANS TO OF PARKSIDE SUBDIVISION RECORDED MARCH 19, 2008 UNDER RECEPTION NO. 197315. EASEMENTS, CONDITIONS, COVENANTS, RESTRICTIONS, RESERVATIONS AND NOTES ON THE PLAT (ZZ RECORDED MARCH 19, 2008 AT RECEPTION NO. 197314. TERMS, CONDITIONS AND PROVISIONS OF SUBDIVISION IMPROVEMENT AND SECURITY AGREEMENT (12 IN INSTRUMENT RECORDED MARCH 19, 2008, UNDER RECEPTION NO. 197316. THE EXTENT THAT SAID COVENENT OR RESTRICTION IS PERMITTED BY APPLICABLE LAW, AS CONTAINED ANCESTRY, OR SOURCE OF INCOME, AS SET FORTH IN APPLICABLE STATE OR FEDERAL LAWS, EXCEPT TO SEXUAL ORIENTATION, FAMILIAL STATUS, MARITAL STATUS, DISABILITY, HANDICAP, NATIONAL ORIGIN, OMITTING ANY COVENANTS OR RESTRICTIONS, IF ANY, BASED UPON RACE, COLOR, RELIGION, SEX, RESTRICTIVE COVENENTS, WHICH DO NOT CONTAIN A FORFEITURE OR REVERTER CLAUSE, BUT (∩Z RECEPTION NO. 18/041. 18, 2003 AT RECEPTION NO. 180738 AS SHOWN ON PLAT OF DEDICATION RECORDED JAUUARY 21, 2005 AT TF078T ON ON THE RECORDED PLAT OF BOUNDARY AND DEDICATION RECORDED JANUARY 21, 2005 AT RECEPTION EASEMENTS, CONDITIONS, COVENENTS, RESTRICTIONS, RESERVATIONS, PROVISIONS AND NOTES (8T NATIONAL BANK RECORDED APRIL 18, 2003 AT RECEPTION NO. 180741. INFRASTRUCTURE BETWEEN OURAY COUNTY SCHOOL DISTRICT R-2, KOLOWICH GROUP, INC. AND FIRST TERMS, CONDITIONS, STIPULATIONS, OBLIGATIONS AND PROVISIONS OF AGREEMENT REGARDING (2τ RECEPTION NO. 180740. & PIPELINE CO., A COLORADO CORPORATION AND FIRST NATIONAL BANK RECORDED APRIL 18, 2003 AT DISTRICT, R-2, KOLOWICH GROUP, INC., A COLORADO LIMITED LIABILITY COMPANY, ROUNDHOUSE WATER JOOHOS YTNUOD YAANO NEEWTER THERE EASEMENT BETWEEN OURAY COUNTY SCHOOL TERMS, CONDITIONS, STIPULATIONS, OBLIGATIONS AND PROVISIONS OF AGREEMENT RECARDING - (9τ TOWN OF RIDGWAY, COLORADO RECORDED APRIL 17, 2003 AT RECEPTION NO. 180716. DECLARATION OF COVENANTS BETWEEN KOLOWICH GROUP, INC. A COLORADO CORPORATION AND THE TERMS, CONDITIONS, STIPULATIONS, OBLIGATIONS AND PROVISIONS OF AGREEMENT AND (GT Order Number 85004389 Policy Number OX85004389.2136365 (Schedule B) Land Title Guarantee Company Representing Old Republic National Title Insurance Company

Lambert and Associates

CONSULTING GEOTECHNICAL ENGINEERS AND MATERIAL TESTING

GEOTECHNICAL ENGINEERING STUDY RESIDENTIAL TRI-PLEX STRUCTURE LOT 15 PARKSIDE DEVELOPMENT RIDGWAY, COLORADO

Prepared for:

HABITAT FOR HUMANITY OF THE SAN JUANS

PROJECT NUMBER: M17022GE

NOVEMBER 17, 2017

P. O. BOX 3986 GRAND JUNCTION, CO 81502 (970) 245-6506 FAX: (970) 248-9758 P. O. BOX 0045 MONTROSE, CO 81402 (970) 249-2154 FAX: (970) 249-3262

Lambert and Associates

CONSULTING GEOTECHNICAL ENGINEERS AND MATERIAL TESTING

November 17, 2017

Habitat for Humanity of the San Juans PO Box 162 Montrose, Colorado

Attention: Mr. Todd Abramson

PN: M17022GE

Subject: Geotechnical Engineering Study for the Proposed Residential Tri-Plex Structure Lot 15 Parkside Development Ridgway, Colorado

Mr. Abramson:

Lambert and Associates is pleased to present our geotechnical engineering study for the subject project. The field study was completed on October 18, 2017. The laboratory study was completed on November 9, 2017. The analysis was performed and the report prepared from November 9 through 17, 2017. Our geotechnical engineering report is attached.

We are available to provide material testing services for soil and concrete and provide foundation excavation observations during construction. We recommend that Lambert and Associates, the geotechnical engineer, for the project provide material testing services to maintain continuity between design and construction phases.

If you have any questions concerning the geotechnical engineering aspects of your project please contact us. Thank you for the opportunity to perform this study for you.

Respectfully submitted,

LAMBERT AND ASSOCIATES

Daniel R. Lambert, P.E.

P. O. BOX 3986 GRAND JUNCTION, CO 81502 (970) 245-6506 FAX: (970) 248-9758 P. O. BOX 0045 MONTROSE, CO 81402 (970) 249-2154 FAX: (970) 249-3262

TABLE OF CONTENTS

1.0 INTRODUCTION	Page 1
1.1 Proposed Construction	1
1.2 Scope of Services	1
2.0 SITE CHARACTERISTICS	2
2.1 Site Location	2
2.2 Site Conditions	2
2.3 Subsurface Conditions	3
2.4 Site Geology	3
2.5 Seismicity	4
3.0 PLANNING AND DESIGN CONSIDERATIONS	4
4.0 ON-SITE DEVELOPMENT CONSIDERATIONS	5
5.0 FOUNDATION SUPPORT CHARACTERISTIC	7
5.1 Swell Potential	7
5.2 Settlement Potential	8
5.3 Soil Support Characteristics	8
6.0 FOUNDATION RECOMMENDATIONS	8
6.1 Spread Footing Foundation	10
7.0 INTERIOR FLOOR SLAB DISCUSSION	16
8.0 COMPACTED STRUCTURAL FILL	20
9.0 LATERAL EARTH PRESSURES	21
10.0 DRAIN SYSTEM	23
11.0 CRAWL SPACE CONSIDERATIONS	23
12.0 BACKFILL	24
13.0 SURFACE DRAINAGE	24
14.0 LANDSCAPE IRRIGATION	25
15.0 SOIL CORROSIVITY TO CONCRETE	26
16.0 RADON CONSIDERATIONS	27
17.0 POST DESIGN CONSIDERATIONS	27
17.1 Structural Fill Quality	28
17.2 Concrete Quality	29
	29
PROJECT VICINITY MAP TEST BORING LOCATION SKETCH	Figure 1
CONCEPTUAL SKETCH OF FOOTING SUBGRADE TREATM	2 //ENT 3
EMBEDMENT CONCEPT	4 AILINI
ZONE OF INFLUENCE CONCEPT	4 5
CONCEPTUAL SKETCH OF FOUNDATION DRAIN SYSTEM	6
FIELD STUDY	Appendix A
KEY TO LOG OF TEST BORING	Figure A1
	Figures A2 - A4
LABORATORY STUDY	Appendix B
SWELL-CONSOLIDATION TESTS	Figure B1-B2
DIRECT SHEAR STRENGTH TESTS	Figure B2
GEOLOGY DISCUSSION SOUTHWEST	riguic b2
COLORADO GEOLOGY	Appendix C
GENERAL GEOTECHNICAL ENGINEERING	Appondix O
CONSIDERATIONS	Appendix D
RADON FLOW CONCEPT	Figure D1

1.0 INTRODUCTION

This report presents the results of the geotechnical engineering study we conducted for the proposed tri-plex residential structure. The study was conducted at the request of Todd Abramson, Construction Manager, Habitat for Humanity of the San Juans, in general accordance with our proposal for geotechnical engineering services dated June 12, 2017.

The conclusions, suggestions and recommendations presented in this report are based on the data gathered during our site and laboratory study and on our experience with similar soil conditions. Factual data gathered during the field and laboratory work are summarized in Appendices A and B.

1.1 Proposed Construction

It is our understanding the proposed construction is to include a tri-plex residential structure and associated utilities and parking and drive areas.

1.2 Scope of Services

Our services included geotechnical engineering field and laboratory studies, analysis of the acquired data and report preparation for the proposed site. The scope of our services is outlined below.

- The field study consisted of describing and sampling the soil materials encountered in three (3) small diameter continuous flight auger advanced test borings in the general vicinity of the proposed structure.
- The materials encountered in the test borings were described and samples retrieved for the subsequent laboratory study.
- The laboratory study included tests of select soil samples obtained during the field study to help assess:
- . the soil strength potential (internal friction angle and cohesion) of samples tested,

- . the swell and expansion potential of the samples tested,
- . the settlement/consolidation potential of the samples tested, and

- the moisture content and density of samples tested.
- This report presents our geotechnical engineering comments, suggestions and recommendations for planning and design of site development including:
- . viable foundation types for the conditions encountered,
- . allowable bearing pressures for the foundation types,
- . lateral earth pressure recommendations for design of laterally loaded walls,
- . geotechnical engineering considerations and recommendations for concrete slab on grade floors, and
- . geotechnical engineering considerations and recommendations for compacted structural fill.
- Our comments, suggestions and recommendations are based on the subsurface soil and ground water conditions encountered during our site and laboratory studies.
- Our study did not include any environmental or geologic hazard issues.

2.0 SITE CHARACTERISTICS

Site characteristics include observed existing and pre-existing site conditions that may influence the geotechnical engineering aspects of the proposed site development.

2.1 Site Location

The site is located on Lot 15 of the Parkside development in Ridgway, Colorado.

2.2 Site Conditions

The site is currently a vacant, undeveloped lot. The lot is generally devoid of vegetation and exhibits positive surface drainage toward the drainage area to the south. The lot is bordered on the west by North Laura Street and to the south by North Railroad Street. The lot is bordered to the north and east by residential lots similar in terrain to the subject site.

2.3 Subsurface Conditions

The subsurface exploration consisted of observing, describing and sampling the soil materials encountered in three (3) small diameter auger advanced test borings. The approximate locations of the test borings are shown on Figure 2. The logs describing the soil materials encountered in the test borings are presented in Appendix A.

The soil materials encountered within the test borings generally consisted of silty clay to the depths explored, approximately fifteen (15) feet below existing site grades. The soil materials encountered were medium stiff and exhibited low load bearing characteristics.

At the time of our field study the proposed development site was not irrigated. It has been our experience that after the site is developed and once landscape irrigation begins the free subsurface water level may tend to rise. In some cases the free subsurface water level rise, as a result of landscape irrigation and other development influences, can be fairly dramatic and the water level may become very shallow.

It appears that the subdivision development included excavating and fill placement. We anticipate that there exists man placed fill material on the lot site areas. The subdivision has been dormant for several years. During that time the near surface soil materials have been subjected to several freeze-thaw cycles each winter and some drying and wetting cycles during the summer. These cycles loosen the near surface materials and they become poor support materials for structural components. These near surface soil materials will likely need to be addressed during lot development.

It is difficult to predict if unexpected subsurface conditions will be encountered during construction. Since such conditions may be found, we suggest that the owner and the contractor make provisions in their budget and construction schedule to accommodate unexpected subsurface conditions.

2.4 Site Geology

A brief discussion of the general geology of the area near the site is presented in Appendix C. The surface geology of the site was determined by observation of the surface conditions

3

at the site and observing the soils encountered in the test borings on the site.

2.5 Seismicity

According to the International Building Code, 2009 Edition, based on the subsurface conditions encountered and the assumption that the soils described in the test borings are likely representative of the top 100 feet of the soil profile, we recommend that the site soil profile be $S_{\rm D}$.

3.0 PLANNING AND DESIGN CONSIDERATIONS

A geologic hazard study was not requested as part of the scope of this report, however there are some conditions which were observed at the site during the field study which may influence the development.

All of the suggestions and design parameters presented in this report are based on high quality craftsmanship, care during construction and post construction cognizance of the potential for swell or settlement of the site support materials and appropriate post construction maintenance.

All construction excavations should be sloped to prevent excavation wall collapse. We suggest that as a minimum the excavation walls should be sloped at an inclination of one-and-one-half (1-1/2) to one (1) (horizontal to vertical) or flatter. The area above the foundation excavations should be observed at least daily for evidence of slope movement during construction. If evidence of slope movement is observed we should be contacted immediately.

We anticipate that excavation and fill placement operations may be associated with the proposed site development. Excavations in the area which generate vertical or sloped exposures should be kept to a minimum.

Excavations which result in cut slopes with a vertical height greater than about four (4) feet or with a slope or structure above should be analyzed on a site specific basis. Temporary excavation cut slopes in competent material should not exceed a one-and-one-half to one (1)

4

-1/2 to 1) (horizontal to vertical) inclination. All construction excavations should conform to Occupational Safety and Health Administration (OSHA) standards or safer. All permanent slopes should be constructed with inclinations of three to one or flatter.

Slope and excavation surfaces should be protected by vegetation and/or other means to prevent erosion. Surface runoff should not be allowed to cascade over the top of a slope or to pond at the toe of any slope.

We anticipate that some embankment fill slopes will be constructed on the site. Fill slopes greater than about three (3) feet vertical height or fill slopes supporting structures will require additional analysis. We recommend that each proposed fill slope on the site be analyzed on a per site basis when the proposed site configuration and fill material has been determined. If fill slopes will be constructed on site we should be contacted to provide geotechnical engineering review and recommendations for the design and construction of the slopes.

Generally, fill material placed on a site surface which will be used to support structures or additional fill material should be placed so that the contact between the existing site surface and the added fill material will be strong enough to support the added load. This should be addressed on a site and fill area specific basis. The technique recommended will be based on the site configuration, the finished fill configuration the actual material to be used for the fill material and the size of the area thus constructed. Frequently the preparation of the site area to receive fill material will include removing organic and loose near surface native material in the area to receive fill material, placing the material in thin horizontal lifts which are compacted at the appropriate moisture content. Some fill areas could benefit from the installation of a subsurface drain system at the fill material/natural material contact. We are available to, and recommend that, we discuss this with you and provide site and fill specific recommendations when this portion of your development plan merits the additional study.

4.0 ON-SITE DEVELOPMENT CONSIDERATIONS

We anticipate that the subsurface water elevation may fluctuate with seasonal and other varying conditions. Excavations may encounter subsurface water and soils that tend to cave or yield. If water is encountered it may be necessary to dewater construction excavations to provide more suitable working conditions. Excavations should be well braced or sloped to

5

prevent wall collapse. Federal, state and local safety codes should be observed. All construction excavations should conform to Occupational Safety and Health Administration (OSHA) standards or safer.

The site construction surface should be graded to drain surface water away from the site excavations. Surface water should not be allowed to accumulate in excavations during construction. Accumulated water could negatively influence the site soil conditions. Construction surface drainage should include swales, if necessary to divert surface water away from the construction excavations.

Organic soil materials in areas to receive fill material or structure components should be removed. The organic soil materials are not suitable for support of the structure or structural components.

Man placed fill material exists on site. The quality of the man placed fill is not known and may not be suitable for support of the structure or structural components. The quality of the existing man placed fill should be verified or the fill removed and replaced with compacted structural fill prior to supporting building or building components on the fill.

It has been our experience that sites in developed areas may contain existing subterranean structures or poor quality man placed fill. If subterranean structures or poor quality man placed fill are suspected or encountered, they should be removed and replaced with compacted structural fill as discussed under COMPACTED STRUCTURAL FILL below.

The soil materials exposed in the bottom of the excavation may be very moist and may become yielding under construction traffic during construction. It may be necessary to use techniques for placement of fill material or foundation concrete which limits construction traffic in the vicinity of the very moist soil material. If yielding should occur during construction it may be necessary to construct a subgrade stabilization fill blanket or similar to provide construction traffic access. The subgrade stabilization blanket may include over excavating the subgrade soils one (1) to several feet and replacing with aggregate subbase course type material. The stabilization blanket may also include geotextile stabilization fabric at the bottom of the excavation prior to placement of aggregate subbase course stabilization fill. Other subgrade stabilization techniques may be available. We are available to discuss this with you.

Free subsurface water was not encountered in our test borings during the drilling activities. We anticipate that the free subsurface water may be much shallower during wetter seasons. We do not recommend construction of basements below the highest anticipated free subsurface water elevation. It may be necessary to install standpipe piezometers in areas where basements will be planned and the free subsurface water elevation monitored for a significant period of time to help identify the anticipated highest elevation of the free subsurface water.

5.0 FOUNDATION SUPPORT CHARACTERISTIC

Two criteria for foundation design which must be satisfied for satisfactory performance are:

- contact stresses must be low enough to preclude shear failure of the foundation soils which would result in lateral movement of the soils from beneath the foundation, and
- 2) settlement or heave of the foundation must be within amounts tolerable to the superstructure.

The soil materials encountered in the test borings have varying engineering characteristics that may influence the design and construction considerations of foundations. The characteristics include swell potential, settlement potential, bearing capacity and the bearing conditions of the soils supporting the foundations. These are discussed below.

5.1 Swell Potential

Some of the materials encountered in the test borings at the anticipated foundation depths may have swell potential. Swell potential is the tendency of the soil to increase in volume when it becomes wetted. The volume change occurs as moisture is absorbed into the soil and water molecules become attached to or adsorbed by the individual clay platlets. Associated with the process of volume change is swell pressure. The swell pressure is the force the soils applies on its surroundings when moisture is absorbed into the soil. Foundation design considerations concerning swelling soils include structure tolerance to movement and dead load pressures to help restrict uplift. The structure's tolerance to movement should be

7

addressed by the structural engineer and is dependent upon many facets of the design including the overall structural concept and the building material. The uplift forces or pressure due to wetted clay soils can be addressed by designing the foundations to account for swelling soils.

5.2 Settlement Potential

Settlement potential of a soil is the tendency for a soil to experience volume change when subjected to a load. Settlement is characterized by downward movement of all or a portion of the supported structure as the soil particles move closer together resulting in decreased soil volume. Settlement potential is a function of foundation loads, depth of footing embedment, the width of the footing and the settlement potential or compressibility of the influenced soil. Foundation design considerations concerning settlement potential include the amount of movement tolerable to the structure and the design and construction concepts to help reduce the potential movement.

5.3 Soil Support Characteristics

The soil bearing capacity is a function of the engineering properties of the soils supporting the foundations, the foundation width, the depth of embedment of the bottom of the foundation below the lowest adjacent grade, the influence of the ground water and the amount of settlement tolerable to the structure.

Foundations for the structures should be placed on relatively uniform bearing conditions. Varying support characteristics of the soils supporting the foundation may result in nonuniform or differential performance of the foundation. The influence of nonuniform bearing conditions may be reduced by recognizing and accommodating during the site specific design.

6.0 FOUNDATION RECOMMENDATIONS

Geotechnical engineering considerations which influence the foundation design and construction recommendations presented below are discussed in Appendix C.

We have analyzed spread footing foundations as a potential foundation system for the



proposed structure. These are discussed below. Due to the number of possible foundation types available and design and construction techniques there may be design alternatives which we have not presented in this report. We are available to discuss other foundation types.

We recommend that the entire structure be supported on only one foundation type. Combining foundation types will result in differential and unpredictable foundation performance between the varying foundation types. We recommend that the structure footprint not be traversed by the cut/fill contact which would result in a portion of the structure underlain by fill material and part of the structure underlain by materials exposed by excavated cut. If this condition will exist please contact us so that we can revise our recommendations to accommodate the cut/fill contact scenario.

All of the design parameters presented below are based on techniques performed by an experienced competent contractor and high quality craftsmanship and care during construction. We recommend post construction cognizance of the volume change potential of the near surface soil materials and the need for appropriate post construction maintenance.

The spread footing recommendations include recommended design and construction techniques to reduce the influence of movement of the soil materials supporting the foundation but should not be interpreted as solutions for completely mitigating the potential for movement from the support soil material volume change.

Because of site configuration and planned construction you may decide that it is not practical to support the structure on drilled piers. For this reason we have provided spread footing recommendations as an alternative foundation to drilled piers. The spread footing recommendations include recommended design and construction techniques to reduce the influence of swelling soils supporting the foundation but should not be interpreted as solutions for completely mitigating the potential for movement from swelling soil supporting footings.

Exterior column supports should be supported by foundations incorporated into the foundation system of the structure not supported on flatwork. Column supports placed on exterior concrete flatwork may move if the support soils below the concrete slab on grade become wetted and swell or freeze and raise or settle. Differential movement of the exterior columns may

9

cause stress to accumulate in the supported structure and translate into other portions of the structure.

6.1 Spread Footing Foundations

In our analysis it was necessary to assume that the material encountered in the test borings extended throughout the building site and to a depth below the maximum depth of the influence of the foundations. We should be contacted to observe the soil materials exposed in the foundation excavations prior to placement of foundations to verify the assumptions made during our analysis.

The bottom of the foundation excavations should be thoroughly cleaned and observed when excavated. Any loose or disturbed material exposed in the foundation excavation should be removed or compacted prior to placing foundation concrete.

The bottom of the foundation excavations should be compacted prior to placing compacted structural fill or foundation concrete. We suggest the materials exposed be compacted to at least ninety (90) percent of the materials moisture content-dry density relationship (Proctor) test, ASTM D1557. Excavation compaction is to help reduce the influence of any disturbance that may occur during the excavation operations. Any areas of loose, low density or yielding soils evidenced during the excavation compaction operation should be removed and replaced with compacted structural fill. Caution should be exercised during the excavation compacting may increase pore pressure of the subgrade soil material and degrade the integrity of the support soils. Loose or disturbed material in the bottom of the foundation excavations which are intended to support structural members will likely result in large and unpredictable amounts of settlement, if the loose or disturbed material is not removed or compacted.

The bottom of any footings exposed to freezing temperatures should be placed below the maximum depth of frost penetration for the area. Refer to the local building code for details.

All footings should be appropriately proportioned to reduce the post construction differential settlement. Footings for large localized loads should be designed for bearing pressures and footing dimensions in the range of adjacent footings to reduce the potential for differential

10

settlement. We are available to discuss this with you.

Foundation walls should be reinforced for geotechnical engineering purposes. The structural engineer should be consulted for foundation design. The structural engineering reinforcing design tailored for this project will be more appropriate than the suggestions presented above.

The structure may be founded on spread footings. We recommend the use of a blanket of structure fill material beneath the spread footing foundation members. Spread footings may be placed either on the natural undisturbed soils or on a blanket of compacted structural fill. The blanket of compacted structural fill is to help provide uniform support for the footings and to help reduce the theoretical calculated post construction settlement. The theoretical calculated post construction settlement. The footings are presented below.

We suggest that you consider the foundation be supported on a blanket of compacted structural fill at least one (1) foot thick to help mask the influence of volume change soil materials supporting the footings. The blanket of compacted structural fill will not prevent movement of the footings from volume change in the support soil materials but will mask the influence of volume changes of the soils supporting the footings. If the footings are supported on a blanket of compacted structural fill should extend beyond each edge of each footing a distance at least equal to the fill thickness. This concept is shown on Figure _. Geotechnical engineering recommendations for constructing compacted structural fill are presented below.

All footings should have a minimum depth of embedment of at least one (1) foot below the lowest adjacent grade when placed either on the natural undisturbed soils or a blanket of compacted structural fill. Deeper embedment will be needed for footings exposed to exterior climate.

The bearing capacity will depend on the minimum depth of embedment of the bottom of the footings below the lowest adjacent grade and the support characteristics of the soils supporting the foundation. Other characteristics may influence embedment. The embedment concept is shown on Figure 4.

11

Bearing capacity and associated minimum depth of embedment of the bottom of the footing below the lowest adjacent grade are presented below.

SPREAD FO	OTING	
SOIL BEARING	CAPACITY	
CONTINUOUS	ISOLATED	D*
(POUNDS PER SQ	UARE FOOT)	(feet)
1,025	1,300	0
1,125	1,400	1
1,225	1,500	2

D* Minimum depth of embedment for footings adjacent to level areas.

If deeper embedment is considered for increased bearing capacity greater than presented above, we should be contacted to provide additional analysis and recommendations as needed. The bearing capacity design value is based on several considerations and these may change with depth.

The bearing capacity may be increased by about twenty (20) percent for transient loads such as wind and seismic loads.

It is our opinion that footings exposed to frost or freezing ground influences and all exterior footings should be embedded to frost depth or deeper. Interior footings should have a minimum depth of embedment of at least one (1) foot on all sides to provide a more predictable long term performance of the footing. We understand that construction techniques typically used in the area may result in some of the footing below the lowest adjacent grade. For this reason we have provided design values for footings constructed without embedment may be influenced by erosion, temperature changes, moisture content changes, swell potential of the soil supporting the footings and weathering of the soils supporting the footings and will have a less predictable settlement response than footings with embedment.

Exterior footings and footings with uneven backfill may result in movement of the footings.

Embedment of the footings on all sides will help reduce the potential for movement of footings with uneven backfill. We do not recommend exterior footings or footings with uneven backfill be constructed without a minimum depth of embedment of the bottom of the footing below the lowest adjacent grade of at least one (1) foot on all sides of the interior footings and frost depth for exterior footings.

The minimum depth of embedment is sufficient only to develop the bearing capacity for design purposes and does not account for frost influences. Actual design and construction should result in interior footings with one (1) foot or more embedment and exterior footings with frost depth or more embedment. Typically deeper embedment will increase bearing capacity and decrease post construction settlement and decrease the influence of expansive soils.

The soil sample tested had a measured swell pressure of approximately 500 to 2,100 pounds per square foot, however, the actual swell pressure of the support materials could be greater. When wetted the site soil materials may have the ability to raise supported foundation members with loads less than the swell pressure. The foundation design should be as rigid as possible with as high of a dead load as can be available. The greater the dead load on the footings the less the potential for movement from the foundation soils should they become wetted. If the soils become wetted they will swell and will raise the foundation portions supported on the wetted soils. If the structure is supported on spread footings the owner must realize that post construction movement of the footings is likely. We are available to discuss the implications of supporting foundations on swelling soils.

Interior column loads supported on spread footings which are structurally connected to the other foundation members will provide more uniform performance of the interior footings with respect to the other foundation members and will help reduce the potential differential settlement between interior and exterior foundation members. The foundation walls should be designed to act as beams to distribute stresses associated with the swelling volume changes of soils. The beam design should be addressed by the project structural engineer.

Exterior column supports should be supported by foundations incorporated into the foundation system of the structure not supported on flatwork. Column supports placed on exterior concrete flatwork may move if the support soils below the concrete slab on grade become wetted and swell or freeze and raise or settle. Differential movement of the exterior columns may

13

cause stress to accumulate in the supported structure and translate into other portions of the structure.

The calculated theoretical estimated post construction settlement and swell potential may be reduced by placing the footings on a blanket of compacted structural fill. The calculated theoretical estimated post construction settlement and associated thickness of compacted structural fill are presented below.

THICKNESS OF	CALCULATED THEORETICAL ESTIMATED POST
COMPACTED STRUCTURAL FILL	CONSTRUCTION SETTLEMENT FOR
SUPPORTING FOOTINGS	CONTINUOUS SPREAD FOOTINGS (INCHES)

0 1 foot 2 feet

0

1 foot

2 feet

1 to 1-3/8 3/4 to 1 1/2 to 3/4

Lambert and Associates

THICKNESS OFCALCULATED THEORETICAL ESTIMATED POSTCOMPACTED STRUCTURAL FILLCONSTRUCTION SETTLEMENT FORSUPPORTING FOOTINGSISOLATED SPREAD FOOTINGS (INCHES)

1 to 1-5/8 3/4 to 1 1/2 to 3/4

The calculated theoretical settlement estimated values above are appropriate for continuous spread footings with a width of about two (2) feet or less and isolated spread footings with a width of about three (3) feet or less. Larger footings should be analyzed on a footing, load and width specific basis.

Footings should be sized so that each footing is in a similar size and load range as nearby footings to encourage similar performance. Very large footings or heavily loaded footings will influence the support soil materials to a deeper depth than small or lightly loaded footings and therefore will have different post construction performance characteristics.

The calculated settlement estimates are theoretical only. Actual settlement could vary throughout the site and with time.

If the footings are supported on a blanket of compacted structural fill, the blanket of compacted structural fill should extend beyond each edge of each footing a distance at least equal to the fill thickness. This concept is shown on Figure 3. Compacted Structural Fill is discussed in Section 8.0 below.

The site soil samples tested have measured swell pressures of approximately 500 to 2,100 pounds per square foot, however, the actual swell pressure of the support material could be greater. This swell pressure was measured for soils at the initial moisture content of the soil sample tested. The swell potential of the site soil materials could vary significantly and could be greater than that measured. The measured swell pressure may be influenced by disturbance of the sample during the sampling operation and the soil suction potential and initial moisture content.

Changes in the initial moisture content will significantly influence the swell pressure of the site soils. If the initial moisture content of the foundation soils is less than that of the test sample the actual swell pressures will likely be significantly higher than measured. If the initial moisture content of the foundation soils is greater than that of the test sample the actual swell pressures may be less than measured.

The bottom of the foundation excavations should be thoroughly cleaned and observed by the project Geotechnical Engineer or his representative when excavated. Any loose or disturbed material exposed in the foundation excavation should be removed or remedied prior to additional construction.

We recommend that we be contacted to observe the foundation excavations and backfill operations during construction to verify the soil support conditions and our assumptions upon which our recommendations are based. If necessary we may revise our recommendations based on our observations. We are available to provide material testing services during the construction phase of the project.

If lightly loaded structure members are supported on spread footings on expansive soil

15

material then the owner must realize that post construction movement of the footings is likely. These lightly loaded areas of the footing should be designed with sufficient structural integrity to resist the forces from swelling soils.

Foundation members that will have significantly small or low dead loads, such as foundations beneath wall openings such as doorways, may be provided with a strengthened grade beam and/or positive separation between the foundation concrete and the underlying soil materials. That separation may be provided by using commercial void form material. We recommend that the structural engineer be consulted concerning the void form design concept.

If the void form design concept is part of the foundation design we suggest that the foundation design may consider including a four (4) to six (6) inch corrugated paper void form material beneath the footings in the lightly loaded portions of the foundation. The corrugated paper void forms provide temporary support for foundation concrete during construction. The low strength of the void form material is intended to allow the underlying soil materials to expand into the void form thereby exerting less or no uplift pressure on the foundation in the areas it is used. We are available to discuss the implications of supporting foundations on swelling soils.

7.0 INTERIOR FLOOR SLAB DISCUSSION

It is our understanding that, as currently planned, the floor may be either a concrete slab on grade or a supported structural floor. The natural soils that will support interior floor slabs are stable at their natural moisture content. However, the owner should realize that when wetted, the site soils may experience volume changes. The site soil samples tested had measured swell pressures of approximately 500 to 2,100 pounds per square foot and associated magnitudes of 2.0 to 6.5 percent of the wetted soil volume at a surcharge load of 100 pounds per square foot and the actual swell pressure could be greater.

The recommendations in this report do not address a monolithic floor slab/footing combination. The design and construction characteristics of the monolithic floor slab need geotechnical engineering design parameters tailored specifically for a monolithic slab and integral footing. Generally this type foundation/floor combination in this area with these site conditions does not perform as well as other choices.

Conditions which vary from those encountered during our field study may become apparent during excavation. We should be contacted to observe the conditions exposed at concrete slab on grade subgrade elevation to verify the assumptions made during the preparation of this report and to provide additional geotechnical engineering suggestions and recommendations as needed.

Engineering design dealing with swelling soils is an art which is still developing. The owner is cautioned that the soils on this site may have swelling potential and concrete slab on grade floors and other lightly loaded members may experience movement when the supporting soils become wetted. We suggest you consider floors suspended from the foundation systems as structural floors or a similar design that will not be influenced by subgrade volume changes. If the owner is willing to accept the risk of possible damage from swelling soils supporting concrete slab on grade floors, the following recommendations to help reduce the damage from swelling soils should be followed. These recommendations are based on generally accepted design and construction procedures for construction on soils that tend to experience volume changes when wetted and are intended to help reduce the damage caused by swelling soil materials. Lambert and Associates does not intend that the owner, or the owner's consultants should interpret these recommendations as a solution to the problems of swelling soils, but as measures to reduce the influence of swelling soils.

The shallow soil materials tested have a low volume change potential under light loading conditions. Concrete slab on grade floors may experience movement when supported by the natural onsite soils. Concrete slab on grade floors will perform best if designed to tolerate movement introduced by the subgrade soil materials.

Concrete flatwork, such as concrete slab on grade floors, should be underlain by compacted structural fill. The layer of compacted fill should be at least one (1) foot thick or thicker and constructed as discussed under COMPACTED STRUCTURAL FILL below. A one (1) foot thick or thicker blanket of structural fill material beneath the concrete flatwork is not sufficient to entirely mask the settlement or swell potential of the subgrade soil material but will only provide better subgrade conditions for construction. The concrete slab on grade should be designed by a structural engineer to be compatible with the site soil conditions.

The calculated theoretical estimated post construction heave potential of the slab may be

reduced by placing the slab on a blanket of compacted structural fill. The calculated theoretical estimated post construction heave and associated thickness of compacted structural fill are presented below.

THICKNESS OF COMPACTED STRUCTURAL FILL <u>SUPPORTING SLABS</u> 0 1 foot 2 feet

3 feet

CALCULATED THEORETICAL ESTIMATED POST CONSTRUCTION HEAVE (INCHES)

2-1/4 to 3 1-7/8 to 2-1/2 1-3/8 to 1-7/8 1 to 1-3/8

Lambert and Associates CONSULTING GEOTECHNICAL ENGINEERS AND MATERIAL TESTING

The calculated post construction heave estimates are theoretical only. Actual heave could vary throughout the site and with time.

The natural soil materials exposed in the areas supporting concrete slab on grade floors should be kept very moist during construction prior to placement of concrete slab on grade floors. This is to help increase the moisture regime of the potentially expansive soils supporting floor slabs and help reduce the expansion potential of the soils. We are available to discuss this concept with you.

Concrete slab on grade floors should be provided with a positive separation, such as a slip joint, from all bearing members and utility lines to allow their independent movements and to help reduce possible damage that could be caused by movement of soils supporting interior slabs. The floor slab should be constructed as a floating slab. All water and sewer pipe lines should be isolated from the slab. Any equipment placed on the floating floor slab should be constructed with flexible joints to accommodate future movement of the floor slab with respect to the structure. We suggest partitions constructed on the concrete slab on grade floors be provided with a void space above or below the partitions to relieve stresses induced by elevation changes in the floor slab.

Floor slabs should not extend over foundations or foundation members. Floor slabs which extend over foundations or foundation members will likely experience post construction movement as a result of foundation movements. We are available to discuss this with you.

18

The concrete slabs should be scored or jointed to help define the locations of any cracking. We recommend that joint spacing be designed as outlined in ACI 224R. In addition joints should be scored in the floors a distance of about three (3) feet from, and parallel to, the walls.

It should be noted that when curing fresh concrete experiences shrinkage. This shrinkage almost always results in some cracks in the finished concrete. The actual shrinkage depends on the configuration and strength of the concrete and placing and finishing techniques. The recommended joints discussed above are intended to help define the location of the cracks but should not be interpreted as a solution to shrinkage cracks. The owner must understand that concrete flatwork will contain shrinkage cracks after curing and that all of the shrinkage cracks may not be located in control joints. Some cracking at random locations may occur.

If moisture migration through the concrete slab on grade floors will adversely influence the performance of the floor or floor coverings we suggest that a moisture barrier may be installed beneath the floor slab to help discourage capillary and vapor moisture rise through the floor slab. The moisture barrier may consist of a heavy plastic membrane, six (6) mil or greater, protected on the top and bottom by clean sand. The clean sand will help to protect the plastic from puncture. The layer of clean sand on the top of the plastic membrane will help the overlying concrete slab cure properly. According to the American Concrete Institute, proper curing requires at least three (3) to six (6) inches of clean sand between the plastic membrane and the bottom of the concrete. The plastic membrane should be lapped and taped or glued and protected from punctures during construction.

If the moisture content of the slab on grade floor will be influencial to the performance of the future floor coverings then the moisture content of the slab can be measured. We are available to monitor the floor slab moisture content prior to the installation of the floor covering. If this service is needed please contact us during the construction phase of the project.

The Portland Cement Association suggests that welded wire reinforcing mesh is not necessary in concrete slab on grade floors when properly jointed. It is our opinion that welded wire mesh may help improve the integrity of the slab on grade floors. We suggest that concrete slab on grade floors should be reinforced, for geotechnical purposes, with at least $6 \times 6 - W2.9 \times W2.9$ ($6 \times 6 - 6 \times 6$) welded wire mesh positioned midway in the slab. The structural engineer should be contacted for structural design of floor slabs.

8.0 COMPACTED STRUCTURAL FILL

Material characteristics desirable for compacted structural fill are discussed in Appendix C. Areas that are over excavated or slightly below grade should be backfilled to grade with properly compacted structural fill or concrete, not loose fill material. If backfilled with other than compacted structural fill material or concrete there will be significant post construction settlement proportional to the amount of loose material.

The natural on site soils are not suitable for use as compacted structural fill material supporting building or structure members because of their clay content and swell potential. The natural on-site soils may be used as compacted fill in areas that will not influence the structure such as to establish general site grade. We are available to discuss this with you.

All areas to receive compacted structural fill should be properly prepared prior to fill placement. The preparation should include removal of all organic or deleterious material. The areas to receive fill material should be compacted after the organic deleterious material has been removed prior to placing the fill material. The area may need to be moisture conditioned for compaction. Any areas of soft, yielding, or low density soil, evidenced during the excavation compaction operation should be removed. The area excavated to receive fill should be moisture conditioned to wet of optimum moisture content as part of the preparation to receive fill. Fill should be moisture conditioned, placed in thin lifts not exceeding six (6) inches in compacted thickness and compacted to at least ninety (90) percent of maximum dry density as defined by ASTM D1557, modified moisture content-dry density (Proctor) test.

After placement of the structural fill the surface should not be allowed to dry prior to placing concrete or additional fill material. This may be achieved by periodically moistening the surface of the compacted structural fill as needed to prevent drying of the structural fill. We are available to discuss this with you.

The soil materials exposed in the bottom of the excavation may be very moist and may become yielding under construction traffic during construction. It may be necessary to use techniques for placement of fill materials or foundation concrete which limit construction traffic in the very moist soil materials. If yielding should occur during construction it may be necessary to construct a subgrade stabilization fill blanket or similar to provide construction

20

traffic access. We are available to discuss this with you.

We recommend that the geotechnical engineer or his representative be present during the excavation compaction and fill placement operations to observe and test the material.

9.0 LATERAL EARTH PRESSURES

Laterally loaded walls supporting soil, such as basement walls, will act as retaining walls and should be designed as such. Walls that are designed to deflect and mobilize the internal soil strength should be designed for active earth pressures. Walls that are restrained so that they are not able to deflect to mobilize internal soil strength should be designed for at-rest earth pressures. The values for the lateral earth pressures will depend on the type of soil retained by the wall, backfill configuration and construction technique. If the backfill is not compacted the lateral earth pressures will be very different from those noted below.

Lateral earth pressure (L.E.P.) values are presented below:

	Level Backfill	
	with on-site soils	
	(pounds per cubic foot per foot of depth)	
Active L.E.P.	75	
At-rest L.E.P.	89	
Passive L.E.P.	162	

The soil samples tested have measured swell pressures of approximately 500 to 2,100 pounds per square foot and the actual swell pressure of the backfill material could be greater. Our experience has shown that the actual swell pressure may be much higher. If the retained soils should become moistened after construction the soil may swell against retaining walls. The walls should be designed to resist the swell pressure of the soil materials if these are used as part of the backfill within the zone of influence. The zone of influence concept is presented on Figure 5.

The above lateral earth pressures may be reduced by overexcavating the wall backfill area beyond the zone of influence and backfilling with crushed rock type material. The zone of

21

influence concept is presented on Figure 5.

The lateral earth pressure design parameters may change significantly if the area near the wall is loaded or surcharged or is sloped. If any of these conditions occur we should be contacted for additional design parameters tailored to the specific site and structure conditions.

Suggested lateral earth pressure (L.E.P.) values if the backfill is overexcavated beyond the zone of influence and backfilled with crushed rock are presented below.

	Level Backfill
	with crushed rock material
	(pounds per cubic foot per foot of depth)
Active L.E.P.	30
At-rest L.E.P.	50

If the area behind a wall retaining soil material is sloped we should be contacted to provide lateral earth pressure design values tailored for the site specific sloped conditions.

Resistant forces used in the design of the walls will depend on the type of soil that tends to resist movement. We suggest that you consider a coefficient of friction of 0.13 for the on site soil.

The lateral earth pressure values provided above, for design purposes, should be treated as equivalent fluid pressures. The lateral earth pressures provided above are for level well drained backfill and do not include surcharge loads or additional loading as a result of compaction of the backfill. Unlevel or non-horizontal backfill either in front of or behind walls retaining soils will significantly influence the lateral earth pressure values. Care should be taken during construction to prevent construction and backfill techniques from overstressing the walls retaining soils. Backfill should be placed in thin lifts and compacted, as discussed in this report to realize the lateral earth pressure values.

Walls retaining soil should be designed and constructed so that hydrostatic pressure will not accumulate or will not affect the integrity of the walls. Drainage plans should include a subdrain behind the wall at the bottom of the backfill to provide positive drainage. Exterior

22



retaining walls should be provided with perimeter drain or weep holes to help provide an outlet for collected water behind the wall. The ground surface adjacent to the wall should be sloped to permit rapid drainage of rain, snow melt and irrigation water away from the wall backfill. Sprinkler systems should not be installed directly adjacent to retaining or basement walls.

10.0 DRAIN SYSTEM

A drain system should be provided around building spaces below the finished grade and behind any walls retaining soil. The drain systems are to help reduce the potential for hydrostatic pressure to develop behind retaining walls. A sketch of the drain system is shown on Figure 6.

Subdrains should consist of a three (3) or four (4) inch diameter perforated rigid pipe surrounded by a filter. The filter should consist of a filter fabric or a graded material such as washed concrete sand or pea gravel. If sand or gravel is chosen the pipe should be placed in the middle of about four (4) cubic feet of aggregate per linear foot of pipe. The drain system should be sloped to positive gravity outlets. If the drains are daylighted the drains should be provided with all weather outlets and the outlets should be maintained to prevent them from being plugged or frozen. We do not recommend that the drains be discharged to dry well type structures. Dry well structures may tend to fail if the surrounding soil material becomes wetted and swells or if the ground water rises to a elevation of or above the discharge elevation in the dry well. We should be called to observe the soil exposed in the excavations and to verify the details of the drain system.

11.0 CRAWL SPACE CONSIDERATIONS

We anticipate that free subsurface water may be shallow enough during wetter seasons to exist in crawl space areas or create very moist conditions in crawl space areas. We suggest that if it is desired to reduce the influence of water in the crawl space area a foundation drain should be installed as discussed above.

The surface of the crawl space may be provided with a layer of about six (6) inches of clean washed gravel or an impervious geotextile fabric to reduce the inconvenience of very moist or muddy crawl space conditions if these should occur. The crawl space should be adequately

vented to reduce the potential for humidity to accumulate in the crawl space area.

12.0 BACKFILL

Backfill areas and utility trench backfill should be constructed such that the backfill will not settle after completion of construction, and that the backfill is relatively impervious for the upper few feet. The backfill material should be free of trash and other deleterious material. It should be moisture conditioned and compacted to at least ninety (90) percent relative compaction using a modified moisture content-dry density (Proctor) relationship test (ASTM D1557). Only enough water should be added to the backfill material to allow proper compaction. Do not pond, puddle, float or jet backfill soil materials.

Improperly placed backfill material will allow water migration more easily than properly recompacted fill. Improperly compacted fill is likely to settle, creating a low surface area which further enhances water accumulation and subsequent migration to the foundation soils.

Improperly placed backfill will allow water to migrate along the utility trench or backfill areas to gain access to the subgrade support soils with subsequent mobilization of the swell or settlement mechanism resulting in movement of the supported structure. Moisture migration could also result in the inconvenience of free water in the crawl space.

Backfill placement techniques should not jeopardize the integrity of existing structural members. We recommend recently constructed concrete structural members be appropriately cured prior to adjacent backfilling.

13.0 SURFACE DRAINAGE

The foundation soil materials should be prevented from becoming wetted after construction. Post construction wetting of the soil support soil materials can initiate swell potential or settlement potential as well as decrease the bearing capacity of the support soil materials. Protecting the foundation from wetting can be aided by providing positive and rapid drainage of surface water away from the structure.

The final grade of the ground surface adjacent to the structure should have a well defined

slope away from the foundation walls on all sides. The ability to establish proper site surface drainage away from the structure foundation system may be influenced by the existing topography, existing structure elevations and the grades and elevations of the ground surface adjacent to the proposed structure. We suggest where possible a minimum fall of the surface grade away from the structure be that which will accommodate other project grading constraints and provide rapid drainage of surface water away from the structure. If there are no other project constraints we suggest a fall of about one (1) foot in the first ten (10) feet away from the structure foundation. Appropriate surface drainage should be maintained for the life of the project. Future landscaping plans should include care and attention to the potential influence on the long term performance of the foundation and/or crawl space if improper surface drainage is not maintained.

Roof runoff should be collected in appropriate roof drainage collection devices, such as eve gutters or similar, and directed to discharge in appropriate roof drainage systems. Roof runoff should not be allowed to fall on or near foundations, backfill areas, flatwork, paved areas or other structural members. Downspouts and faucets should discharge onto splash blocks that extend beyond the limits of the backfill areas. Splash blocks should be sloped away from the foundation walls. Snow storage areas should not be located next to the structure. Proper surface drainage should be maintained from the onset of construction through the proposed project life.

If significant water concentration and velocity occurs erosion may occur. Erosion protection may be considered to reduce soil erosion potential. A landscape specialist or civil engineer should be consulted for surface drainage design, erosion protection and landscaping considerations.

14.0 LANDSCAPE IRRIGATION

An irrigation system should not be installed next to foundations, concrete flatwork or paved areas. If an irrigation system is installed, the system should be placed so that the irrigation water does not fall or flow near foundations, flatwork or pavements. The amount of irrigation water should be controlled.

We recommend that wherever possible xeriscaping concepts be used. Generally, the

xeriscape includes planning and design concepts which will reduce irrigation water. The reason we suggest xeriscape concepts for landscaping is because the reduced landscape water will decrease the potential for water to influence the long term performance of the structure foundations and flatwork. Many publications are available which discuss xeriscape. Colorado State University Cooperative Extension has several useful publications and most landscape architects are familiar with the subject. Montrose Botanical Society has a Botanical Garden, 1800 Pavilion Drive, south of Niagara Drive, Montrose, Colorado, that has a very good exhibit with examples and information regarding successful xeriscape concepts.

Due to the expansive nature of the soils tested we suggest that the owner consider landscaping with only native vegetation which requires only natural precipitation to survive. Additional irrigation water will greatly increase the likelihood of damage to the structure as a result of volume changes of the material supporting the structure.

Impervious geotextile material may be incorporated into the project landscape design to reduce the potential for irrigation water to influence the foundation soils.

15.0 SOIL CORROSIVITY TO CONCRETE

Our scope of services did not include performing chemical tests to help identify the potential for soil corrosivity to concrete.

It has been our experience that much of the soils in the area contain sufficient water soluble sulfate content to be corrosive to concrete. We suggest sulfate resistant cement be used in concrete which will be in contact with the on-site soils. American Concrete Institute recommendations for sulfate resistant cement based on the water soluble sulfate content should be used.

If it is desirable by you or your design team to help identify the potential for corrosivity to concrete at the proposed development site we suggest that site specific chemical tests be performed.





16.0 RADON CONSIDERATIONS

Our experience indicates that many of the soils in western Colorado produce small quantities of radon gas. Radon gas may tend to collect in closed poorly ventilated structures. Radon considerations are presented in Appendix D.

17.0 POST DESIGN CONSIDERATIONS

The project geotechnical engineer should be consulted during construction of the project to observe site conditions and open excavations during construction and to provide materials testing of soil and concrete.

This subsurface soil and foundation condition study is based on limited sampling; therefore, it is necessary to assume that the subsurface conditions do not vary greatly from those encountered in the field study. Our experience has shown that significant variations are likely to exist and can become apparent only during additional on site excavation. For this reason, and because of our familiarity with the project, Lambert and Associates should be retained to observe foundation excavations prior to foundation construction, to observe the geotechnical engineering aspects of the construction and to be available in the event any unusual or unexpected conditions are encountered. The cost of the geotechnical engineering observations and material testing during construction or additional engineering consultation is not included in the fee for this report. We recommend that your construction budget include site visits early during construction schedule for the project geotechnical engineer to observe foundation excavations and for additional site visits to test compacted soil.

We recommend that the observation and material testing services during construction be retained by the owner or the owner's engineer or architect, not the contractor, to maintain third party credibility. We are experienced and available to provide material testing services. We have included a copy of a report prepared by Van Gilder Insurance which discusses testing services during construction. It is our opinion that the owner, architect and engineer be familiar with the information. If you have any questions regarding this concept please contact us.

We suggest that your construction plans and schedule include provisions for geotechnical

27



engineering observations and material testing during construction and your budget reflect these provisions.

It is difficult to predict if unexpected subsurface conditions will be encountered during construction. Since such conditions may be found, we suggest that the owner and the contractor make provisions in their budget and construction schedule to accommodate unexpected subsurface conditions.

17.1 Structural Fill Quality

It is our understanding that the proposed development may include compacted structural fill. The quality of compacted structural fill will depend on the type of material used as structural fill, fill lift thickness, fill moisture condition and compactive effort used during construction of the structural fill. Engineering observation and testing of structural fill is essential as an aid to safeguard the quality and performance of the structural fill.

Fill materials placed on sloped areas require special placement techniques that key the fill materials unto the underlying support materials. These techniques include a toe key at the toe contact of the slope fill and benching the fill/natural contact up the slope into the competent natural material. The placing technique will also include subdrains at several locations to intercept subsurface water and route it away from the fill materials. We are available to discuss these techniques with you and your earthwork contractor.

Testing of the structural fill normally includes tests to determine the grain size distribution, swell potential and moisture-density relationship of the fill material to verify the material suitability for use as structural fill. As the material is placed the in-place moisture content and dry density are tested to indicate the relative compaction of the placed structural fill. We recommend that your budget include provisions for observation and testing of structural fill during construction.

Testing of the compacted fill material should include tests of the moisture content and density of the fill material placed and compacted prior to placement of additional fill material. We suggest that a reasonable number of density tests of the fill material can best be determined on a site, material and construction basis although as a guideline we suggest one test per

28

about each 300 to 500 square feet of each lift of fill material. Utility trench backfill may need to be tested about every 100 linear feet of lift of backfill.

17.2 Concrete Quality

It is our understanding current plans include reinforced structural concrete for foundations and walls and may include concrete slabs on grade and pavement. To insure concrete members perform as intended, the structural engineer should be consulted and should address factors such as design loadings, anticipated movement and deformations.

The quality of concrete is influenced by proportioning of the concrete mix, placement, consolidation and curing. Desirable qualities of concrete include compressive strength, water tightness and resistance to weathering. Engineering observations and testing of concrete during construction is essential as an aid to safeguard the quality of the completed concrete.

Testing of the concrete is normally performed to determine compressive strength, entrained air content, slump and temperature. We recommend that your budget include provisions for testing of concrete during construction. We suggest that a reasonable frequency of concrete tests can best be determined on a site, materials and construction specific basis although as a guideline American Concrete Institute, ACI, suggests one test per about each fifty (50) cubic yards or portion thereof per day of concrete material placed.

18.0 LIMITATIONS

It is the owner's and the owner's representatives' responsibility to read this report and become familiar with the recommendations and suggestions presented. We should be contacted if any questions arise concerning the geotechnical engineering aspects of this project as a result of the information presented in this report.

The scope of services for this study does not include either specifically or by implication any environmental or biological (such as mold, fungi, bacteria, etc.) Assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be performed.

29

The proposed building site contains soil materials with significant swell potential. For this reason we suggest that you consult, as suggested by Senate Bill 13, a copy of Colorado Geological Survey Special Publication 11, "Home Construction on Shrinking and Swelling Soils", and a copy of CGS Special Publication 14, "Home Landscaping and Maintenance on Swelling Soils". We are available to discuss this with you.

The recommendations outlined above are based on our understanding of the currently proposed construction. We are available to discuss the details of our recommendations with you and revise them where necessary. This geotechnical engineering report is based on the proposed site development and scope of services as provided to us by Mr. Todd Abramson, Habitat for Humanity of the San Juan's, on the type of construction planned, existing site conditions at the time of the field study, and on our findings. Should the planned, proposed use of the site be altered, Lambert and Associates must be contacted, since any such changes may make our suggestions and recommendations inappropriate. This report should be used ONLY for the planned development for which this report was tailored and prepared, and ONLY to meet information needs of the owner and the owner's representatives. In the event that any changes in the future design or location of the building are planned, the conclusions and recommendations contained in this report shall not be considered valid unless the changes are reviewed and conclusions of this report are modified or verified in writing. It is recommended that the geotechnical engineer be provided the opportunity for a general review of the final project design and specifications in order that the earthwork and foundation recommendations may be properly interpreted and implemented in the design and specifications.

This report does not provide earthwork specifications. We can provide guidelines for your use in preparing project specific earthwork specifications. Please contact us if you need these for your project.

This report presents both suggestions and recommendations. The suggestions are presented so that the owner and the owner's representatives may compare the cost to the potential risk or benefit for the suggested procedures.

This report contains suggestions and recommendations which are intended to work in concert with recommendations provided by the other design team members to provide somewhat

30

predictable foundation performance. If any of the recommendations are not included in the design and construction of the project it may result in unpredictable foundation performance or performance different than anticipated. We recommend that we be requested to provide geotechnical engineering observation and materials testing during the construction phase of the project as discussed in this report. The purpose for on site observation and testing by us during construction is to help provide continuity of service from the planning of the project through the construction of the project. This service will also allow us to revise our recommendations if conditions occur or are discovered during construction that were not evidenced during the initial study. We suggest that the owner and the contractor make provisions in their construction budget and construction schedule to accommodate unexpected subsurface conditions.

We represent that our services were performed within the limits prescribed by you and with the usual thoroughness and competence of the current accepted practice of the geotechnical engineering profession in the area. No warranty or representation either expressed or implied is included or intended in this report or our contract. We are available to discuss our findings with you. If you have any questions please contact us. The supporting data for this report is included in the accompanying figures and appendices.

This report is a product of Lambert and Associates. Excerpts from this report used in other documents may not convey the intent or proper concepts when taken out of context, or they may be misinterpreted or used incorrectly. Reproduction, in part or whole, of this document without prior written consent of Lambert and Associates is prohibited.

This report and information presented can be used only for this site, for this proposed development, and only for the client for whom our work was performed. Any other circumstances are not appropriate applications of this information. Other development plans will require project specific review by us.

We have enclosed a copy of a brief discussion about geotechnical engineering reports published by Association of Soil and Foundation Engineers for your reference.

If you plan to utilize the services of Home Buyers Warranty for the proposed development you should become familiar with their construction criteria prior to beginning your development.

31



For further information we suggest you contact Home Buyers Warranty, 2675 S. Abilene Street, Aurora, Colorado, 80014, 1-800-488-8844 for a copy of their manual.


Please call when further consultation or observations and tests are required.

If you have any questions concerning this report or if we may be of further assistance, please contact us.


Respectfully submitted LAMBERT AND Daniel R. Lambe Geotechnical Enginee

Reviewed by ° 18168 Dennis D. Lamberts Geotechnical Engineer






Lambert and AssociatesProject No.M17022GEDate:November 17, 2017Figure:1





Indicates approximate test boring locations This sketch was reproduced by information provided by others and is intended to present geotechnical engineering data only NO SCALE


TEST BORING LOCATION SKETCH

	Project No.	M17022GE
Lambert and Associates	Date:	November 17, 2017
	Figure:	2









APPENDIX A


The field study was performed on October 18, 2017. The field study consisted of logging and sampling the soils encountered in three (3) small diameter test borings in the general vicinity of the proposed single family residential structure. The logs of the soils encountered in the test borings and profile boring are presented on Figures A2 through A4.

The test borings were logged by Lambert and Associates and samples of significant soil types were obtained. The samples were obtained from the test borings using a Modified California Barrel sampler and bulk disturbed samples were obtained. Penetration blow counts were determined using a 140 pound hammer free falling 30 inches. The blow counts are presented on the logs of the test borings such as 7/6 where 7 blows with the hammer were required to drive the sampler 6 inches.

The engineering field description and major soil classification are based on our interpretation of the materials encountered and are prepared according to the Unified Soil Classification System, ASTM D2488. The description and classification which appear on the test boring log is intended to be that which most accurately describes a given interval of the test boring (frequently an interval of several feet). Occasionally discrepancies occur in the Unified Soil Classification System nomenclature between an interval of the soil log and a particular sample in the interval. For example, an interval on the test boring log may be identified as a silty sand (SM) while one sample taken within the interval may have individually been identified as a sandy silt (ML). This discrepancy is frequently allowed to remain to emphasize the occurrence of local textural variations in the interval.

The stratification lines presented on the logs are intended to present our interpretation of the subsurface conditions encountered in the test boring. The stratification lines represent the approximate boundary between soil types and the transition may be gradual.

A1



Project Name: Lot 15 - Parkside


Project Number: M17022GE

Figure: A1

CONSULTING GEOTECHNICAL ENGINEERS AND MAYPERING GEOTECHNICAL ENGINEERS AND MAYPERING GEOTECHNICAL ENGINEERS AND

				LOG OF TEST I	BORING	
	Date Drilled: October 18, 2017 Field Engineer: DRL Boring Number: 1					
	ocation: See test boring location diagram Elevation: iameter: 4 inches Total Depth: 15 feet Depth to Water at Time of Drilling: None Encountered				Elevation:	
And and Addition of the local division of the		Sample			to water at time of Drining: None Encountered	
Symbol	Depth	Туре	N	Soil Description	Laboratory Test Results	
S						
	0 1				-	
	-			Clay, silty, moist, stiff, gray, brown	+	
	Ť			김 아이의 손 가슴한 것 것	+	
	1				+	
	5 -	cX	7/6 7/6		Swell/Consolidation Test: DD: 99 pcf MC: 18.0%	
11.1.111 11.1.111 11.1.111	_		2/0			
	÷	c	3/6 5/6		+	
	-			* Increased Moisture Content	+	
1. (1) 1. (1) 1. (1) 1. (1)	10 -			Observed	+	
	-				—	
	Ť				—	
	15 -					
	-			Bottom of Test Boring at 15 feet	+	
	-				+	
	-				+	
					+	
	20 -					
					1	
	25			2.0 성업 것이 모두 지수	1	
Proi	ect Na	ame:	Lot 15 -	Parkside Project	t Number: M17022GE Figure: A2	

Lambert and Aziliantert and Associates CONSULTING GEOTECHNICAL ENGINEERS AND MATERIAL TESTING



Lambert and Astociatest and Associates CONSULTING GEOTECHNICAL ENGINEERS AND MATERIAL DESTING

m	eter:	See test boring location diagram 4 inches Total Depth: 15 feet			Elevation: Depth to Water at Time of Drilling: None Encountered		
	Depth	Туре	mple N	Soil Description	Laboratory Test Results		
				Clay, silty, moist, stiff, gray, brown			
マンシンシンシンシンシンシンシンシンシンシンシンシンシンシンシンシンシンシンシ	5 -	c	18/6 12/6		Swell/Consolidation Test: DD: 113 pcf MC: 16.7%		
シンシンシン シンシンシンシンシンシンシンシンシンシンシンシンシンシンシンシン	10 -			* Increased Moisture Content Observed			
	15 -			Bottom of Test Boring at 15 feet			
	20 -						
	25				-		

Lambert and Astornbert and Associates CONSULTING GEOTECHNICAL ENGINEERS AND MARY ERIAL TESTING

APPENDIX B

The laboratory study consisted of performing:

. Moisture content and dry density tests,

- . Swell-consolidation tests, and
- . Direct Shear Strength tests.

It should be noted that samples obtained using a drive type sleeve sampler may experience some disturbance during the sampling operations. The test results obtained using these samples are used only as indicators of the in situ soil characteristics.

TESTING

Moisture Content and Dry Density

Moisture content and dry density were determined for each sample tested of the samples obtained. The moisture content was determined according to ASTM Test Method D2216 by obtaining the moisture sample from the drive sleeve. The dry density of the sample was determined by using the wet weight of the entire sample tested. The results of the moisture and dry density determinations are presented on the logs of borings, Figures A2 through A4.

Swell Tests

Loaded swell tests were performed on drive samples obtained during the field study. These tests are performed in general accordance with ASTM Test Method D2435 to the extent that the same equipment and sample dimensions used for consolidation testing are used for the determination of expansion. A sample is subjected to static surcharge, water is introduced to produce saturation, and volume change is measured as in ASTM Test Method D2435. Results are reported as percent change in sample height.

Consolidation Tests

One dimensional consolidation properties of drive samples were evaluated according to the provisions of ASTM Test Method D2435. Water was added in all cases during the test.

M17022GE

Exclusive of special readings during consolidation rate tests, readings during an increment of load were taken regularly until the change in sample height was less than 0.001 inch over a two hour period. The results of the swell-consolidation load test are summarized on Figures B1 and B2, swell-consolidation tests.


It should be noted that the graphic presentation of consolidation data is a presentation of volume change with change in axial load. As a result, both expansion and consolidation can be illustrated.

Direct Shear Strength Test


Direct shear strength properties of sleeve samples were evaluated in general accordance with testing procedures defined by ASTM Test Method D3080. The results of the direct shear tests are summarized on Figure B3, direct shear test.







PRESSURE (POUNDS PER SQUARE FOOT) 10 1,000 10,000 100 6 5 4 3 2 Swell 1 0 % Consolidation 1 2 3 Water added to sample 4 5 6 SUMMARY OF TEST RESULTS Moisture **Dry Density** Height Diameter Swell Pressure Boring No. 3 Depth PCF 4-5 ft Content % in In PSF Initial 16.7 113 1.00 1.94 ±2,100 0.978 Final 20.3 116 1.94 Soil Description Clay, sandy, brown SWELL-CONSOLIDATION TEST Project No. M17022GE Lambert and Associates November 17, 2017 Date: **B**2 Figure:



% Strain	Cohesion (psf)	Friction Angle (deg)	
2	242	12	
4	332	10	
6	408	11	
		Project No.: Date:	M17022GE November 17, 2017

B3

Figure:

APPENDIX C

GEOLOGY DISCUSSION SOUTHWEST COLORADO GEOLOGY

Southwest Colorado exhibits many geologic features formed by a multitude of geologic processes. Regional inundation, uplift, volcanism and glaciation are responsible for some of the complex geology of the region. Many theories and speculations concerning the mode of occurrence of the regions's geology have been presented over the years. This cursory discussion of the geology of southwest Colorado presents some theories accepted by the geologic community, but is only intended to introduce the basic concepts and restraints that arise due to geologic activity.

Prior to the formation of the Rocky Mountains southwest Colorado was a primarily a flat lying region with little topographic expression. The North American continent was experiencing many episodes of deposition. The Transcontinental Sea was transgressing and regressing across the continent, these transgressions and regressions are the cause for such diverse rock types. The stratigraphic column in southwestern Colorado expresses rock types from variable depositional environments. Limestones are formed in deeper water, sandstones are formed in beach and tidal flat environments, while arkosic sandstone and conglomerates are formed in alluvial plains and fans. Particle size and mineralogic content in rock units are related to the depositional environment. A sandstone or conglomerate would not be likely to form in a deep sea environment because there would not be enough energy to carry such large particles a great distance from the source lands. As one observes the stratigraphic column of southwest Colorado a siltstone may be overlain by a sandstone which is in turn overlain by a siltstone. This represents a regressional then transgressional sequence. Many such sequences or combinations of other rock units are exhibited throughout southwest Colorado.

The final regression of the sea may have been caused by orogenic activity and uplift. This uplift was not confined to Colorado, it was a regional uplift that occurred in many stages. The uplift is what caused the formation of the ancestral rockies. The Larimide Orogenic episode is responsible for the formation of the San Juan dome. (Note: The San Juan

dome theory is not accepted by the entire geologic community. It is used here for descriptive purposes). The San Juan dome was essentially an upwarp of the stratigraphy formed by sedimentation during the Transcontinental Sea. An actual dome probably never existed due to erosion during the uplift. The idea being that a dome of sediments and rock units would have existed had erosion and diastrophism not taken place. The orientation of bedding planes forms a radial pattern around the San Juan region which seems to vindicate this theory.

The stresses need to "upwarp" this large area were obviously tremendous. Locally occurring stresses may not be sufficient to move this quantity of material, global tectonics, directly or indirectly, may have been involved. Compression of the entire North American plate could have occurred. The magnitude of the stresses and the deep seated origin of these stresses also have caused extensive volcanism. Colorado has many large remnants of Calderas that were active during the orogenic activity. The Silverton and Lake City Calderas are the largest in the San Juan region. Activity in the Silverton Caldera has been estimated (radiometrically) to have occurred 22 million years ago. Calderas of this magnitude are believed to have formed by the collapse of epierogenic magma chambers. Volcanic and metamorphic rock bodies are common in the San Juan region, many of these units are related to the orogenic activity in the region.

Faults associated with local orogenic activity are another common geologic feature found in southwestern Colorado. As stated previously, extreme stresses were probably associated with the formation of the San Juan Mountains and may be responsible for deepseated volcanic and metamorphic processes. These stresses had to be released, the geologic mode for stress release is faulting. Diastrophic activity in the area today is quite low, the lack of seismic activity indicates that stresses are not currently being released. An explanation for the loss of stresses is through faulting.

The last episode of regional geologic activity in the area was glaciation. The most recent period of glacial activity ended approximately 10,000 years ago. Glacial activity is responsible for much of the topographic expression in the area. "U-Shaped" valleys, moraine deposits, tarns, (glacial formed lakes), and rock glaciers are the most prominent features which are found in southwestern Colorado as a result of glacial activity. The valley configurations are a result of the erosional activity of the glaciers. Moraine deposits

developed during the glacial activity. Rock glaciers are moving masses of rock which are thought to have an ice core which may be the last remnant of glacial ice. As the surbsurface ice core moves and melts, the overlying mass of rock also moves.



APPENDIX D

GENERAL GEOTECHNICAL ENGINEERING CONSIDERATIONS

D1.0 INTRODUCTION

Appendix D presents general geotechnical engineering considerations for design and construction of structures which will be in contact with soils. The discussion presented in this appendix are referred to in the text of the report and are intended as tutorial and supplemental information to the appropriate sections of the text of the report.

D2.0 FOUNDATION RECOMMENDATIONS

Two criteria for any foundation which must be satisfied for satisfactory foundation performance are:

- . contact stresses must be low enough to preclude shear failure of the foundation soils which would result in lateral movement of the soils from beneath the foundation, and
- . settlement or heave of the foundation must be within amounts tolerable to the superstructure.

The soils encountered during our field study have varying engineering characteristics that may influence the design and construction considerations of the foundations. The characteristics include swell potential, settlement potential, bearing capacity and the bearing conditions of the soils supporting the foundations. The general discussion below is intended to increase the readers familiarity with characteristics that can influence any structure.

D2.1 Swell Potential

Some of the materials encountered during our field study at the anticipated foundation depth may have swell potential. Swell potential is the tendency of the soil to increase in volume when it becomes wetted. The volume change occurs as moisture is absorbed into the soil and water molecules become attached to or adsorbed by the individual clay platlets. Associated with the process of volume change is swell pressure. The swell pressure is the force the soil applies on its surroundings when moisture is absorbed into the soil. Foundation design considerations concerning swelling soils include structure tolerance to movement and dead load pressures to help restrict uplift. The structure's tolerance to movement should be addressed by the structural engineer and is dependent upon many facets of the design

including the overall structural concept and the building material. The uplift forces or pressure due to wetted clay soils can be addressed by designing the foundations with a minimum dead load and/or placing the foundations on a blanket of compacted structural fill. The compacted structural fill blanket will increase the dead load on the swelling foundations soils and will increase the separation of the foundation from the swelling soils. Suggestions and recommendations for design dead load and compacted structural fill blanket are presented below. Compacted structural fill recommendations are presented under COMPACTED STRUCTURAL FILL below.

D2.2 Settlement Potential

Settlement potential of a soil is the tendency for the soil to experience volume change when subjected to a load. Settlement is characterized by downward movement of all or a portion of the supported structure as the soil particles move closer together resulting in decreased soil volume. Settlement potential is a function of;

- . foundation loads,
- . depth of footing embedment,
- the width of the footing, and
- the settlement potential or compressibility of the influenced soil.

Foundation design considerations concerning settlement potential include the amount of movement tolerable to the structure and the design and construction concepts to help reduce the potential movement. The settlement potential of the foundation can be reduced by reducing foundation pressures and/or by placing the foundations on a blanket of compacted structural fill. The anticipated post construction settlement potential and suggested compacted fill thickness recommendations are based on site specific soil conditions and are presented in the text of the report.

D2.3 Soil Support Characteristics

The soil bearing capacity is a function of;

- . the engineering properties of the soil material supporting the foundations,
- . the foundation width,
- . the depth of embedment of the bottom of the foundation below the
- . lowest adjacent grade,
- . the influence of the ground water, and
- . the amount of settlement tolerable to the structure.

Soil bearing capacity and associated minimum depth of embedment are presented in the text

D2

of the report.

The foundation for the structure should be placed on relatively uniform bearing conditions. Varying support characteristics of the soils supporting the foundation may result in nonuniform or differential performance of the foundation. Soils encountered at foundation depths may contain cobbles and boulders. The cobbles and boulders encountered at foundation depths may apply point loads on the foundation resulting in nonuniform bearing conditions. The surface of the formational material may undulate throughout the building site. If this is the case it may result in a portion of the foundation being placed on the overlying soils. Varying support material will result in nonuniform bearing conditions. The influence of nonuniform bearing conditions may be reduced by placing the foundation members on a blanket of compacted structural fill. Suggestions and recommendations for constructing compacted structural fill are presented under COMPACTED STRUCTURAL FILL below and in the text of the report.

D3.0 COMPACTED STRUCTURAL FILL

Compacted structural fill is typically a material which is constructed for direct support of structures or structural components.

There are several material characteristics which should be examined before choosing a material for potential use as compacted structural fill. These characteristics include;

- . the size of the larger particles,
- . the engineering characteristics of the fine grained portion of material matrix,
- . the moisture content that the material will need to be for compaction with respect to the existing initial moisture content,
- . the organic content of the material, and
- . the items that influence the cost to use the material.

Compacted fill should be a non-expansive material with the maximum aggregate size less than about two (2) inches and less than about twenty five (25) percent coarser than three quarter (3/4) inch size.

The reason for the maximum size is that larger sizes may have too great an influence on the compaction characteristics of the material and may also impose point loads on the footings or floor slabs that are in contact with the material. Frequently pit-run material or crushed aggregate material is used for structural fill material. Pit-run material may be satisfactory, however crushed aggregate material with angular grains is preferable. Angular particles tend

to interlock with each other better than rounded particles.

The fine grained portion of the fill material will have a significant influence on the performance of the fill. Material which has a fine grained matrix composed of silt and/or clay which exhibits expansive characteristics should be avoided for use as structural fill. The moisture content of the material should be monitored during construction and maintained near optimum moisture content for compaction of the material.

Soil with an appreciable organic content may not perform adequately for use as structural fill material due to the compressibility of the material and ultimately due to the decay of the organic portion of the material.

D4.0 RADON CONSIDERATIONS


Information presented in "Radon Reduction in New Construction, An Interim Guide: OPA-87-009 by the Environmental Protection Agency dated August 1987 indicates that currently there are no standard soil tests or specific standards for correlating the results of soil tests at a building site with subsequent indoor radon levels. Actual indoor levels can be affected by construction techniques and may vary greatly from soil radon test results. Therefore it is recommended that radon tests be conducted in the structure after construction is complete to verify the actual radon levels in the home.

We suggest that you consider incorporating construction techniques into the development to reduce radon levels in the residential structures and provide for retrofitting equipment for radon gas removal if it becomes necessary.

Measures to reduce radon levels in structures include vented crawl spaces with vapor barrier at the surface of the crawl space to restrict radon gas flow into the structure or a vented gravel layer with a vapor barrier beneath a concrete slab-on-grade floor to allow venting of radon gas collected beneath the floor and to restrict radon gas flow through the slab-on-grade floor into the structure. These concepts are shown on Figure D1.

If you have any questions or would like more information about radon, please contact us or the State Health Department at 303-692-3030.

D4



7C Y L X A + L	Project No.	M17022GE
Lambert and Associates	Date:	November 17, 2017
	Figure: D1	D1



January 6, 2023

Habitat for Humanity of the San Juans Amanda Gerhardt, Exec. Dir. PO Box 162 Montrose, CO 81402

SENT VIA E-MAIL TO amanda@buildinglives.org

RE: Amended Plat for Lot 15, Parkside Subdivision and Side Setback Variance, 1s^t Planning Review Comments.

Dear Amanda:

The above-mentioned application and supplemental materials were reviewed by Community Planning Strategies (CPS). The enclosed comments represent the findings of the review against applicable Town of Ridgway (Town) development and land use regulations.

The following items must be addressed and resubmitted to the Town to be reviewed and evaluated:

- 1. To be more in line with the currently adopted landscape regulations, please consider using the alternative landscaping #6 where landscaping stone is uses and reduce the amount of turf. (Sec. 7-7-7-D of PMC)
- 2. The proposed 6' fence cannot impede the flow of the drainage easement along the eastern property line.
- 3. Amend the title of the amended plat to be:

Final Plat for [*Subdivision Name*] An Amendment to Lot 15, Parkside Subdivision SE ¼ Section 8 and SW ¼ Section 9, Township 45 North, Range 8 West, New Mexico Principal Meridian Town of Ridgway, Ouray County, Colorado

4. Add the following certificates to the plat:

ATTORNEYS CERTIFICATE:

I, ______, an attorney at law duly licensed to practice before the courts of record of Colorado, do hereby certify that I have examined the Title Commitment Order Number _______effective as of _______at __:____.M. issued by ______and according to that title commitment, of all land herein platted and that title to such land is in the dedicator(s) and owners, and that based upon my review of said title commitment, the property dedicated hereon has been dedicated free and clear of all liens and encumbrances, except as follows:

• Dated this ______day of ______, 202___. By: _____

[legal counsel Name] , Attorney at Law

PLANNING COMMISSION: Recommended for approval by the Planning Commission this day of, 202
Ву:
Michelle Montague, Town of Ridgway Planning Commission Chairperson
TOWN COUNCIL:
Approved by the Town Council thisday of
202 But
By: John Clark, Town of Ridgway Mayor
APPROVAL OF TOWN ATTORNEY:
Approved for recording with the Ouray County Clerk and Recorder's Office thi day of, 202
Ву:,
Bo Nerlin, Town of Ridgway Town Attorney
CERTIFICATE OF IMPROVEMENTS:
The undersigned, Town Manager of the Town of Ridgway, certifies that all required improvement
and utilities are installed, available, and adequate to serve each lot in the
Subdivision.
Dated this day of, 202
By:
Preston Neill, Town of Ridgway Town Manager

LIEN HOLDER'S CERTIFICATE:

The undersigned, being the holder of a deed of trust (Reception No.____) encumbering the property described in (name of subdivision) joins in and consents to the filing hereof for: _____(name of lien holder)_____BY:_____TITLE:

TREASURERS CERTIFICATE:

According to the records of the County of Ouray Treasurer there are no liens against this subdivision or any part thereof for unpaid state, county municipal or local taxes or special assessments due and payable.

Dated this	dav	/ of	202	
	uu		202	

By:

Jill Mihelich, Ouray County Treasurer

- 5. Add the following notes to the plat:
 - a. All construction will conform with the Ridgway Municipal Code.

Town of Ridgway Habitat for Humanity Triplex January 6, 2023 3 of 3

- b. Outdoor Lighting; All outdoor lighting shall conform to Ridgway Municipal Code Section 6-5 "Outdoor Lighting regulations", as may be amended.
- c. Any water or sewer tap fees which have not been paid or waived pursuant to Note 6 of the Parkside Subdivision plat shall be paid in accordance with Section 9-1-9 of the Ridgway Municipal Code prior to issuance of the first building permit for any lot in this subdivision.
- d. The property platted hereby is subject to the plat notes as recorded in Parkside Subdivision as recorded in the Ouray County Records at Reception No. 197315, and the Declarations of protective covenants, conditions, and restrictions of Parkside Subdivision as recorded in the Ouray County Records at Reception No. 197316 and as may be amended from time to time.
- e. The property platted hereon is subject o the prior easements as shown hereon.
- 6. If applicable excise tax pursuant to Section 4 Development Excise Tax of Chapter 3 Finance of the RMC has not been paid, such tax must be paid in accordance with this section prior to the plat amendment being recorded with the Ouray County Clerk and Recorder.
- 7. There appear to be many measurement discrepancies between the recorded bearings and distances and those indicated on the Amended Plat. Please evaluate and correct discrepancies where applicable. Where the measurements differ from the recorded plat, please provide written explanation of why they differ.
- 8. Address all redlines and comments on attached submitted materials.

We reserve the right to provide additional comments once more information is provided. Please reach out if you have any questions regarding these review comments.

Sincerely,


COMMUNITY PLANNING STRATEGIES, LLC

& Dollar

TJ Dlubac, AICP Principal / Owner 970-744-0623 TDlubac@PlanStrategize.com

Encl: Planning Review Redlines

Cc: Preston Neill, Town of Ridgway Town Manager





CERTIFICATE OF OWNERSHIP DEDICATION

Known all persons by these presents that we, the undersigned being the owners of certain lands in Ouray County, Colorado, described as Lot 15, Parkside Subdivision, Ouray County, Colorado, have caused same to be laid out and platted as shown on this plat under the name and style of Amended Plat of Lot 15 Parkside Subdivision.

Executed this	day of		2022	
Owner: Habitat for Humanity	of the San Juans			
Ву:			Date:	
Printed Name:				
Title:				
STATE OF COLORADO) ss.)			
COUNTY OF)			
The foregoing Owner Certifica	ate was acknowledged before me this	s day of _		, A.D. 2022,
by	as the			_ of Habitat for Humanity of the San Juans
Witness my hand and official	seal.			
			My Commision Expire	95:


Notary Public

SURVEYOR'S CERTIFICATE

I, Jeremiah D. Harness, a Registered Land Surveyor in the State of Colorado, hereby certify that this Amended Plat of Lot 15 Parkside Subdivision was prepared under my direction and supervision and that said survey is accurate to the best of my knowledge, conforms to all the requirements of the Colorado Revised Statutes, and all applicable Town of Ridgway regulations, and that all required monuments have been set as shown. There are no roads, pipelines, irrigation ditches or other easements or rights- of-way in evidence or known to me to exist on or across said property except as shown on this plat. I certify that I have made the survey represented by this plat and that this plat accurately represents said survey, and conforms to all applicable requirements of the City Subdivision Regulations and applicable law. I further certify that all monuments shown hereon actually exist and their positions are as shown.

Jeremiah D. Harness Colorado Registered Lan Registration No. 38758 Date:	d Surveyor				
	RECORDER'S CERTIFICAT	E			
	This Amended plat of Lot 15 Parkside Su	bdivision was file	d for record in the	office of the Clerk and Recorder of Oura	y County at
Χ	m. on the day of		, 20		
	Reception No	_·			
	County Clerk & Recorder	, 1	by Deputy		
		PART	PAR SITUATED I TOWNS OF THE SCHOOL A	NDED PLAT OF LOT 1 KSIDE SUBDIVISION IN THE SE ¹ / ₄ SECTION 8 AND SW ¹ / ₄ SECTIO SHIP 45 NORTH, RANGE 8 WEST, NMPM ADDITION TO THE TOWN OF RIDGWAY, F ITY OF OURAY, STATE OF COLORADO	N 9
recorded and and		PLAT DATE: PROJ. #	11/03/2022 22-201-SUR	BUCKHOR	V
d		CAD FILE: 22-20 PARKS	1-SUR LOT15 SIDE SUB.dwg	ENGINEERING	
		DRAFTER:	JDH	jrease@buckhornengineering.com 222	South Park Avenue
		FEILD DATE:	10/18/2022	Montro	ose, Colorado 81401
	1.5" CAP LS 16840	FIELD CREW:	JDH	0.1517	970-249-6828
		AREA: CLOSURE:	1.31 ACRES CLOSURE	CLIENT: HABITAT FOR HUMANITY OF THE SAN JUANS	DRAWING NUMBER V-1 1 OF 1

CPS Review 2/17/2022



LANDSCAPE NOTES:

1. THE OWNER AND GENERAL CONTRACTOR SHALL ENSURE THAT THE LANDSCAPE PLAN IS COORDINATED WITH THE PLANS PREPARED BY OTHER CONSULTANTS SO THAT THE PROPOSED GRADING, STORM DRAINAGE, EXTERIOR LIGHTING OR OTHER CONSTRUCTION DOES NOT CONFLICT WITH NOR PRECLUDE INSTALLATION OF MAINTENANCE OF LANDSCAPE ELEMENTS AS DESIGNATED ON THIS PLAN.

2. INSTALL A NEW UNDERGROUND AUTOMATIC IRRIGATION SYSTEM. IF DOMESTIC WATER IS USED, INSTALL A BACKFLOW PREVENTER WITH LOCKABLE ENCLOSURE. IF DITCH IRRIGATION WATER IS USED, INSTALL A PUMP WITH FILTER. AN AUTOMATIC IRRIGATION CONTROLLER SHALL BE INSTALLED FOR THE NEW SYSTEM. TURF GRASS AREAS SHALL BE IRRIGATED USING POP-UP SPRAY OR ROTOR TYPE HEADS. ALL SHRUBS AND TREES SHALL BE IRRIGATED USING DRIP/BUBBLER IRRIGATION. MEADOW GRASS IS EXISTING AND IS NON-IRRIGATED.

3. TOPSOIL SHALL BE IMPORTED FROM ON-SITE EXCAVATION AREAS INTO ALL OF THE LANDSCAPE AREAS TO BE PLANTED WITH TREES, SHRUBS, AND SOD. THERE SHALL BE A MINIMUM OF 8" OF TOPSOIL IN ALL SHRUB BED AREAS AND SOD GRASS AREAS.

4. SOIL PREPARATION FOR GRASS AREAS SHALL BE ORGANIC MATTER (100% DECOMPOSED WOOD CHIPS) APPLIED AT A RATE OF 3-5 CY/1000 SF., AND TILLED TO A DEPTH OF 6"-8", AND FINE GRADED.

6. WHEN INSTALLING EACH PLANT, PLANT MIX SHALL BE COMPRISED OF 1 PART SOIL CONDITIONER (DECOMPOSED BARK MULCH OR "BACK-TO-EARTH" ACIDIFIER PRODUCT) TO 2 PARTS TOPSOIL. OVER EXCAVATE THE PLANTING HOLES TWO TIMES THE DIAMETER OF THE ROOTBALL. FILL WITH PLANT MIX. ROOTING HORMONE SUCH AS INDOL 3 BUTERIC ACID SHALL BE USED FOR ALL TREES & SHRUBS.

7. ALL SHRUB BED AREAS SHALL BE SEPARATED FROM GRASS AREAS BY A STEEL LANDSCAPE EDGER. 3" DEEP MULCH SHALL BE PLACED OVER WEED BARRIER FABRIC.

8. SHRUB BEDS SHALL HAVE "DEWITT PRO 5" WEED BARRIER FABRIC OR APPROVED EQUAL INSTALLED UNDER MULCH UNLESS NOTED OTHERWISE -OVERLAP SEAMS MIN. 4" AND ATTACH FABRIC IN PLACE WITH 8" LONG STAPLES AT MAX. 4' O.C.

9. WHEN PLANTING TREES OR SHRUBS: THOROUGHLY SOAK PLANTING HOLE WHILE BACKFILLING. PRUNE DEAD OR DAMAGED BRANCHES IMMEDIATELY AFTER PLANTING. FERTILIZE WITH AGRIFORM 21 GRAM PLANT TABLETS, 20–10–5. 6 TABLETS PER TREE, AND 3 PER SHRUB.

10. SHREDDED CEDAR BARK MULCH SHALL BE PLACED AROUND THE DRIPLINE OF EACH PLANT TO MAINTAIN MOISTURE, 4 FT. DIAMETER AROUND TREES, AND 2 FT. DIAMETER AROUND SHRUBS. DO NOT LET BARK MULCH TOUCH THE BASE AND STEM OF EACH PLANT - KEEP CLEAR 2".

11. ALL DECIDUOUS TREES SHALL BE STAKED WITH (2) 6 FT. T-POSTS. ALL EVERGREEN TREES SHALL BE STAKED WITH (3) 2 FT. T-POSTS. ALL POSTS SHALL BE GUYED TO THE TREE WITH 12 GA. WIRE ENCASED IN RUBBER HOSE.

12. ALL TREES WITHIN THE SIGHT TRIANGLES SHALL BE LIMBED UP TO A HEIGHT OF 8 FT. AS THE TREE GROWS, AND THIS CLEARANCE SHALL BE MAINTAINED.


13. LOCATE AND MARK LOCATIONS OF ALL UTILITIES PRIOR TO COMMENCING WORK. DO NOT PLANT ANY TREES OR SHRUBS DIRECTLY OVER BURIED UTILITY LINES, OR ANY TREES UNDER OVERHEAD UTILITY LINES.

14. PLANT MATERIAL WAS CHOSEN FOR ITS SPECIFIC VARIETY, HEIGHT, AND COLOR. ANY PLANT MATERIAL SUBSTITUTIONS MUST BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION.


15. ALL PLANT MATERIAL SHALL BE GROWN IN A NURSERY IN ACCORDANCE WITH PROPER HORTICULTURAL PRACTICE. PLANS SHALL BE HEALTHY, WELL-BRANCHED, AND VIGOROUS WITH A GROWTH HABIT NORMAL TO THE SPECIES AND VARIETY, AND FREE OF DISEASES, INSECTS, AND INJURIES.

16. CONTRACTOR TO WARRANTY IRRIGATION SYSTEM AND ALL PLANT MATERIAL FOR A PERIOD OF ONE YEAR. REPLACE ANY DEAD OR DYING PLANTS DURING THAT ONE-YEAR WARRANTY PERIOD.

REVISIONS	BY
UPDATED CIVIL & ARCH BASES	9/2/20



61945 Nighthawk Road Montrose, CO 81403 office: 970.249.9392 mobile: 970.417.1779 julee@juleewolverton.con



LANDSCAPE NOTES & DETAILS

SHEET No.

L-2

AGENDA ITEM #4



То:	Town of Ridgway Planning Commissioners
From:	Katie Kent, <i>CPS, Contracted Town Planner</i> TJ Dlubac, <i>CPS, Contracted Town Planner</i>
Cc:	Preston Neill, Town Manager
Date:	January 6, 2023
Subject:	Ridgway Municipal Code, Chapter 7 Process Update

As a follow-up to the Planning Commission discussions held on September 22, 2022, and November 29, 2022, we are excited to return to you to present an explanation of proposed application processes as we move forward with amending Chapter 7 of the Ridgway Municipal Code (RMC).

To recap those earlier discussions, this project was kicked off in September when we proposed a scope of services to develop updates and discussed those with the Planning Commission. It was explained that the primary objectives of updating Chapter 7, Zoning and Subdivision Regulations were to:

- 1. Clarify the zoning and subdivision review process,
- 2. Remove contradictions and duplication between Code sections, and
- 3. Create a system that can easily be updated to adapt to changing trends and needs

To reach these objectives, CPS provided a scope of work that included updating the procedures, evaluating ancillary sections of the RMC to ensure there are no contradictions, and provide the town with a graphic clearly describing the application process as well as internal guidelines for staff to use to process applications.

Following that meeting, CPS began reorganizing Chapter 7 and sent an updated draft to Town Staff for review and feedback. An updated draft of the updates were presented to the Planning Commission on November 29th. The slides and other materials presented to the Planning Commission on November 29th are attached to this memo along with the draft updates.

At the January 10, 2023 meeting, we will 1) provide a general overview of the feedback received so far from Planning Commissioners and Town Staff, 2) explain how we are making updates in response to that feedback and 3) present various development scenarios and explain the processes that an applicant would follow if proposing that type of development within the Town. These scenarios will demonstrate how an applicant would move forward through Town Staff reviews, Planning Commission consideration, and/or Town Council approval, based on the requests.

Attachment: November 29, 2022 meeting packet.

Planning Commission November 29, 2022 Worksession Meeting Materials

- Memo to Planning Commissioners dated November 23, 2022
- PowerPoint presented to Planning Commission November 29, 2022
- Proposed Code Updates



То:	Town of Ridgway Planning Commissioners
From:	Katie Kent, <i>CPS, Contracted Town Planner</i> TJ Dlubac, <i>CPS, Contracted Town Planner</i>
Cc:	Preston Neill, Town Manager
Date:	November 23, 2022
Subject:	Ridgway Municipal Code, Chapter 7 Proposed Updated Outline

As a follow-up to the Planning Commission meeting discussion held on September 22, 2022, regarding moving forward with amending Chapter 7 of the Ridgway Municipal Code (RMC) to clarify application processes, we have prepared an outline of the proposed section headings.

In the below outline, notes on existing code sections to be evaluated and/or modified through this process are presented in blue italicized font with brackets. This general outline is the first step to updating the procedures and evaluating ancillary sections of the RMC.

The outline below may change over the course of the project, however, the intent is to present the idea of restructuring Chapter 7 to better delineate and separate the three functions of the code:

- 1) Administration: This function includes the legal authority, interpretation, administration, and enforcement provisions of the code. Includes general administration, nonconforming uses and structures, enforcement provisions, etc.
- Procedures: This function includes all the procedures for various review processes. This ties to standards that are required for specific application types as well as the enforcement clauses and provisions as necessary. Includes application review procedures, nonconforming uses and structures, flow charts, etc.
- 3) Standards: This is the meat of a code. This has all the standards that need be met ranging from subdivision design, infrastructure improvements, zoning district standards and uses, to use requirements. Includes zoning district standards, use standards, development standards, subdivision standards, nonconforming uses and structures, etc.

Please feel free to follow up with any questions.

Town of Ridgway November 23, 2022 Page 2 of 13

CHAPTER 7, LAND DEVELOPMENT REGULATIONS

SECTION 1 – GENERAL PROVISIONS [This Section has brought in existing language from Code and also added new language]

7-1-1 INTERPRETATION OF THE PROVISIONS OF THESE LAND DEVELOPMENT REGULATIONS [New language]

- 7-1-2 RULES OF CONSTRUCTION OF LANGUAGE [New language]
- 7-1-3 COMPUTATION OF TIME [New language]
- 7-1-4 STATUTORY VESTED PROPERTY RIGHTS [Brought in from Chapter 7, Section 5]
- 7-1-5 ADEQUATE PUBLIC WATER SUPPLY [Brought in from Chapter 7, Section 6]

7-1-6 FEES AND COSTS [Existing 7-4-12. However, removed specific fee amounts and referenced a fee schedule]

7-1-7 ENFORCEMENT AND ADMINISTRATION [Brought in from 7-3-24]

SECTION 2 – PLANNING COMMISSION [No changes were made to this Section]

SECTION 3 – BOARD OF ADJUSTMENT [No changes were made to this Section]

SECTION 4 – ZONING REGULATIONS [This Section has brought in existing language from Code and also added new language]

- 7-4-1 GENERAL PROVISIONS [This brings in existing 7-3-1 along with adding a few other general provisions]
- 7-4-2 ZONING MAP [This is identical to existing 7-3-3]

7-4-3 ZONING APPLICATIONS AND REVIEW PROCEDURES [*This Section outlines review procedures for each application type and then breaks down each application type*]

- (A) Table X-XX Zoning Application Types and Processes [This Table states each zoning application type and what the process is the application goes through including public noticing requirements and approving authority]
- (B) General Application Review Procedures [This Section replaces existing 7-3-23 and clarifies the individual application process steps]
 - (1) Pre-Application Meeting
 - (2) Application Submittal Requirements

(a) Basic Application Materials

- (3) Completeness Review [Within 10 days, review for completeness.]
- (4) Referral Agencies [There is currently not a referral review period for zoning applications; this adds one.]
- (5) Staff Report
- (6) Notice Requirements [Includes 15 day publication in paper, 7 day mailing to adjacent owners, 30 day mineral estates notice]
- (7) Public Hearings
- (8) Post Approval [Includes submitting final documents and recordation of documents]

Town of Ridgway November 23, 2022 Page 3 of 13

- (C) Rezoning
 - (1) General Provisions [Brought in from 7-3-3 and 7-3-22 and added new language]
 - (2) Review Procedures
 - (a) Review flowchart
 - (b) Pre-Application meeting
 - (c) Application submittal requirements
 - (d) Completeness review
 - (e) Evaluation by Staff and Referral Agencies
 - (f) Staff Report
 - (g) Review and Recommendation by Planning Commission
 - (h) Review and Action by Town Council
 - (3) Approval Criteria [Brought in from 7-3-21]
- (D) Text Amendment [7-3-22 states Amendments and Additions to Zoning Regulations but does not give clear information on text language amendments so this section is written from scratch]
 - (1) General Provisions
 - (2) Review Procedures
 - (a) Review flowchart
 - (b) Staff Report
 - (c) Review and Recommendation by Planning Commission
 - (d) Review and Action by Town Council
 - (3) Approval Criteria
- (E) Conditional Uses
 - (1) General Provisions
 - (2) Applicability
 - (3) Concurrent Applications
 - (4) Existing Permits
 - (5) Review and Revocation of a Conditional Use Permit
 - (6) Review Procedures
 - (a) Review flowchart
 - (b) Pre-Application meeting
 - (c) Application submittal requirements
 - (d) Completeness review
 - (e) Evaluation by Staff and Referral Agencies
 - (f) Staff Report
 - (g) Review and Action by Planning Commission

Town of Ridgway November 23, 2022 Page 4 of 13

- (7) Approval Criteria [Brought in from 7-3-19]
- (F) Minor Amendments to a Conditional Use Permit [New application type being added to RMC]
 - (1) General Provisions
 - (2) Review Procedures
 - (a) Review flowchart
 - (b) Pre-Application meeting
 - (c) Application submittal requirements
 - (d) Completeness review
 - (e) Evaluation by Staff and Referral Agencies
 - (f) Review and Decision by Town Manager or designee
 - (3) Approval Criteria [Directs applicants to approval criteria for a CUP application]
- (G) Temporary Use Permits
 - (1) General Provisions [Brought in from 7-3-18 (C)]
 - (2) Review Procedures
 - (a) Review flowchart
 - (b) Pre-Application meeting
 - (c) Application submittal requirements
 - (d) Completeness review
 - (e) Evaluation by Staff and Referral Agencies
 - (f) Review and Decision by Planning Commission [Brought in from 7-3-18 (C)]
 - (3) Approval Criteria
- (H) Site Plan [New application type being added to RMC]
 - (1) General Provisions
 - (2) Review Procedures
 - (a) Review flowchart
 - (b) Pre-Application meeting
 - (c) Application submittal requirements
 - (d) Completeness review
 - (e) Evaluation by Staff and Referral Agencies
 - (f) Review and Decision by Town Manager or designee (may be appealed to Board of Adjustment in accordance with appeal section of Code)
 - (3) Approval Criteria
- (I) Administrative Adjustment [New application type being added to RMC]
 - (1) General Provisions
 - (2) Review Procedures

Town of Ridgway November 23, 2022 Page 5 of 13

- (a) Review flowchart
- (b) Pre-Application meeting
- (c) Application submittal requirements
- (d) Completeness review
- (e) Evaluation by Staff and Referral Agencies
- (f) Review and Decision by Town Manager or designee (may be appealed to Board of Adjustment in accordance with appeal section of Code)
- (3) Approval Criteria
- (J) Variance
 - (1) General Provisions
 - (2) Review Procedures
 - (a) Review flowchart
 - (b) Pre-Application meeting
 - (c) Application submittal requirements
 - (d) Completeness review
 - (e) Evaluation by Staff and Referral Agencies
 - (f) Staff Report
 - (g) Review and Decision by Planning Commission
 - (3) Approval Criteria [Brought in from 7-3-21]
- (K) Appeal [7-3-21 states Variances and Appeals but does not give clear information on appeals so this section is written from scratch]
 - (1) General Provisions
 - (2) Review Procedures
 - (a) Review flowchart
 - (b) Pre-Application meeting
 - (c) Application submittal requirements
 - (d) Completeness review
 - (e) Evaluation by Staff and Referral Agencies
 - (f) Staff Report
 - (g) Review and Decision by Board of Adjustment
 - (3) Approval Criteria

7-4-4 ZONING DISTRICTS

- (A) Establishment of Districts. [Each Zone District is same as exists in current RMC]
- (B) Residential Districts
- (C) Commercial Districts

Town of Ridgway November 23, 2022 Page 6 of 13

- (D) Industrial Districts
- (E) R Low-Density Residential District
 - (1) Intent [Brought in from 7-3-5]
 - (2) District Standard
 - (a) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-5]
 - (b) Lot size and required setbacks. [Refers to Dimensional Standards table copied from existing RMC]
- (F) HR Historic Residential District
 - (1) Intent [Brought in from 7-3-6]
 - (2) District Standards
 - (a) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-6]
 - (b) Lot size and required setbacks. *[Refers to Dimensional Standards table copied from existing RMC]*
- (G) MR Mixed Residential District
 - (1) Intent [Brought in from 7-3-7]
 - (2) District Standards
 - (a) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-7]
 - (b) Lot size and required setbacks. *[Refers to Dimensional Standards table copied from existing RMC]*
 - (3) Performance and Design Standards [Existing language pulled in from 7-3-7]
- (H) FD Future Development District
 - (1) Intent [Brought in from 7-3-8]
 - (2) District Standard
 - (a) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-8]
 - (b) Lot size and required setbacks. *[Refers to Dimensional Standards table copied from existing RMC]*
- (I) HB Historic Business District
 - (1) Intent [Brought in from 7-3-9]
 - (2) District Standards
 - (a) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-9]
 - (b) Lot size and required setbacks. [Refers to Dimensional Standards table copied from existing RMC]
 - (3) Performance and Design Standards [Existing language pulled in from 7-3-9]

Town of Ridgway November 23, 2022 Page 7 of 13

- (J) DS Downtown Service District
 - (1) Intent [Brought in from 7-3-10]
 - (2) District Standards
 - (a) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-10]
 - (b) Lot size and required setbacks. *[Refers to Dimensional Standards table copied from existing RMC]*
 - (3) Performance Standards for Conditional Uses [Existing language pulled in from 7-3-10]
- (K) GC General Commercial District
 - (a) Intent [Brought in from 7-3-11]
 - (b) District Standards
 - (i) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-11]
 - (ii) Lot size and required setbacks. *[Refers to Dimensional Standards table copied from existing RMC]*
 - (c) Performance Standards [Existing language pulled in from 7-3-11]
- (L) I-1 Light Industrial 1 District
 - (a) Intent [Brought in from 7-3-12]
 - (b) District Standards
 - (i) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-12]
 - (ii) Lot size and required setbacks. *[Refers to Dimensional Standards table copied from existing RMC]*
 - (c) Performance Standards [Existing language pulled in from 7-3-12]
- (M) I-2 Light Industrial 2 District
 - (a) Intent [Brought in from 7-3-13]
 - (b) District Standards
 - (i) Permitted uses. [Refers to new Land Use Table which pulls existing permitted and conditional uses from 7-3-13]
 - (ii) Lot size and required setbacks. *[Refers to Dimensional Standards table copied from existing RMC]*
 - (c) Performance Standards [Existing language pulled in from 7-3-13]
- (N) UROD Uncompanyer River Overlay District
 - (a) Purpose and Intent [Brought in from 7-3-14]
 - (b) Applicability [Brought in from 7-3-14]
 - (c) Uses by Right [Brought in from 7-3-14]
 - (d) Conditional Uses [Brought in from 7-3-14]

Town of Ridgway November 23, 2022 Page 8 of 13

- (e) Development between 25 and 75 feet [Brought in from 7-3-14]
- (f) Performance Standards [Brought in from 7-3-14]
- (g) Submittal requirements [Brought in from 7-3-14]
- (h) Exempt Uses and Activities [Brought in from 7-3-14]
- (O) Land Use Table [New table being inserted which brings in all uses within Code into one place and states which zone districts permit uses by right or conditional use within the Code. No changes made to where uses permitted. Still need to finalize all industrial uses into table]
- (P) Zone District Dimensional Standards [Table and associated footnotes brought in from 7-3-15]
- 7-4-5 SUPPLEMENTAL REGULATIONS
 - (A) Home Occupations [Brought in from 7-3-18 (A)]
 - (B) Offensive Businesses [Brought in from 7-3-18 (B)]
 - (C) Use and Location of Travel Homes [Brought in from 7-3-18 (D)]
 - (D) Garage and Yard Sales [Brought in from 7-3-18 (E)]
 - (E) Bed and Breakfast Operations [Brought in from 7-3-18 (F)]
 - (F) Accessory Dwelling Units [Brought in from 7-3-18 (G)]
 - (G) Telecommunication Antenna and Tower Regulations [Brought in from 7-3-18 (H)]
 - (H) Short-Term Rental Regulations [Brought in from 7-3-18 (I)]
 - (I) Marijuana [Brought in from 7-3-18 (J)]
 - (J) Manufactured Homes [Brought in from 7-3-18 (K)]
 - (K) Employee Housing [Brought in from 7-3-18 (L)]
 - (L) Parking Standards [Brought in from 7-3-15]
 - (M) Fence, Hedge, and Wall Regulations [Brought in from 6-4-1]
 - (N) Outdoor Lighting Regulations [Brought in from Chapter 6, Section 5]
- 7-4-6 SIGN REGULATIONS [Brought in from 7-3-17]
- 7-4-7 LANDSCAPE REGULATIONS [Brought in from Chapter 7, Section 7]
- 7-4-8 RESIDENTIAL DESIGN STANDARDS [Brought in from Chapter 6, Section 6]
- 7-4-9 REGULATIONS FOR MANUFACTURED HOMES, TRAVEL HOMES AND OTHER FACTORY-BUILT HOUSING [All section in existing code but various sections: brought in from Chapter 6, Section 3 and Chapter 8, Section 1]
- 7-4-10 NONCONFORMING USES [Brought in from 7-3-20]

SECTION 5 - SUBDIVISION REGULATIONS

7-5-1 GENERAL PROVISIONS [Brought in from 7-4-1, 7-4-2, and 7-4-3]

7-5-2 SUBDIVISION APPLICATIONS AND REVIEW PROCEDURES [This Section replaces existing 7-4-5 and clarifies the individual subdivision application process steps]

Town of Ridgway November 23, 2022 Page 9 of 13

- (A) Subdivision Application Types and Processes [This Table states each subdivision application type and what the process is the application goes through including public noticing requirements and approving authority]
- (B) General Application Review Procedures [This Section replaces existing 7-4-5 and clarifies the individual application process steps]
 - (1) Pre-Application Meeting
 - (2) Application Submittal Requirements
 - (a) Basic Application Materials
 - (i) Application Form [Includes application form, applicant/agent and owner information requirements]
 - (ii) Fees [Includes application fees and payment of consultant fees]
 - (i) Proof of Ownership
 - (ii) Legal Description
 - (iii) Adjacent Property Owners
 - (iv) Mineral Interest Owners
 - (v) Vicinity Map
 - (vi) General Written Narrative
 - (3) Completeness Review [Within 10 days, review for completeness]
 - (4) Referral Agencies [Brought in from 7-4-5]
 - (5) Staff Report
 - (6) Notice Requirements [Includes 15 day publication in paper, 7 day mailing to adjacent owners, 30 day mineral estates notice]
 - (7) Public Hearings
 - (8) Post Approval [Includes submitting final documents, Improvements Agreement, Recordation of documents, and public sale of lots]
- (C) Major Subdivision [Pulls information from 7-4-5 and adds new information for further clarification. Three stages of subdivision process remain in this section (Sketch Plan, Preliminary Plat, Final Plat)]
 - (1) General Provisions
 - (2) Review Procedures
 - (a) Sketch Plan Review
 - (i) Review Flowchart
 - (ii) Pre-Application meeting
 - (iii) Application submittal requirements
 - (iv) Completeness review
 - (v) Evaluation by Staff and Referral Agencies
 - (vi) Staff Report
 - (vii) Review and Recommendation by Planning Commission

Town of Ridgway November 23, 2022 Page 10 of 13

- (viii) Review and Action by Town Council
- (b) Preliminary Plat
 - (i) Review Flowchart
 - (ii) Pre-Application meeting
 - (iii) Application submittal requirements
 - (iv) Completeness review
 - (v) Evaluation by Staff and Referral Agencies
 - (vi) Staff Report
 - (vii) Review and Recommendation by Planning Commission
 - (viii) Review and Action by Town Council
- (c) Final Plat
 - (i) Review Flowchart
 - (ii) Pre-Application meeting
 - (iii) Application submittal requirements
 - (iv) Completeness review
 - (v) Evaluation by Staff and Referral Agencies
 - (vi) Staff Report
 - (vii) Review and Recommendation by Planning Commission
 - (viii) Review and Action by Town Council
 - (ix) Post Approval
- (3) Approval Criteria
- (D) Minor Subdivision [Pulls from 7-4-8 and added some new sub-application types]
 - (1) Applicability
 - (2) Procedures
- (E) Plat Amendments [Pulls information from 7-4-10 and adds new information]
 - (1) Applicability
 - (2) Procedures
- (F) Lot Splits [Brought in from 7-4-9]
 - (1) Applicability
 - (2) Procedures
- (G) Boundary of Lot Line Adjustment. [New Section]
 - (1) Applicability
 - (2) Procedures
- (H) Townhomes [New Section]

Town of Ridgway November 23, 2022 Page 11 of 13

- (1) Applicability
- (2) Procedures
- (I) Building Footprint [New Section]
 - (1) Applicability
 - (2) Procedures
- (J) Condominiumization [New Section]
 - (1) Applicability
 - (2) Procedures
- (K) Exempt Division of Land [New Section]
 - (1) Applicability
 - (2) Procedures
- (L) Lot Consolidation [New Section]
 - (1) Applicability
 - (2) Procedures
- (M) Replat [New Section]
 - (1) Applicability
 - (2) Procedures
- (N) Right-of-Way Vacation [New Section]
 - (1) Applicability
 - (2) Procedures
- 7-5-3 SUBDIVISION REQUIRED IMPROVEMENTS [Brought in from 7-4-6]
- 7-5-4 DESIGN STANDARDS [Brought in from 7-4-7]

SECTION 6 – PLANNED UNIT DEVELOPMENT (PUD) [Brought in from 7-3-16 and inserted additional information for process outline]

- 7-6-1 GENERAL PUD REVIEW PROCEDURES
 - (A) Authorization
 - (B) General Provisions [Brought in from 7-3-16]
 - (C) Intent
 - (D) Application
 - (E) Eligibility
 - (F) Permitted Uses
 - (G) Coordination with Subdivision and Zoning Regulations
 - (H) Modification of Requirements
- 7-6-2 PUD STANDARDS

Town of Ridgway November 23, 2022 Page 12 of 13

- (A) General Provisions
- (B) Affordable Housing
- (C) Installation of Electric Vehicle Spaces
- 7-6-3 GENERAL PUD REVIEW PROCEDURES
 - (A) Table of PUD Application Types and Processes
 - (B) Pre-Application Meeting
 - (C) Application Submittal Requirements
 - (D) Completeness Review
 - (E) Referral Agencies
 - (F) Staff Report
 - (G) Notice Requirements
 - (H) Public Hearings
 - (I) Post Approval
- 7-6-4 PUD ZONING [New application type]
 - (A) General Provisions
 - (B) Review Procedures
 - (C) Approval Criteria
- 7-6-5 MAJOR PUD AMENDMENT[New application type]
 - (A) General Provisions
 - (B) Review Procedures
 - (C) Approval Criteria [Refers back to original PUD approval criteria as currently exist]
- 7-6-6 MINOR PUD AMENDMENT [New application type]
 - (A) General Provisions
 - (B) Review Procedures
 - (C) Approval Criteria

SECTION 7 – ANNEXATIONS [New Section]

- 7-7-1 Application of Municipal Code
- 7-7-2 Purpose
- 7-7-3 Statement of Policy and Review Criteria
- 7-7-4 Responsibilities of Applicant
- 7-7-5 Annexation Procedures
 - (A) Eligibility
 - (B) Annexation Process Summary
 - (C) Pre-Application Meeting

Town of Ridgway November 23, 2022 Page 13 of 13

- (D) Application and Petition Submittal Requirements
- (E) Completeness Review
- (F) Substantial Compliance
- (G) Evaluation and Review of Application and Petition
- (H) Notice of Public Hearing
- (I) Planning Commission Review
- (J) Town Council
- (K) Post Approval

SECTION 8 – DEFINITIONS [Consolidates all definitions currently under 6-3-1, 7-3-2, and 7-4-4]



Community Planning Strategies

CHAPTER 7 CONCEPTUAL DRAFT

NOVEMBER 29, 2022



Objective of Tonight's Discussion

- Review approach to making updates
- Review Chapter 7 layout
- Policy Changes
- Questions/Discussion





Approach to updates

Established Section Titles:

- General Procedures
- Planning Commission
- Board of Adjustment
- Zoning Regulations
- Subdivision Regulations
- Planned Unit Development
- Annexation



Approach to updates

- Within each Section, ensured there are:
 - Regulations
 - Review procedures
 - Approval criteria
- Information from existing Code was brought into relevant sections and subsections
- Found gaps where further detail needed, and inserted new language to ensure Chapter 7 reads clearly



Supplemental Regulations

- Home Occupations
- Offensive Businesses
- Use and Location of Travel Homes
- Garage and Yard Sales
- Bed and Breakfast Operations
- Accessory Dwelling Units
- Telecommunication Antenna and Tower Regulations
- Short-Term Rental Regulations
- Marijuana
- Manufactured Homes

- Employee Housing
- Parking Standards
- Fence, Hedge, and Wall Regulations
- Sign Regulations
- Landscape Regulations
- Residential Design Standards
- Regulations for Manufactured Homes, Travel Homes, and other Factory-built Housing
- Non-Conforming Uses



Proposed Restructure

General Review Procedures

- Pre-Application meeting with Staff
- Application submittal requirements
- Completeness review period
- Referral Agencies' review period
- Staff Report requirements
- Public Notice Requirements
- Public Hearing(s)
- Post Approval



Zoning Application Types and Processes Table

	Pre- Application Meeting (§7-4-XX)	Completenes s Review (§7-4-XX)	Referrals (§7-4-XX)	Notice of Hearing (§7-4-XX)	Town Manager or their designee	Planning Commission (§7-4-XX)	Town Council (§7-4-XX)	BOA (§7-4-XX)
R=Required; O=Option	al; PH=Required	Public Hearing	Rec=Reco	mmendation;	D=Decision			
Map Amendment (§7-4-X)	0	R	R	R Posting	Rec	R PH / Rec	R PH / D	
Text Amendment (§7-4-X)	0	R	R	R Publication	Rec	R Rec	R PH / D	
Conditional Use Permit (§7-4-X)	0	R	R	R Posting	Rec	R PH / D		
Minor Amendment to Conditional Use Permit (§7-4-X)	0	R	0		Rec	R D		
Temporary Use Permit (§7-4-XX)	0	R	0		Rec	R D		
Site Plan (§7-4-XX)	0	R	0		Rec	R D		
Administrative Adjustment (§7-4-XX)	0	R	0		D			
Variance (§7-4-XX)	0	R	R	R Posting	Rec	R PH / D		
Appeal (§7-4-XX)	0	R	О	R Posting	Rec			R PH / D

Zoning Applications

NEW ZONING APPLICATION TYPES

- Administrative Adjustments
- Minor Amendment to CUP
 - Site Plan

Administrative Adjustment: may be requested by an applicant to adjust any dimensional standard set forth in Chapter 4, Zoning Regulations, by no more than ten (10) percent of the required dimensional standard.

Minor Amendment to CUP: do not alter the basic intent and character of the approved conditional use and are deemed necessary in light of technical or engineering considerations not first discovered during actual construction; or could not have been reasonably anticipated during the initial review process.

Site Plan

Purpose:

To ensure that nonresidential and multifamily uses comply with access, parking, setbacks, signage, and other site design standards as required by the Ridgway Municipal Code.

Project requiring Site Plan Approval:

- All new uses and structures which are not exempted in Section X-XX;
- Any modification of an existing use, structure, or site where, in the opinion of the Town Manager or designee, significant changes to the use, structure, or site are proposed; or
- Any modification of an existing structure where the exemption limits set forth in Section X.XX are exceeded.

Projects Exempt from Site Plan Approval:

- Single-family attached or detached dwellings; or
- Any proposed modification of an existing structure where less than twenty (20) percent of gross floor footage of the existing structure is being modified, provided that the modification does not exceed one thousand (1,000) gross square feet.

Land Uses and Dimensional Requirements

Land Use Table: Identifies each use within existing RMC and uses allowed by right or conditionally allowed.

*Administrative Approvals may be added if Town chooses

Use Category		R	HR	MR	FD	HB	DS	GC	I-1	I-2
R – Allow	ed by Right A – Administrative Approval Requi	ed (C – Co	onditic	nal U	se Pe	rmit R	Require	ed	
Agricultural Uses	Agriculture				R					
	Feed Storage and Sales							С		
Animal Services	Veterinary Clinic							С		R
	Kennel, Boarding Facility		5							R
Childcare Facilities	Day Care Facility	С	С	С			С	С		
Community and	Libraries					R		R		
Cultural Facilities	Museums					R		R		
	Community Center		С			R	С	R		
	Churches	С	С			R	С	R		

Zone District Dimensional Standards: Copied from existing RMC and located into a new table.

* Footnotes may be reconfigured into relevant sections of Code...Thoughts?

Zone Districts

- Each Zone District broken down into:
 - Intent
 - District Standards
 - Performance Standards
- Performance Standards: Example: DS, Downtown Service District (Chapter 7, Section 4, pages 30-31)
 - CPS requesting to redistribute through other sections of Code so information is not removed, but it is relocated to relevant sections of Code.
 - For example, parking requirements would be within the Parking Standards, not the performance standards within the DS District





Proposed Major Subdivision Process





Subdivision Application Types

	Pre- Application Meeting (§X.XX)	Completeness Review (§X.XX)	Referrals (§X.XX)	Notice of Hearing (§X.XX)	Town Manager or their designee	Planning Commission (§X.XX)	Town Council (§X.XX)
)=Optional; Pl	H=Required Pub	lic Hearing;	Rec=Recom	mendation; D=	=Decision	1
Minor Subdivision Plat (§7-5-XX)	R	R	R	R Posting	Rec	R PH / Rec	R PH / D
		Major S	ubdivision ((Section 7-5-)	(X)		
Sketch Plan (§7-5-XX)	R	R	R	R Posting		R PH / D	
Preliminary Plat (§7-5-XX)	R	R	R	R Posting	Rec	R PH / Rec	R PH / D
Final Plat (§7-5-XX)	0	R	R	R Posting	Rec	R PH / Rec	R PH / D
			Resubdiv	risions			
Plat Amendments (§7-5-XX)	R	R	R	R Posting	Rec	R PH / Rec	R PH / D
Lot Splits (§7-5-XX)	R	R	R	R Posting	Rec	R PH / Rec	R PH / D
Boundary or Lot Line Adjustment (§7-5-XX)	ο	R	R	R Posting	Rec	R PH / D	
Townhome (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Building Footprint (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Condominium (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Exempt Division of Land (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Lot Consolidation (§7-5-XX)	о	R	R	R Posting	Rec	R PH / D	
Replat (§7-5-XX)	0	R	R	R Posting	Rec		R PH / D
Right-of-Way Vacation (§7-5-XX)	0	R	R	R Posting	Rec		R PH / D

Planned Unit Development (PUD)

- PUD process should be looked at similarly to a rezoning.
 - An applicant would be required to also subdivide if they are intending to sell any property within the PUD
- PUD Standards added include:
 - Affordable Housing
 - Installation of EV Spaces

PUD Process:

	Pre- Application Meeting	Completeness Review	Referrals	Notice of Hearing	Planning Commission	Town Coun cil	Recording				
R= Required; O-Optional; PH=Public Hearing; Rec = Recommendation; D= Decision											
PUD Zoning	R	R	R	R Posting	R PH/Rec	R PH/D	R				
Major PUD Amendment	R	R	R	R Posting	R PH/Rec	R PH/D	R				
Minor PUD Amendment	0	R		0	R PH/Rec	R PH/D	R				

Planned Unit Development (PUD)

Continued

Major PUD Amendment:

- Major PUD amendments include any modification or amendment to an approved PUD development plan or development guide which:
 - Modifies the approved phasing plan;
 - Modifies a use or density established by the PUD; or
 - Removes or substantially modifies any standard or plan provision.

Minor PUD Amendment:

 Minor PUD amendments include any modification or amendment to an approved PUD development plan or development guide which does not constitute a major PUD amendment as defined in Section XXX, General Provisions.

Annexation

- New Section added, partially in response to questions that arose with the Preserve PUD
 - Resolution finding substantial compliance
 - Annexation Impact Report
 - Ordinance
 - Initial Zoning
 - Annexation Agreement

Timeline

Tentative Project Schedule

- ✓ Refine scope *September 22, 2022*
- ✓ Restructure and update October / November
- Draft updates to PC November 29th
- Refine updates December 2022
 * Submit to CPS prior to December 16, 2022
- Applicant/Developer Open House January 2023
- PC hearing January 2023
- TC hearing February 2023

Updates

- Continue internal discussions
- Refine updates (*December 2022*)

Please submit questions/comments to CPS by end of business day December 16, 2022

Thank you!!

Questions / Discussion

TJ Dlubac, AICP TDlubac@PlanStrategize.com Katie Kent KKent@PlanStrategize.com



Chapter 7: Land Development Regulations

SECTION 1 – GENERAL PROVISIONS

7-1-1 INTERPRETATION OF THE PROVISIONS OF THESE LAND DEVELOPMENT REGULATIONS [New language]

- (A) The provisions of these Land Development Regulations shall be regarded as the minimum requirements for the protection of the public health, safety, and general welfare.
- (B) These Land Development Regulations shall be interpreted in a manner to further its underlying purposes.
- (C) If a conflict occurs between provisions of these Land Development Regulations, or between provisions of these Land Development Regulations and a state statute or other applicable codes and regulations, the more restrictive provision controls unless otherwise specified these Land Development Regulations, or preempted by a direct conflict with state statute.
- (D) Unless otherwise specified in these Land Development Regulations, the requirements of these Land Development Regulations are presumed to apply to actions related to a change in land use as defined herein.

7-1-2 RULES OF CONSTRUCTION OF LANGUAGE [New language]

- (A) Words and phrases shall be read in context and construed according to common usage. Words and phrases that have acquired a technical or particular meaning, by legislative definition or otherwise, shall be construed accordingly.
- (B) The particular controls the general.
- (C) The word "shall" is always mandatory.
- (D) The words "may" and "should" are permissive.
- (E) Unless the context clearly indicates otherwise, words used in the singular number include the plural and words used in the plural number include the singular.
- (F) If there is a conflict between figures and words expressing a number, the words govern.
- (G) The phrase "used for" includes "arranged for," "designed for," "intended for," "maintained for," and "occupied for."

7-1-3 COMPUTATION OF TIME [New language]

- (A) In computing a period of days, the first day is excluded and the last day is included unless the last day of any period is a Saturday, Sunday or legal holiday, in which case the last day shall be the next working day.
- (B) Unless otherwise specified in these Land Development Regulations, the term "days" shall refer to calendar days.

7-1-4 STATUTORY VESTED PROPERTY RIGHTS [Brought in from Ch. 7, Sec. 5]

(A) Purpose.

The purpose of this Section is to provide procedures necessary to implement a program of legislated vested rights similar, but not necessarily identical, to that called for by the provisions of Article 68 of Title 24, C.R.S. The provisions of said Article 24-68, to the extent inconsistent with the provisions of this Chapter, including but not necessarily limited to the provisions of C.R.S. 24-68-102.5(1), are hereby superseded.

- (B) General Provisions.
 - (1) As used in this Section, "Site-Specific Development Plan" means a plan approved by the Town pursuant to this Section which has been submitted to the Town by a landowner or his representative describing with reasonable certainty the type and intensity of use for a specific parcel or parcels of property. Such plan may consist of one or more of the following:
 - (2) An approved Final Planned Unit Development Plan;
 - (3) An approved Subdivision Final Plat;
 - (4) An approved Conditional Use;
 - (5) An approved change in a nonconforming use; or
 - (6) Annexation Agreements or Development Agreements executed by the Town which specifically provide that they should be part of a Site-Specific Development Plan.
 - (7) Neither a Sketch Plan, a Preliminary Subdivision Plat nor a Preliminary PUD Plan may qualify as a Site-Specific Development Plan. An approved Zoning Variance, final architectural plans, public utility filings, or final construction drawings and related documents and methods for construction of improvements shall not, in and of itself constitute a Site-Specific Development Plan although it may be an additional element of a Site-Specific Development Plan which is specified in paragraph (1) above.
 - (8) A Site-Specific Development Plan for any development shall include all of the items identified in paragraphs (1) and (2), above, to the extent applicable to the development.
 - (9) None of the items identified in paragraphs (1) and (2) shall be considered a Site-Specific Development Plan until approved, pursuant to the procedures of this Section in addition to the procedures applicable to such individual items. Such procedures may be pursued contemporaneously.
- (C) Procedures
 - (1) A landowner desiring approval of a Site-Specific Development Plan shall submit an application therefore on forms provided by the Town indicating each element of such plan and shall submit a copy of each element as approved by the Town together with any other information necessary to determine with reasonable certainty the type and intensity of use for the property.
 - (2) Upon receipt of a properly completed application with fee, the Town shall schedule a public hearing and publish notice thereof.
 - (3) Following the Hearing, the Town Council may approve the Site-Specific Development Plan if it is consistent with the requirements of this Section.

- (4) Following approval, the Town shall cause a Notice describing generally the type and intensity of the use approved, and the description of the property affected. Such notice shall not be published more than 14 days after approval.
- (5) The Site-Specific Development Plan shall be deemed approved upon the effective date of the Town Council's action. In the event amendments to any of the elements of the Site-Specific Development Plan are subsequently proposed and approved, the effective date of such amendments for purposes of the duration of vested property rights shall be the date of approval of the original Site-Specific Development Plan.
- (D) Limitations.
 - Approval of a Site-Specific Development Plan pursuant to this Chapter shall be deemed to create a vested property right which shall be subject to the provisions and limitations of 24-68-103(1)(b) and (c), 104 and 105, C.R.S., except inconsistent with any provision of this Chapter.
 - (2) Failure of any landowner to request a hearing and approval of various elements of the development plan as a Site-Specific Development Plan shall constitute a waiver and no vested right shall be deemed to have been created by the Town's approval of such elements.
 - (3) Approval of a Site-Specific Development Plan may be revoked by the Board of Trustees following notice and hearing on account of breach of any condition of approval of the various elements of the plan or any ordinance or regulations of the Town applicable to the various approvals or the various elements of the plan.
 - (4) The provisions of all duly adopted zoning ordinances and other land use and development ordinances and regulations and master plans, as amended from time to time, shall apply in accordance with their terms, to all property and pending applications and proceedings except to the extent otherwise specifically provided in the adopting legislation, and except to the extent otherwise provided for an approved Site-Specific Development Plan pursuant to paragraph (A) above.

7-1-5 ADEQUATE PUBLIC WATER SUPPLY [Brought in from Ch. 7, Sec. 6]

(A) Purpose

The purpose of this Section is to provide procedures necessary to implement a program to insure adequate public water supplies similar, but not necessarily identical, to that called for by the provisions of Part 3 of Article 20 of Title 31, C.R.S. The provisions of said C.R.S. 31-20-301 et seq., to the extent inconsistent with the provisions of this Section, are hereby superseded.

(B) General Provisions

As used in this Section, "Development Permit" means any preliminary or final approval of an application for rezoning, conditional use permit, subdivision, PUD, building permit, site plan, development plan or similar application for new construction; which includes new water use in an amount more than that used by 50 single-family equivalents.

(C) Procedures

(1) Unless the Town has authorized use of a water supply other than that of the Town, in a preannexation agreement or by other official action of the Town, a landowner desiring approval of a Development Permit shall submit with the application a report complying with C.R.S. 29-20-304(1) with respect to the Town's water supply, until such time as the Town has adopted a water supply plan conforming with C.R.S. 29-20-304(3).

- (2) If the Town has previously authorized Tri County Water Conservation District water or other source of supply, the applicant shall submit, the report, letter, or plan complying with C.R.S. 29-20-304(1). The Town shall have no obligation to approve any source of supply other than that of the Town.
- (3) No development permit shall be approved until the Town has determined in its sole discretion that the documents required by subsections (1) and (2) have been properly submitted and that the water supply for the proposed development, as such may been modified, will be adequate to meet its water supply requirements.

(D) Applicability

The provisions of this Section 7-1-6 shall apply to all new and pending applications for a development permit submitted after May 29, 2008, except for pending subdivisions or PUDs with an unexpired and approved preliminary plat, unless materially changed to increase water supply requirements. The determination of the adequacy of water supply for subdivisions or PUDs shall be made at the sketch plan stage unless material changes occur after sketch plan approval, in which case the determinations shall be made at the next stage of review and approval. The determination for other applications shall be made prior to approval of the application.

7-1-6 FEES AND COSTS [Brought in from Sec. 7-4-12, but removed specific fee amounts]

(A) Application Fees.

- (1) Any application must be accompanied by the appropriate fees. A schedule of fees is available through the Town of Ridgway.
- (2) The Town Council, in its sole discretion, may defer, reduce and/or waive certain land use fees within this Chapter 7 for projects demonstrating significant public benefit such as perpetual, deed-restricted affordable or workforce housing projects.

(B) Reimbursement of Costs

In addition to the application fees, the applicant shall reimburse the Town for all out-of-pocket costs incurred during the review including legal fees, postage, notice and publishing costs, map costs, engineering fees, etc., together with wages and associated payroll costs for contract employees, plus ten percent to cover overhead and administration. The Town shall bill the applicant periodically as such costs are incurred. Payment is due within 30 days. Bills not paid by the due date shall accrue interest at the rate of one and one-half percent per month or part thereof. No plat shall be recorded, improvement accepted, lien released, building permit issued, tap approved or other final approval action taken until all fees then due are paid to the Town. Such fees may be certified to the County Treasurer for collection as delinquent charges against the property concerned.

7-1-7 ENFORCEMENT AND ADMINISTRATION [Brought in from Sec. 7-4-24]

- (A) The Building Official shall be responsible for the interpretation, administration and enforcement of the provisions of these Regulations, as amended, the Official Zoning Map, as amended, and of any decisions entered by the Planning Commission, Board of Adjustment or Town Council, pursuant to this Section.
- (B) No building permit, occupancy permit, or other permit or license shall be issued, nor shall any other action of approval be taken or allowed by the Town for any property which is not in

compliance with the provisions of these Zoning Regulations, and any decision issued pursuant hereto.

- (C) Whenever necessary to make an inspection to enforce any of the provisions of these Zoning Regulations, or any provision of a decision entered, pursuant to this Section, or whenever there is reasonable cause to believe that a violation of any provision of these Zoning Regulations, or of any decision issued, pursuant to this Section exists, the Marshal, Building Inspector, or their authorized representative, shall have the right to enter upon such building or premises at all reasonable times for purposes of inspection or to perform any other duty imposed by this Section. Prior to entry, he shall identify himself and request permission to enter from the occupant or person in charge of the premises if they can be found by reasonable efforts. If entry is refused, he shall have recourse to any remedy provided by law to secure entry.
- (D) The Town may maintain an action in a court of competent jurisdiction to enjoin any violation of these Zoning Regulations or of the terms of any decision entered pursuant to this Section.
- (E) Any action which reduces the area of any site, lot or tract in violation of the minimum dimensional requirements of these regulations shall be unlawful.
- (F) It shall be unlawful to violate any of the provisions of these Zoning Regulations, or the terms of any decision entered pursuant to this Section. Any person convicted of such a violation may be punished by a fine of up to \$300.00. Each day any violation continues shall constitute a separate violation.
- (G) Continuing Violations of this Section, the terms of any decision issued pursuant to this Section, or any subdivision plat restrictions, are hereby declared to be a nuisance and may be abated in any lawful manner.

SECTION 2 - PLANNING COMMISSION

7-2-1 ESTABLISHMENT [Same as existing 7-1-1]

- (A) The Ridgway Planning Commission is hereby created to consist of seven members. Five members shall be appointed by the Mayor to serve six-year terms, which will expire at one-year intervals. The Mayor and one member of the Town Council, appointed by the Mayor, shall be ex-officio members, and shall serve for the period of their incumbency. Any vacancy shall be filled by the Mayor for remaining term.
- (B) All members shall be qualified electors of the Town.
- (C) The Mayor may appoint an alternate who may serve and vote in the absence of any of the regular members. Such alternate shall serve a two-year term ending on December 31st of the odd-numbered years.

7-2-2 BY-LAWS AND RULES OF PROCEDURE [Same as existing 7-1-2]

The Planning Commission may adopt By-Laws and Rules of Procedure as necessary for the conduct of business not in conflict with this Section or State law.

7-2-3 POWERS AND DUTIES [Same as existing 7-1-3]

The Planning Commission shall have the following powers and duties:

- (A) To discharge duties specified for a Planning Commission or Zoning Commission in any Town ordinance or Town Code.
- (B) To make recommendations to the Town Council upon referral or otherwise concerning matters related to planning, zoning and land use regulation.
- (C) To make recommendations for the adoption of, or amendments to, a master plan.

7-2-4 REMOVAL OF MEMBERS [Same as existing 7-1-4]

Members may be removed for malfeasance in office by the Mayor. If any member, other than the Mayor, misses any more than five meetings in any calendar year, they shall be automatically removed and a replacement appointed by the Mayor.

SECTION 3 - BOARD OF ADJUSTMENT

7-3-1 CREATION [Same as existing 7-2-1]

- (A) The Board of Adjustment is hereby created to consist of seven members. Five members shall be appointed by the Mayor to serve six-year terms, expiring at two-year intervals. The Mayor and one member of the Town Council appointed by the Mayor shall be ex officio members and shall serve for the period of their incumbency. Any vacancy shall be filled by the Mayor for the remaining terms.
- (B) All members shall be qualified electors of the Town.
- (C) The members of the Board of Adjustment and Planning Commission may be the same.
- (D) The Mayor may appoint an alternate who may serve and vote in the absence of any of the regular members. Such alternate shall serve a two-year term ending on December 31st of the odd-numbered years.

7-3-2 BY-LAWS AND RULES OF PROCEDURE [Same as existing 7-2-2]

The Board of Adjustment may adopt By-Laws and Rules of Procedure, as necessary, for the conduct of its business not in conflict with this Section, other ordinances of the Town or State law.

7-3-3 POWERS AND DUTIES [Same as existing 7-2-3]

The Board of Adjustment shall discharge duties as specified for a Board of Adjustment in the Town Zoning Regulations, other Town ordinances and State law.

7-3-4 REMOVAL OF MEMBERS [Same as existing 7-2-4]

Members may be removed for malfeasance in office by the Mayor. If any member, other than the Mayor, misses any more than five meetings in any calendar year, they shall be automatically removed, and a replacement appointed by the Mayor.

Chapter 7: Land Development Regulations

SECTION 4 – ZONING REGULATIONS

7-4-1 – GENERAL PROVISIONS

- (A) This Section, as amended from time to time, together with the Official Zoning Map as adopted and amended from time to time, may be cited as the Town's Zoning Regulations .
- (B) The purpose of these Zoning Regulations is to promote the public health, safety and welfare.
- (C) Whenever there is any conflict between these Zoning Regulations and any other ordinance, code provision, regulation, or law, the more restrictive or higher standard shall apply.
- (D) These Zoning Regulations and the Official Zoning Map shall constitute a part of the Town's Comprehensive Master Plan. These Zoning Regulations are enforceable in accordance with Subsection 7-1-XX, Administration and Enforcement. However, the Master Plan is advisory in nature.
- (E) This Section lays out the application types, requirements, and review procedures for requests associated with zoning changes and land use approvals within the Town of Ridgway. These common review procedures provide the foundation for specific review and approval procedures. See those specific sections to determine which of these common review procedures apply to individual applications for development review.
- (F) Multiple Applications
 - (1) Concurrent Review Permitted. Where multiple applications concern the same property, the Town Manager or their designee, may permit concurrent review of applications for efficiency and practicality.
- (G) Continued Work on Application. Applicants shall continuously and diligently pursue their application(s). An applicant who fails to respond to staff comments or requests for a period of four (4) months shall be administratively withdrawn by the Town Manager or their designee. An applicant may request, in writing, an extension to the Town Manager or their designee. The Town Manager or their designee may allow such extension if it is determined that good cause exists to extend the application time frame.

7-4-2 - ZONING MAP

- (A) The 1993 Revised Zoning Map of the Town, as such may be amended from time to time, may be known or cited as the "Official Zoning Map" of the Town.
- (B) Amendments to the Official Zoning Map may be made by an ordinance enacting a revised map or by an ordinance amending portions of the Official Zoning Map by specifying the legal description of the property to be rezoned. A copy of the Official Zoning Map, as amended from time to time, shall be maintained in the Town Clerk's office available for public inspection. Periodically, copies of the Official Zoning Map, as amended, may be reproduced and made available to the public.
- (C) The regulations for the various districts provided for in this Section shall apply within the boundaries of each such district as indicated on the Official Zoning Map. The district boundaries, as shown on the Official Zoning Map, shall be construed to follow the center lines of streets, to follow platted lot lines or the lines of undivided parcels of property, or to follow the Town limits, whenever a

boundary is shown as approximately in the vicinity of such lines. Distances may be determined by the scale of the map.

7-4-3 – ZONING APPLICATIONS AND REVIEW PROCEDURES

This Section outlines the review procedures that are common to all applications regulated within Section 3, Zoning Application and Review Procedures, unless otherwise stated in this Chapter. Table XXX identifies the various application types and associated review procedures regulated by the Zoning Regulations. The submittal requirements, review procedures, and approval criteria for each application type are laid out in subsequent sections of this Chapter as identified in Table XXX. All documents and materials identified in this Section, and the particular application type section shall be required.

	Pre- Application Meeting (§7-4-XX)	Completenes s Review (§7-4-XX)	Referrals (§7-4- XX)	Notice of Hearing (§7-4-XX)	Town Manager or their designee	Planning Commission (§7-4-XX)	Town Council (§7-4-XX)	BOA (§7-4- XX)
R=Required; O=C	R=Required; O=Optional; PH=Required Public Hearing;			Rec=Recommendation; D=Decision				
Rezoning (§7-4-X)	Ο	R	R	R Posting	Rec	R PH / Rec	R PH / D	
Text Amendment (§7-4-X)	0	R	R	R Publication	Rec	R Rec	R PH / D	
Conditional Use Permit (§7-4-X)	0	R	R	R Posting	Rec	R PH / D		
Minor Amendment to Conditional Use Permit (§7-4-X)	0	R	0		Rec	R D		
Temporary Use Permit (§7-4-XX)	о	R	0		Rec	R D		
Site Plan (§7-4-XX)	0	R	0		Rec	R D		
Administrative Adjustment (§7-4-XX)	Ο	R	0		D			
Variance (§7-4-XX)	0	R	R	R Posting	Rec	R PH / D		
Appeal (§7-4-XX)	0	R	0	R Posting	Rec			R PH / D

(A) Table XXX - Zoning Application Types and Processes

(B) General Application Review Procedures

The following procedures shall apply to all classifications of development applications which are required under this Chapter.

(1) Pre-Application Meeting

If the applicant or Town Manager or their designee, requests a pre-application meeting, the following process shall be followed:

- (a) Prior to the formal submission of the application, the applicant shall contact the Town Manager or their designee to schedule and request a pre-application meeting. Following receipt of a request, the pre-application meeting should be set for a date within ten (10) business days of the date of the applicant's request. The Town Manager or their designee shall advise the applicant of the date and time of the pre-application meeting.
- (b) The applicant shall be prepared to discuss the proposed application with the Town Manager or their designee. The applicant is encouraged to present such plats, plans, diagrams, or other preliminary information sufficient to allow a conceptual review of the proposed application.
- (c) The purpose of the pre-application meeting is to assist the applicant in understanding the town's application review processes and to allow the Town Manager or their designee to determine the applicable process(es) and regulations for the proposed application.
- (2) Application Submittal Requirements

All of the following information and materials shall be submitted to the Town of Ridgway in a form acceptable to the Town Manager or their designee. Additional information and materials required to be submitted for each specific application type identified in Table XXX are set forth in subsequent sections of this Chapter and shall also be submitted in order to receive a determination of completeness.

(a) Basic Application Materials

The following materials are required for all applications regulated by Chapter 7, Section 4 Zoning Regulations, unless waived by the Town Manager or their designee.

- (i) Application Form. An application form for the request shall be obtained from the Town. Completed application forms and accompanying materials shall be submitted to the Town by the owner or applicant.
 - a. Authorized Agent. If the applicant is not the owner of the land based on Ouray County Assessor records, the applicant shall submit a letter signed by the owner consenting to the submission of the application(s).
 - b. Applicant is Not the Sole Owner. If the applicant is not the sole owner of the land, the applicant shall submit a letter signed by all owners or an association representing all the owners, by which all owners consent to or join in the application.
- (ii) Fees. All application fees shall be in compliance with Section 7-1-6, Fees and Costs.
- (iii) Proof of Ownership. Proof of Ownership in the form of a copy of the property deed or a title commitment which has been issued within sixty (60) days of the application submittal along with copies of all documents listed in the exceptions.
- (iv) Legal Description. Legal description of the property subject to the development application.

- (v) Mineral Interest Owners. List of all mineral interest owners with interests severed from the subject property.
- (vi) Vicinity Map. A map locating the project limits, parcel(s), and property within Ridgway. The vicinity map shall clearly show the boundaries of the subject property and all property within a three-mile radius of the subject property.
- (vii) General Written Narrative. A general written narrative identifying the development team, existing conditions of the property, proposed uses, density, lot layout, end users, financing, public dedications (including rights-of-way, parks, open space, infrastructure), and describing the purpose of the project, how the request meets the applicable approval criteria, furthers the goals and objectives specified in the Master Plan, and identifying any potential impacts on adjacent properties and public infrastructure and how those impacts are proposed to be mitigated.
- (3) Completeness Review

When a completeness determination is required pursuant to Table X-X.X, the following shall apply:

- (a) Within ten (10) days following receipt of an application, the Town Manager or their designee shall administratively review the application and determine whether it includes all the application content requirements of the Ridgway Municipal Code for the requested application type.
- (b) All plans, reports, maps, and other information required for the application type must be complete and legible. A failure of the application to meet the requirements of the Zoning Regulations and this Ridgway Municipal Code may delay the processing of the application until the application is sufficient and deemed complete.
- (c) When the Town Manager or their designee determines that the application is complete as submitted, the Town Manager or their designee shall process the application for review in accordance with the provisions set forth in this Chapter 7, Land Development Regulations.
- (d) In the event the Town Manager or their designee determines that the application is incomplete, the Town Manager or their designee shall inform the applicant in writing of the deficiencies in the application. No further processing of the incomplete application shall be undertaken until the Town Manager, or their designee, determines that the applicant has remedied the application's deficiencies.
- (4) Referral Agencies

In accordance with Table X-X.X, applications shall be referred to any of the below referral agencies the Town Manager or their designee determines is necessary to the complete and comprehensive review of the request. Referral of applications to other agencies shall be for a minimum time frame of fourteen (14) days. However, the time frame for review and comment may be extended if the application presents technical issues which require additional review, additional information is provided by the applicant, or the application is modified. Referral agencies include, but are not limited to, the following:

- (a) Bureau of Land Management (BLM)
- (b) Colorado Department of Transportation (CDOT)
- (c) Colorado Division of Reclamation, Mining & Safety
- (d) Colorado Division of Water Resources
- (e) Colorado Parks and Wildlife

- (f) Colorado State Forest Service
- (g) Ditch companies
- (h) Fire Protection District(s) or department(s)
- (i) Ouray County Departments (Assessor, Clerk & Recorder, Attorney, Health Department, Building Department, Road & Bridge, Sheriff Office, etc.) as appropriate
- (j) Town of Ridgway Departments (Town Clerk, Town Attorney, Engineering Department, Building Department, Public Works Department, Police Department, etc.) as appropriate
- (k) Water Conservation District(s)
- (I) San Miguel Power Authority
- (m) School district(s)
- (n) Soil Conservation District
- (o) Utility service providers and districts
- (p) US Army Corp of Engineers
- (q) US Environmental Protection Agency (EPA)
- (r) US Forest Service
- (s) Xcel Energy / Public Service of Colorado
- (t) Any other entity or agency deemed necessary by the Town Manager or their designee
- (5) Staff Report

The Town Manager or their designee shall review the application to determine if the proposal satisfies the applicable standards. The Town Manager or their designee shall prepare a staff report discussing whether the applicable standards of the Ridgway Municipal Code have been satisfied. The staff report should identify issues raised through staff and referral agency review, potential mitigation requirements, any recommended conditions for approval, and any additional information pertinent to the review of the application.

(6) Notice Requirements

All public notices of hearings required by these Zoning Regulations shall include the date, time, place, and purpose of the hearing, a general description of the property affected, and any other information deemed appropriate to apprise the public of the general nature of the action proposed. Errors or inaccuracies in the notice shall not be deemed sufficient cause to postpone or invalidate a hearing except where such errors are substantive in material and are found to have reasonably mislead or misinformed the public.

(a) Notice by Posting

When notice by posting is required for a public hearing by Table X-X.X, notice of the hearing shall be posted at Town Hall ten (10) days before the hearing and posted, visible from each street frontage abutting the property, for at least ten (10) days prior to the hearing in addition to any other notice required by Town regulations.

(b) Mineral Estates Notice.

Per 24-65.5-103, C.R.S. if the surface estate and mineral estate are severed, the owners of severed mineral estates shall be entitled to notification of not less than thirty (30) days before the date scheduled for the public hearing for the application. A copy of the notice shall be given to the Town along with the applicant's certification of compliance with said

notification requirements. Provided this notice is not required if notice was previously sent and such certification previously provided with respect to the same surface development, or the application is only platting an additional single lot, unless a mineral estate owner has requested notice pursuant to 24-6-402(7), C.R.S.

(7) Public Hearings

When an application requires a public hearing before the Planning Commission, the Town Council, or the Board of Adjustment in accordance with Table X-X.X, the following shall apply:

- (a) The Town shall set the date and time of a public hearing. Notice of the public hearing shall be issued in accordance with Table X-X.X and Section XXX.XX, Notice Requirements.
- (b) At the public hearing, the reviewing body shall review the application for conformance with the applicable review standards and approval criteria for the request.
- (c) Any public hearing or other action of the body may be continued or postponed at any time to a specified date and time in order to permit preparation of additional information for further review by the reviewing body.
- (d) When required, the Planning Commission recommendation shall be forwarded to the Town Council. Following a public hearing, the Town Council shall approve, approve with conditions, or deny the application or continue the matter to a date certain.
- (e) The applicant shall bear the burden of presenting sufficient competent evidence at the public hearing to support the standards for approval set forth by this Ridgway Municipal Code. Any decision by the reviewing body to recommend, or to act to, approve, conditionally approve, or deny an application shall be based upon a consideration of all evidence presented during the public hearing. Where evidence presented is contradictory, the reviewing body shall weigh such evidence and judge the credibility and sufficiency of the evidence prior to rendering a decision.
- (8) Post Approval
 - (a) Review. Prior to recording of the approved documents, the applicant shall submit all final documents reflecting any conditions of approval to the Town Manager or their designee for final review and acknowledgement.
 - (b) Recording. Any documents required to be recorded with the Ouray County Clerk and Recorder shall be fully executed by the applicant and filed for execution by the Town and recorded. Recording of all documents shall be completed within a reasonable period of time from the date of approval by the approving body.
 - (c) Effective Upon Recording. The approval does not become effective until all approved documents have been properly recorded with the Ouray County Clerk and Recorder.

(C) Rezoning

- (1) General Provisions.
 - (a) Amendments to the Official Zoning Map may be made by an ordinance enacting a revised map or by an ordinance amending portions of the Official Zoning Map by specifying the legal description of the property to be rezoned. A copy of the Official Zoning Map, as amended from time to time, shall be maintained in the Town Clerk's office available for public inspection. Periodically, copies of the Official Zoning Map, as amended, may be reproduced and made available to the public.
 - (b) Rezonings may be requested or initiated by the Town, the Planning Commission, or the owner of any legal or equitable interest in the property or his representative. The area

considered for rezoning may be enlarged by the Planning Commission on its own motion over the area requested in the application as part of its recommendation.

- (c) Legislative Zoning: Comprehensive review and reenactment of all or a significant portion of the Official Zoning Map shall be a legislative action and shall not be required to meet any criteria set out in this Subsection.
- (2) Review Procedures.
 - (a) Review Flowchart.

The flowchart depicts the zoning map amendment application review process described in greater detail in this section.

[Insert Flowchart]

(b) Pre-Application Meeting.

A pre-application meeting may be held in accordance with the provisions set forth in Section XXX, Pre-Application Meeting.

(c) Application Submittal Requirements.

The following are the application materials required to be submitted for a rezoning request. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.

- (i) Basic Application Materials. All materials set forth in Section XXX, Basic Application Materials
- (ii) Written Narrative. A written narrative shall be submitted addressing all of the following items and any other pertinent or necessary information.
 - a. A general written narrative describing the purpose of the project;
 - The source and quantity of water required for the proposed use(s) within the project;
 - c. The method of wastewater treatment and anticipated quantity of wastewater generated;
 - d. When water or wastewater service would be provided by a municipality or a water or sanitation district or other public entity, written confirmation that such entity is willing and able to provide such service;
 - e. A description of any natural or man-made hazard within or in the vicinity of the land within the application and a statement describing how the anticipated impact of such hazards would be mitigated if the proposed request requires such mitigation;
 - f. A vicinity map showing to scale the proposed project area in relationship to the surrounding municipal and unincorporated area;
 - g. A description of any unique features, such as historical sites, unique landforms or scenic vistas, contained within the project area;
- (iii) Site Improvement Plan.
 - a. The size of the map shall be of a size that is legible for reasonable review and interpretation, as determined by the Town Manager or designee.

- b. A scale that is one (1) inch equals two hundred (200) feet or another suitable scale if approved by Town Manager or designee;
- c. Legal description of the parcel;
- d. North arrow, scale, and legend;
- e. A vicinity map at a suitable scale;
- f. Outline of the parcel boundary or the portion of the parcel that the application applies to;
- g. The location and name of any streams, ponds, waterways, and irrigation ditches within the property boundaries;
- h. The location and names of all roads and highways abutting the site;
- i. All existing and proposed structures and their dimensions;
- j. The location, dimensions and design of any existing signs on the site;
- k. All utility easements or rights-of-way for telephone, gas, electric, water and sewer lines;
- The location of vehicular drives, entrances, exits, acceleration and deceleration lanes; location and dimensions of pedestrian entrances, exits, walks and walkways;
- m. General location, arrangement and dimensions of parking spaces, aisles, bays and other similar information; and
- n. A notation on the site improvement plan of all existing or potential natural or manmade hazards on or adjacent to the site and a narrative description of an acceptable plan for the mitigation of the impact of such identified hazards.
- (iv) Supplemental Materials. The following items are also required to be submitted to the Town of Ridgway:
 - a. Proof of minimum guaranteed water supply.
- (v) Additional Requirements.
 - a. Any other information deemed necessary by the Town Manager or designee to assist in the review of the application.
- (d) Completeness Review.

The Town Manager or their designee shall review the application for completeness in accordance with the provisions of Section XXX, Completeness Review.

(e) Evaluation by Staff and Referral Agencies.

Upon determination of completeness, the Town Manager or their designee shall refer the application to additional reviewing agencies as set forth in Section XXX, Referral Agencies and review the application for conformance with the requirements and standards of this Chapter.

(f) Staff Report.

A staff report shall be prepared and provided to the reviewing body in accordance with Section XXX, Staff Report.

(g) Review and Recommendation by the Planning Commission.

The Planning Commission shall review the rezoning application in a manner consistent with Table XXX to evaluate compliance with applicable standards. Following its review of the application, the Planning Commission may provide either a recommendation to approve, approve with conditions, or deny the application to the Town Council based on the criteria set forth in Section XXX, Approval Criteria.

- a. The Planning Commission may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to providing a recommendation to the Town Council.
- (h) Review and Action by the Town Council.

The final decision to approve, approve with conditions, or deny a rezoning shall be made by the Town Council in a manner consistent with Table XXX and be based upon the criteria set forth in Section XXX, Approval Criteria.

- a. The Town Council may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Town Council prior to making a final decision.
- (3) Approval Criteria.

Rezonings involving any change in the boundaries of an existing zoning district, or changing the designation of a district, shall be allowed only upon a determination following public hearing that the following criteria are met:

- (a) The amendment is not adverse to the public health, safety and welfare, and
- (b) Either:
 - (i) The amendment is in substantial conformity with the Master Plan; or
 - (ii) The existing zoning is erroneous;
 - (iii) Conditions in the area affected or adjacent areas have changed materially since the area was last zoned.

(D) Text Amendment

(1) General Provisions.

Text amendments are changes to these Land Use Regulations. Such amendments may be submitted, reviewed, and approved pursuant to this section to respond to changed conditions, changes to public policy, or to advance the general welfare of the town. The review process for text amendments shall be reviewed as set forth in Section XXX, Review Procedures. A text amendment may only be initiated by the Planning Commission, Town Council, or the Town Manager or their designee.

- (2) Review Procedures
 - (a) Review Flowchart

The flowchart depicts the text amendment application review process described in greater detail in this section.

[Insert Flowchart]

(b) Staff Report.

A staff report shall be prepared and provided to the reviewing body in accordance with Section XXX, Staff Report.

(c) Review and Recommendation by the Planning Commission.

The Planning Commission shall review the text amendment application in a manner consistent with Table XXX to evaluate compliance with applicable standards. Following its review of the application, the Planning Commission may provide either a recommendation to approve, approve with conditions, or deny the application to the Town Council based on the criteria set forth in Section XXX, Approval Criteria.

- a. The Planning Commission may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to providing a recommendation to the Town Council.
- (d) Review and Action by the Town Council.

The final decision to approve, approve with conditions, or deny a text amendment shall be made by the Town Council in a manner consistent with Table XXX and be based upon the criteria set forth in Section XXX, Approval Criteria.

- a. The Town Council may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Town Council prior to making a final decision.
- (3) Approval Criteria.

The following criteria shall be found to be met by the application and supplemental materials in order for the Planning Commission and/or Town Council to recommend approval or approve a text amendment.

- (a) The text amendment is consistent with the intent of applicable portions of the Master Plan in the reasonable judgement of the approving body; and
- (b) The proposed text amendment is necessary to correct an omission or error in the code;
- (c) The proposed text amendment is necessary to adapt to a change in conditions within the town; or
- (d) Changes in public policy are needed to advance the general welfare of the town.

(E) Conditional Uses

(1) General Provisions

Conditional uses are land uses that have potential for causing adverse impacts on other uses because of such factors as location, method of operation, scale or intensity of activity, or traffic generated. Because of their unusual or special characteristics, conditional uses require review and evaluation so that they may be located properly with respect to their effects on surrounding properties and the Town of Ridgway at large. Conditional uses may be permitted subject to such conditions and limitations as the town may prescribe. The intent is to ensure that the location and operation of the conditional use is in accordance with the development objectives of the town and the Master Plan and will not be detrimental to other uses or properties. All conditional uses shall meet all applicable site development standards as detailed in this Chapter. The review process for conditional uses is set forth in Section XXX, Review Procedures.

- (2) Applicability. Conditional use approval is required for those uses listed as conditional uses in the Land Use Table in Section XXX.
- (3) Concurrent Applications. An application for conditional use approval is required and shall be submitted at the same time as site plan review, if one is necessary.

- (4) Existing permits. Conditional use permits issued prior to the effective date of these Land Development Regulations shall be allowed to continue as long as the use is consistent with the conditions of the permit and the provisions of Section X, Nonconforming Land Uses and Structures and is renewed as required by the conditional use permit. If the conditions of approval are not maintained, it shall be considered a violation of these Land Development Regulations, punishable in a manner set forth in Section X-XX Administration and Enforcement. In addition, the Town may revoke the permit.
- (5) Review and Revocation of a Conditional Use Permit
 - (a) At such intervals as the Planning Commission may have specified in its original decision, or when there is an alleged violation of the provisions of a conditional use permit, the Town Manager or designee shall review the terms, conditions, and other provisions of conditional use permit(s) issued by Planning Commission.
 - (b) Upon review of the permit terms, conditions, and provisions, the Town Manager or designee shall make recommendations to the Planning Commission at its next available meeting to remedy any violations, the reasons for such recommendations, and specific time period(s) in which violations of the provisions of the permit shall be corrected.
 - (c) The Planning Commission may apply any and all remedies and penalties set forth in the Municipal Code to correct violations of a conditional use permit.
 - (d) If the Town Council finds that terms, conditions, and/or provisions of a conditional use permit have been violated, the conditional permit shall be revoked, and such use shall be considered in violation of the Ridgway Municipal Code.
- (6) Review Procedures
 - (a) Review Flowchart. Figure XXX, Conditional Use Permit Flowchart, depicts the conditional use permit application review process described in greater detail in this section.

[Insert Flowchart]

(b) Pre-Application Meeting

A pre-application meeting may be held in accordance with the provisions set forth in Section XXX, Pre-Application Meeting.

(c) Application Submittal Requirements.

The following are the application materials required to be submitted for conditional use requests. The Town Manager may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.

- (i) Basic Application Materials. All items set forth in Section XXX, Basic Application Materials.
- (ii) Written Narrative. A written narrative shall be submitted addressing all of the following items and any other information:
 - a. A general written narrative describing the purpose of the project;
 - Description of the current land use(s) on the property, the characteristics of the land within the property boundaries, and the current land use on all adjoining property;
 - c. A time schedule for construction and/or operation;
 - d. Description of how the use will be operated

- e. How ongoing maintenance of the use and site will be provided;
- f. How the use's impacts on surrounding properties will be minimized and mitigated;
- g. A statement describing how the proposed use would be in compliance with the provisions of the Master Plan;
- h. The proposed sources of water and sanitary sewer; and
- i. A listing of additional local, state and/or federal permits required prior to commencing the proposed land use and notation of which permits have been applied for and which, if any, have been granted.
- (iii) Site Improvement Plan
 - a. The size of the map shall be of a size that is legible for reasonable review and interpretation, as determined by the Town Manager or designee.
 - b. A scale that is one (1) inch equals two hundred (200) feet or another suitable scale if approved by Town Manager or designee;
 - c. Legal description of the parcel;
 - d. North arrow; scale, and legend;
 - e. A vicinity map at a suitable scale;
 - f. Outline of the parcel boundary or the portion of the parcel that the conditional use applies to;
 - g. The location and name of any streams, ponds, waterways and irrigation ditches within the property boundaries;
 - h. Current and proposed grading and drainage patterns including:
 - i. Drainage arrows depicting surface flow;
 - j. Drainage facilities and improvements; and
 - k. A grading plan depicting existing and proposed site contours at two-foot intervals.
 - I. The location and names of all roads and highways abutting the site;
 - m. All existing and proposed structures and their dimensions;
 - n. The location, and dimensions of any existing and proposed signs on the site;
 - o. All utility easements or rights-of-way transmission and/or service lines;
 - p. The location and dimensions of vehicular drives, entrances, exits, acceleration and deceleration lanes; location and dimensions of pedestrian entrances, exits, walks and walkways;
 - q. General location, arrangement and dimensions of parking spaces, width of aisles, width of bays, angle of parking and other similar information;
 - r. A notation on the site improvement plan of all existing or potential natural or manmade hazards on or adjacent to the site and a narrative description of an acceptable plan for the mitigation of the impact of such identified hazards; and

- s. Any other information deemed necessary by the Town Manager or designee to assist in the review of the application.
- (iv) Supplemental Materials. The following items are required to be submitted to the Town of Ridgway:
 - a. Drainage plan or study calculating historic and proposed surface and stormwater flows and how such flows will be managed.
 - 1) Traffic statement or study identifying current and proposed traffic counts and proposed trip generation along with any needed or anticipated improvements to mitigate the projects use on the public transportation network and infrastructure.
 - 2) Proof of minimum guaranteed water supply appropriate for the requested use.
- (v) Additional Requirements

Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.

(d) Completeness Review

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section XXX, Completeness Review.

(e) Evaluation by Staff and Referral Agencies

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section XXX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

(f) Staff Report.

A staff report shall be prepared and provided to the reviewing body in accordance with Section XXX, Staff Report.

(g) Review and Action by the Planning Commission.

The Planning Commission shall review the conditional use application in a manner consistent with Table XXX to evaluate compliance with applicable standards. The final decision to approve, approve with conditions, or deny a conditional use permit shall be made by the Planning Commission in a manner consistent with Table XXX and be based upon the criteria set forth in Section XXX, Approval Criteria.

- a. The Planning Commission may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to making a final decision.
- (7) Approval Criteria.

Uses listed as conditional uses for the various zoning districts provided in this Chapter shall be allowed only if the Planning Commission determines, following review pursuant to Subsection 7-3-XX, that the following criteria are substantially met with respect to the type of use and its dimensions:

(a) The use will not be contrary to the public health, safety, or welfare.

- (b) The use is not materially adverse to the Town's Master Plan.
- (c) Streets, pedestrian facilities, and bikeways in the area are adequate to handle traffic generated by the use with safety and convenience.
- (d) The use is compatible with existing uses in the area and other allowed uses in the District.
- (e) The use will not have an adverse effect upon other property values.
- (f) The location of curb cuts and access to the premises will not create traffic hazards.
- (g) The use will not generate light, noise, odor, vibration, or other effects which would unreasonably interfere with the reasonable enjoyment of other property in the area.
- (h) Visual impact due to a building's size shall be mitigated by means of design, landscaping, berming, and other methods of site treatment, and must be compatible with the mass and scale of existing buildings on adjacent properties, or if there are no such buildings, compatible with the mass and scale of buildings in the Town generally.

(F) Minor Amendment to a Conditional Use Permit

- (1) General Provisions
 - (a) Minor amendments to conditional use permits are those that do not alter the basic intent and character of the approved conditional use and are deemed necessary in light of technical or engineering considerations not first discovered during actual construction; or could not have been reasonably anticipated during the initial review process. Minor amendments shall not include changes in use.
 - (b) Any change not qualifying as a minor amendment shall be processed as a new conditional use request.
 - (c) No conditional use permit may receive more than one (1) minor amendment. For purposes of this subsection, a minor amendment may include multiple amendments consolidated and submitted as one minor amendment to a conditional use permit application. Any additional amendments, minor or otherwise, shall be processed as a new conditional use application pursuant to Section XXX, Conditional Use Permit.
 - (d) The review process for a minor amendment to conditional use permit is set forth in Section XXX, Review Procedures. These minor amendments may include, but are not limited to:
 - (i) Variations to the location of an approved building footprint of not more than five (5) feet;
 - (ii) Minor deviations in the location of infrastructure (roads and utilities);
 - (iii) Pedestrian or vehicular circulation throughout or adjacent to the project;
 - (iv) Changes to the gross floor area of not more than ten (10) percent of the approved square footage;
 - (v) Modifications to include necessary operations to enhance the area or clear the site;
 - (vi) Modification to the day by which the conditional use permit is in operation;
 - (vii)Other minor changes to a conditional use permit as determined by the Town Manager or designee;
- (2) Review Procedures
 - (a) Review Flowchart. Figure XXX, Minor Amendment to a conditional use permit Flowchart, depicts the minor amendment to a conditional use permit application review process described in greater detail in this section.

Figure XXX, Minor Amendment to a Conditional Use Permit Flowchart

[Insert Flowchart]

(b) Pre-Application Meeting

A pre-application meeting may be held in accordance with the provisions set forth in Section XXX, Pre-Application Meeting.

(c) Application Submittal Requirements.

The following are the application materials required to be submitted for minor amendment to conditional use permit requests. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.

- (i) Basic Application Materials. All items set forth in Section XXX, Basic Application Materials.
- (ii) Written Narrative. A written narrative shall be submitted addressing all of the following items and any other information.
 - a. A general narrative of the conditional use permit issued by the town and any conditions or provisions included in such permit;
 - b. A description of the minor amendment being requested and justification and rationale for such request; and
 - c. Any impacts the amendment may have on the use, adjacent properties, and/or public infrastructure.
- (iii) Site Improvement Plan. The site improvement plan shall include all items required for a conditional use set forth in Section XXX, Site Improvement Plan.
- (iv) Supplemental Materials. The supplemental materials shall include all items required for a conditional use set forth in Section XXX, Supplemental Materials.
- (v) Additional Requirements. Any additional information deemed necessary by the Town Manager or designee to assist in the review of the application.
- (d) Completeness Review

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section XXX, Completeness Review.

(e) Evaluation by Staff and Referral Agencies

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section XXX, Referral Agencies and review the application for conformance with the requirements and standards of these Land Use Regulations.

(f) Review and Action by the Planning Commission.

The Planning Commission shall review the minor amendment to a conditional use application in a manner consistent with Table XXX to evaluate compliance with applicable standards. The final decision to approve, approve with conditions, or deny a minor amendment to a conditional use permit shall be made by the Planning Commission in a manner consistent with Table XXX and be based upon the criteria set forth in Section XXX, Approval Criteria.

- (i) The Planning Commission may, in its sole discretion, continue or postpone the meeting to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to making a final decision.
- (3) Approval Criteria

A minor amendment to a conditional use permit may be approved by the Planning Commission if the application is found to meet the approval criteria of a conditional use permit set forth in Section XXX, Approval Criteria.

(G) Temporary Use Permits

(1) General Provisions.

Temporary uses or structures are uses and/or structures that will be used for a specified period of time, is not permanent, or is for a special event or purpose. The review process for a temporary use permit is set forth in Section X.XX, Review Procedures.

(a) The Planning Commission may issue a permit authorizing certain temporary uses of premises in a district for a use which is otherwise not allowed in such a district for the periods specified here below:

Use	Zoning District	Period
Construction office incidental to construction	All districts	9 months
on premises		
Carnival, circus, bazaar, fairs	Commercial	1 week
Tent meetings or crusades	Commercial	2 weeks

- (a) A permit for a period of up to one year may be issued under the following circumstances by the Planning Commission for temporary location or use of a manufactured home or travel home:
 - (i) For fire protection or security purposes in the General Commercial District.
 - (ii) At a construction site during the construction period.
- (2) Review Procedures.
 - (a) Review Flowchart. Figure XXX, Temporary Use Permit Flowchart, depicts the temporary use permit application review process described in greater detail in this section.

Figure XXX, Temporary Use Permit Flowchart

[Insert Flowchart]

- (b) Pre-Application Meeting. A pre-application meeting may be held in accordance with the provisions set forth in Section XXX, Pre-Application Meeting.
- (c) Application Submittal Requirements. The following are the application materials required to be submitted for temporary use requests. The Town Manager may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.
 - (i) Basic Application Materials. All items set forth in Section X-XX, Basic Application Materials.
 - (ii) Written Narrative. A written narrative shall be submitted addressing all of the following items and any other information:
 - a. A general written narrative describing the purpose of the project;

- Description of the current land use(s) on the property, the characteristics of the land within the property boundaries, and the current land use on all adjoining property;
- c. A time schedule for construction and/or operation;
- d. Description of how the use will be operated
- e. How ongoing maintenance of the use and site will be provided;
- f. How the use's impacts on surrounding properties will be minimized and mitigated;
- g. A statement describing how the proposed use would be in compliance with the provisions of the Master Plan;
- h. The proposed sources of water and sanitary sewer; and
- i. A listing of additional local, state and/or federal permits required prior to commencing the proposed land use and notation of which permits have been applied for and which, if any, have been granted.
- (iii) Site Improvement Plan
 - a. The size of the map shall be of a size that is legible for reasonable review and interpretation, as determined by the Town Manager or designee.
 - b. A scale that is one (1) inch equals two hundred (200) feet or another suitable scale if approved by Town Manager or designee;
 - c. Legal description of the parcel;
 - d. North arrow; scale, and legend;
 - e. A vicinity map at a suitable scale;
 - f. Outline of the parcel boundary or the portion of the parcel that the conditional use applies to;
 - g. The location and name of any streams, ponds, waterways and irrigation ditches within the property boundaries;
 - h. Current and proposed grading and drainage patterns including:
 - i. Drainage arrows depicting surface flow;
 - j. Drainage facilities and improvements; and
 - k. A grading plan depicting existing and proposed site contours at two-foot intervals.
 - I. The location and names of all roads and highways abutting the site;
 - m. All existing and proposed structures and their dimensions;
 - n. The location, and dimensions of any existing and proposed signs on the site;
 - o. All utility easements or rights-of-way transmission and/or service lines;
 - p. The location and dimensions of vehicular drives, entrances, exits, acceleration and deceleration lanes; location and dimensions of pedestrian entrances, exits, walks and walkways;
 - q. General location, arrangement and dimensions of parking spaces, width of aisles, width of bays, angle of parking and other similar information;

- r. A notation on the site improvement plan of all existing or potential natural or manmade hazards on or adjacent to the site and a narrative description of an acceptable plan for the mitigation of the impact of such identified hazards; and
- s. Any other information deemed necessary by the Town Manager or designee to assist in the review of the application.
- (iv) Additional Requirements. Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.
- (d) Completeness Review

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section XXX, Completeness Review.

(e) Evaluation by Staff and Referral Agencies

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section XXX, Referral Agencies and review the application for conformance with the requirements and standards of these Land Use Regulations.

(f) Review and Decision by Planning Commission

The Planning Commission shall review the temporary use application to evaluate compliance with applicable standards. Following the review, the Planning Commission may approve, approve with conditions, or deny an application for a temporary use permit based on the criteria set forth in Section X.XX, Approval Criteria.

- (i) The Planning Commission may, in its sole discretion, continue or postpone the meeting to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to making a final decision.
- (3) Approval Criteria. The following criteria shall be met by the application and supplemental materials in order for the Planning Commission or designee to issue a temporary use permit.
 - (a) The owner of the property on which the temporary use, structure or event is proposed consents in writing to the issuance of the permit.
 - (b) Local governmental agencies have the resources to dedicate to the use, structure or event;
 - (c) The use, structure or event is not too intrusive or destructive to the community;
 - (d) The proposed use, structure or event is compatible with surrounding land users and uses;
 - (e) The use, structure or event complies with all requirements imposed by this code; and
 - (f) The use, structure or event complies with all applicable laws and regulations

(H)Site Plan

- (1) General Provisions.
 - (a) The purpose of a site plan is to ensure that nonresidential and multifamily uses comply with access, parking, setbacks, signage, and other site design standards as required by the Ridgway Municipal Code. When site plan review is required, structures shall not be constructed or installed and uses may not begin until a site plan showing the proposed development has been approved in accordance with the procedures and provisions of this section. The review process for site plans is set forth in Section X.XX, Review Procedures.
 - (b) The following projects require site plan approval:

- (i) All new uses and structures which are not exempted in Section X-XX;
- (ii) Any modification of an existing use, structure, or site where, in the opinion of the Town Manager or designee, significant changes to the use, structure, or site are proposed; or
- (iii) Any modification of an existing structure where the exemption limits set forth in Section X.XX are exceeded.
- (c) The following projects are exempt from site plan approval:
 - (i) Single-family attached or detached dwellings; or
 - (ii) Any proposed modification of an existing structure where less than twenty (20) percent of gross floor footage of the existing structure is being modified, provided that the modification does not exceed one thousand (1,000) gross square feet.
- (2) Review Procedures
 - (a) Review Flowchart. Figure XXX, Site Plan Flowchart, depicts the site plan application review process described in greater detail in this section.

Figure XXX, Site Plan Flowchart

[Insert Flowchart]

(b) Pre-Application Meeting

A pre-application meeting may be held in accordance with the provisions set forth in Section XXX, Pre-Application Meeting.

(c) Application Submittal Requirements.

The following are the application materials required to be submitted for site plan requests. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.

- (i) Basic Application Materials. All items set forth in Section X.XX, Basic Application Materials.
- (ii) Written Narrative. A written narrative shall be submitted addressing all of the following items and any other information:
 - a. A general written narrative describing the purpose of the project;
 - b. The proposed vehicular access including ingress, egress, internal circulation, and parking;
 - c. The source and quantity of water required for the proposed use(s) within the area to be developed;
 - d. The method of wastewater treatment and anticipated quantity of wastewater generated;
 - e. When water or wastewater service would be provided by a municipality or a water or sanitation district or other public entity, written confirmation that the public entity in question is willing and able to provide the service in question;
 - f. A description of any natural or man-made hazard within or in the vicinity of the subject parcel and a statement describing how the anticipated impact of such hazards would be mitigated if the proposed development requires such mitigation;

- g. A description of any unique features, such as historical sites, unique landforms or scenic vistas, contained within the subject parcel.
- (iii) Site Improvement Plan
 - a. The size of the map shall be of a size that is legible for reasonable review and interpretation, as determined by the Town Manager or designee.
 - b. A scale that is one (1) inch equals two hundred (200) feet or another suitable scale if approved by Town Manager or designee;
 - c. Legal description of the parcel;
 - d. North arrow; scale, and legend;
 - e. A vicinity map at a suitable scale;
 - f. Outline of the parcel boundary or the portion of the parcel that the conditional use applies to;
 - g. The location and name of any streams, ponds, waterways and irrigation ditches within the property boundaries;
 - h. Current and proposed grading and drainage patterns including:
 - i. Drainage arrows depicting surface flow;
 - ii. Drainage facilities and improvements; and
 - iii. A grading plan depicting existing and proposed site contours at two-foot intervals.
 - i. The location and names of all roads and highways abutting the site;
 - j. All existing and proposed structures and their dimensions;
 - k. The location, and dimensions of any existing and proposed signs on the site;
 - I. All utility easements or rights-of-way transmission and/or service lines;
 - The location and dimensions of vehicular drives, entrances, exits, acceleration and deceleration lanes; location and dimensions of pedestrian entrances, exits, walks and walkways;
 - n. General location, arrangement and dimensions of parking spaces, width of aisles, width of bays, angle of parking and other similar information;
 - o. A notation on the site improvement plan of all existing or potential natural or manmade hazards on or adjacent to the site and a narrative description of an acceptable plan for the mitigation of the impact of such identified hazards; and
 - p. Any other information deemed necessary by the Town Manager or designee to assist in the review of the application.
- (iv) Supplemental Materials. The following items are required to be submitted to the Town of Ridgway:
 - a. Drainage plan or study calculating historic and proposed surface and stormwater flows and how such flows will be managed.
 - b. Traffic statement or study identifying current and proposed traffic counts and proposed trip generation along with any needed or anticipated improvements to mitigate the projects use on the public transportation network and infrastructure.

- c. Proof of minimum guaranteed water supply appropriate for the requested use.
- (v) Additional Requirements

Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.

(d) Completeness Review

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section XXX, Completeness Review.

(e) Evaluation by Staff and Referral Agencies

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section XXX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

(f) Review and Decision by Town Manager

The Town Manager shall review the site plan application to evaluate compliance with applicable standards. Following the review, the Town Manager may approve, approve with conditions, or deny a site plan based on the criteria set forth in Section X.XX, Approval Criteria.

- (i) The decision of the Town Manager or designee may be appealed to the Planning Commission in accordance with Section X.XX, Appeal
- (3) Approval Criteria.

Prior to making a decision on a site plan application, the Town Manager shall consider the following review criteria and find that each criterion has been met or determined to be inapplicable:

- (a) The application complies with all requirements imposed by these Land Development Regulations;
- (b) The application complies with all applicable laws and regulations;
- (c) The proposed use is compatible with surrounding land users and uses; and
- (d) The proposed use does not result in undue traffic congestion or traffic hazards.

(I) Administrative Adjustment

(1) General Provisions.

An administrative adjustment may be requested by an applicant to adjust any dimensional standard set forth in Chapter 4, Zoning Regulations, by no more than ten (10) percent of the required dimensional standard. An administrative adjustment shall be submitted and reviewed in compliance with this Section XXX, Administrative Adjustment.

- (a) The request for an administrative adjustment must be made in writing to Town Manager.
- (b) If an applicant desires over ten (10) percent relief from a dimensional standard set forth in Section 4, Zoning Regulations, the applicant must pursue a variance in accordance with Section X.XX, Variance.
- (2) Review Procedures

(a) Review Flowchart. Figure XXX, Administrative Adjustment Flowchart, depicts the administrative adjustment application review process described in greater detail in this section.

Figure XXX, Administrative Adjustment Flowchart

[Insert Flowchart]

(b) Pre-Application Meeting

A pre-application meeting may be held in accordance with the provisions set forth in Section XXX, Pre-Application Meeting.

(c) Application Submittal Requirements.

The following are the application materials required to be submitted for administrative adjustment requests. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.

- (i) Basic Application Materials. All items set forth in Section X.XX, Basic Application Materials.
- (ii) Written Narrative. A written narrative shall be submitted addressing all of the following items and any other information:
 - a. A general written narrative describing the purpose of the project;
 - b. Explanation of the request(s) and justification for why the standard for which an adjustment is being requested is unable to be met;
 - c. Any efforts the applicant or property owner has made to meet the minimum standards;
 - d. Justification for the request and how the request is the minimum required standard(s); and
 - e. Description of how the request meets each of the criterion set forth in Section X.XX, Approval Criteria.
- (iii) Site Improvement Plan
 - a. All existing, required, and proposed dimensional standards clearly depicting the location and increase of the administrative adjustment request.
 - b. A table identifying the required standard(s) and the numerical value being requested by the administrative adjustment.
- (iv) Additional Requirements
 - a. Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.
- (d) Completeness Review

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section XXX, Completeness Review.

(e) Evaluation by Staff and Referral Agencies

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section XXX, Referral Agencies

and review the application for conformance with the requirements and standards of this Municipal Code.

(f) Review and Decision by Town Manager or designee

The Town Manager or designee shall review the administrative adjustment application to evaluate compliance with applicable standards. Following the review, the Town Manager or designee may approve, approve with conditions, or deny an administrative adjustment based on the criteria set forth in Section X.XX, Approval Criteria.

- (ii) The decision of the Town Manager or designee may be appealed to the Board of Adjustment in accordance with Section X.XX, Appeal
- (3) Approval Criteria.

The Town Manager or designee may approve an administrative adjustment upon a finding that:

- (a) The request is consistent with the intent, purpose, and goals of this Municipal Code;
- (b) The administrative adjustment is of a technical nature (i.e., relief from a dimensional or design standard), and is either:
 - (i) Required to compensate for some unusual aspect of the site or the proposed development that is not shared by landowners in general;
 - (ii) Support by an objective or goal from the purpose and intent of the zoning district within which the project is located; or
 - (iii) Proposed to protect sensitive natural resources or better integrate development with the surrounding environment.

(J) Variance

(1) General Provisions.

Variances are deviations from the zoning dimensional standards set forth in Chapter 7, Land Use Development Regulations, that would not be contrary to the public interest when, owing to special circumstances or conditions such as exceptional topographic conditions, narrowness, shallowness or the shape of a specific piece of property, the literal enforcement of the provisions of this Ridgway Municipal Code would result in peculiar and exceptional practical difficulties to or exceptional and undue hardship upon the owner of the property. No variance from the provisions governing "Uses By Right", and "Conditional Uses" within any zoning district may be granted.

- (2) Review Procedures
 - (a) Review Flowchart. Figure XXX, Variance Flowchart, depicts the variance application review process described in greater detail in this section.

Figure XXX, Variance Flowchart

[Insert Flowchart]

(b) Pre-Application Meeting

A pre-application meeting may be held in accordance with the provisions set forth in Section XXX, Pre-Application Meeting.

(c) Application Submittal Requirements.

The following are the application materials required to be submitted for variance requests. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.

- (i) Basic Application Materials. All items set forth in Section X.XX, Basic Application Materials.
- (ii) Written Narrative. A written narrative shall be submitted addressing all of the following items and any other information:
 - a. Explanation of the request(s) and justification for why the standard for which the variance is being requested is unable to be met;
 - b. Any efforts the applicant or property owner has made to meet the minimum standards;
 - c. Justification for the request and how the request is the minimum required standard(s);
 - d. Description of how the request meets each of the criterion set forth in Section X.XX, Approval Criteria;
- (iii) Site Improvement Plan
 - a. All existing, required, and proposed dimensional standards clearly depicting the location and increase of the variance request.
 - b. A table identifying the required standard(s) and the numerical value being requested by the variance.
- (iv) Additional Requirements
 - b. Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.
- (d) Completeness Review

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section XXX, Completeness Review.

(e) Evaluation by Staff and Referral Agencies

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section XXX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

(f) Staff Report

A staff report shall be prepared and provided to the reviewing body in accordance with Section X.XX, Staff Report.

(g) Review and Decision by Planning Commission

The Planning Commission shall review the variance application in a manner consistent with Table X-X.X to evaluate compliance with applicable standards. Following its review of the application, the Planning Commission shall approve, approve with conditions, or deny the application based on the criteria set forth in Section X.XX Approval Criteria.

a. No variance shall be granted with fewer than four (4) concurring votes of the Planning Commission regardless of number of Commissioners present.

- b. If there are only four (4) Commissioners present, the applicant may elect to, in their sole discretion, continue the hearing to a future meeting when more than four (4) Commissioners will be present.
- (3) Approval Criteria.
 - (a) The Planning Commission may grant a variance for allowed deviations only upon the finding that the following criteria are met:
 - (i) There are practical difficulties or unnecessary hardships in the way of carrying out the strict letter of the zoning ordinance, and
 - (ii) The spirit of the ordinance will be observed, the public health, safety and welfare secured and substantial justice done by granting the variance.
 - (b) The Planning Commission may grant a variance from the Off-Street Parking Requirements within the Historic Business Zoning District only upon the finding that the following criteria are met:
 - The variance is requested for an addition to an existing building or the construction of a purely accessory structure and these modifications will have a de minimis effect on traffic and parking; or,
 - (ii) The placement of on-site parking is not congruent with the goals and objectives of the downtown and as such will create an undesirable effect on the downtown streetscape, potentially interrupting, impeding or otherwise adversely affecting existing or future infrastructure such as pedestrian walkways and landscape areas; or,
 - (iii) There are practical difficulties or unnecessary hardships in the way of carrying out the strict letter of the Off-Street Parking Requirements.

(K) Appeal

- (1) General Provisions. Administrative interpretations and final decisions of the Town Manager or designee may be appealed to the Board of Adjustment. Recommendations to a decision-making authority are not subject to appeal pursuant to this Section X.XX, Appeal.
 - (a) Any person applying to the courts for a review of any decision made under the terms of this section shall apply for review within thirty (30) days after the date of decision and shall be required to pay the cost of preparing a transcript of proceedings and the application for review shall be in the nature of certiorari under Rule 106 (a) (4) of the Colorado Rules of Civil Procedure. The town shall be entitled to appeal any decision of the District Court under said Rule 106 proceedings.
 - (b) No appeal shall be granted with fewer than four (4) concurring votes of the Board of Adjustment members regardless of number of members present.
 - (c) If there are only four (4) members present, the applicant may elect to, in their sole discretion, continue the hearing to a future meeting when more than four (4) members will be present.
- (2) Review Procedures
 - (a) Review Flowchart. Figure XXX, Appeal Flowchart, depicts the appeal application review process described in greater detail in this section.

Figure XXX, Appeal Flowchart

[Insert Flowchart]

(b) Pre-Application Meeting

A pre-application meeting may be held in accordance with the provisions set forth in Section XXX, Pre-Application Meeting.

(c) Application Submittal Requirements.

The following are the application materials required to be submitted for appeal requests. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.

- (i) Basic Application Materials. All items set forth in Section X.XX, Basic Application Materials.
- (ii) Written Narrative. A written narrative shall be submitted addressing all of the following items and any other information:
 - a. Explanation of the request(s) and justification for why the standard for which the variance is being requested is unable to be met;
 - b. Any efforts the applicant or property owner has made to meet the minimum standards;
 - c. Justification for the request and how the request is the minimum required standard(s);
 - d. Description of how the request meets each of the criterion set forth in Section X.XX, Approval Criteria;
- (d) Completeness Review

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section XXX, Completeness Review.

(e) Evaluation by Staff and Referral Agencies

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section XXX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

(f) Staff Report

A staff report shall be prepared and provided to the reviewing body in accordance with Section X.XX, Staff Report.

(g) Review and Decision by Board of Adjustment

The Board of Adjustment shall review the appeals application in a manner consistent with Table X-X.X to evaluate compliance with applicable standards. Following its review of the application, the Board of Adjustment shall approve, approve with conditions, or deny the application based on the criteria set forth in Section X.XX Approval Criteria.

- (3) Approval Criteria.
 - (a) The Board of Adjustment may only approve an appeal upon a finding that the following criteria have been met:
 - (i) Literal enforcement of the standard or requirement would place an unnecessary and unreasonable hardship upon the applicant;
 - (ii) The granting of the appeal will not be materially detrimental to the public welfare or injurious to other property in the neighborhood and surrounding area;

- (iii) The appeal will not have adverse effect on the intent, goals, and policies of the Town of Ridgway;
- (iv) The appeal will not be averse to the intent of the applicable portions of the Master Plan in the reasonable judgement of the Board of Adjustment;
- (v) Evidence of the manner in which the provision has been interpreted in the past, if applicable; and
- (vi) The positive or negative impact of the requested appeal on the achievement of the purposes of the Municipal Code.

7-4-4 – ZONING DISTRICTS

(A) Establishment of Districts.

The following districts are established to encourage the most appropriate use of land within the Town of Ridgway.

(B) Residential Districts

The residential districts described in this Section are established to support a diversity of housing options; to promote stability in residential neighborhoods; to protect such property from incompatible land uses; to protect property values; and to encourage the appropriate use of such land. Certain other uses are permitted which are compatible with residences.

(C) Commercial Districts [New language]

The commercial districts described in this section are established to support a diverse and sustainable local economy with a mix of retail and service uses meeting the needs of the Ridgway community.

(D) Industrial Districts. [New language]

The industrial districts described in this section are established to support a diverse mix of employment opportunities including manufacturing, warehousing, distribution, or office uses to meet the needs of the regional workforce.

Table X-XX, Zone District Abbreviations

District Regulations	Abbreviation
Low Density Residential District	R
Historic Residential District	HR
Mixed Residential	MR
Future Development District	FD
Historic Business District	HB
Downtown Service District	DS
General Commercial District	GC
Light Industrial -1 District	I-1
Light Industrial – 2 District	I-2
Uncompahgre River Overlay District	UROD

(E) "R" Low Density Residential District

- (1) Intent: The "R" Low Density District is intended to accommodate low to moderate density development for single-family detached dwellings, as well as a mix of other housing types and other compatible land uses where supported by the Master Plan. Environmental protection is provided by allowing cluster development to preserve environmentally sensitive lands, maintain common open space, and to provide recreational opportunities for residents.
- (2) District Standards
 - (a) Permitted uses are identified in Table XXX.
 - (b) Lot size and required setbacks are identified in Table XXX.

(F) "HR" Historic Residential District

- (1) Intent: This District is intended to coincide with the historic residential core of Ridgway and accommodate a variety of housing types at medium density as well as other activities which are compatible with such uses.
- (2) District Standards
 - (a) Permitted uses are identified in Table XXX.
 - (b) Lot size and required setbacks are identified in Table XXX.

(G)"MR" Mixed Residential

- (1) Intent: This District provides opportunities for a diverse mix of housing options at higher densities, as well as supporting services and other compatible uses that help meet the needs of area residents. Uses should be organized in compact, pedestrian and bicycle friendly manner and be responsive to the scale and intensity of development in adjacent zoning districts.
- (2) District Standards
 - (a) Permitted uses are identified in Table XXX.
 - (b) Lot size and required setbacks are identified in Table XXX.
- (3) Performance and Design Standards. In addition to the Residential Design Standards in Section X-X, the following standards shall apply:
 - (a) Developments must address stormwater drainage and to employ a stormwater drainage plan that does not discharge to the Town streets or stormwater infrastructure if available, an amount greater than historic flows have discharged to public infrastructure.
 - (b) A mix and variety of housing types and unit sizes must be incorporated to the maximum extent feasible based on the size of the development, adjacent development context, and other site considerations.
 - (c) Parks, open spaces or common areas must be incorporated into the development.
 - (d) Parking shall be sited to provide the least visual impact from public rights-of-way and shall not dominate the frontage of pedestrian-oriented streets. Site parking shall include bike racks and areas for parking strollers and other nonmotorized vehicles near the main entrance to the primary building(s) and shall have a logical connection to on site non-motorized access routes.

- (e) Parking areas, outside trash receptacles, large utility boxes, open storage areas, mechanical systems and other unattractive views shall be screened from the street and public right-of-way. Screening of utility boxes, trash enclosures, and similar uses shall be around all sides except for those required for access, which will be screened with a gate on the access side.
- (f) Buildings containing more than 25,000 square feet of gross floor area are not permitted.

(H)"FD" Future Development District

- (a) Intent: This District is intended to include lands held in reserve to meet future growth needs of the community. Uses include very low-density single-family detached dwellings and agriculture.
- (b) District Standards
 - (i) Permitted uses are identified in Table XXX.
 - (ii) Lot size and required setbacks are identified in Table XXX.

(I) "HB" Historic Business District

- (a) Intent: This District encompasses the historic commercial core of Town. Intended uses include a mix of retail, restaurants, office, lodging, residential, service, institutional and other uses that are compatible with the historic character of the Town Core and contribute to vibrant, pedestrian-friendly atmosphere. All residential development must comply with residential design standards in Section XX. Where short-term rentals are permitted, they must comply with subsection XXX.
- (b) District Standards
 - (i) Permitted uses are identified in Table XXX.
 - (ii) Lot size and required setbacks are identified in Table XXX.
- (c) Performance Standards
 - (i) No use shall be established, maintained or conducted in any "HB" Historic Business District that will result in any public or private nuisance.
 - (ii) No equipment, inventory, or supplies may be stored outside, except as authorized pursuant to subsection 7-3-9(C)(3).
 - (iii) All manufacturing and industrial activities must take place inside with no noise, smoke, dust or light observable off of the premises.
 - (iv) Parking:
 - a. Residential uses must provide off-street parking as required by subsection XXX and subsection XXX.
 - b. All nonresidential uses must provide a minimum of one off-street parking space per 1,650 square feet of gross floor area. Partial spaces will be rounded up to the next whole number of required parking spaces. If the structure contains both residential and nonresidential uses, calculation of the gross floor area shall not include the residential area(s) for purposes of determining off-street parking pursuant to this paragraph. Also excluded from this calculation are enclosed parking and outdoor common areas. Parking spaces will be accessed only from an alley. The first three spaces must be provided on-site.

- c. In cases where mixed residential and nonresidential uses occur within the same property, the residential parking requirements of paragraph (a) shall be in addition to the nonresidential parking space requirement set forth in paragraph (b).
- d. In lieu of nonresidential off-street parking requirements in excess of three spaces and pursuant to paragraph (b) above, a money payment of \$3,000.00 per space may be paid to the Town, which money shall be used to fund the acquisition or construction of public parking facilities to serve the Historic Business Zoning District.
- (v) Buildings containing more than 15,000 square feet of gross floor area shall not be allowed.

(J) "DS" Downtown Service District

- (a) Intent: The Downtown Service District is not intended to compete with the Historic Business District or the General Commercial District, but rather intended to provide some flexibility in use for existing residences located on or within 100 feet of Highway 62, west of Laura Street as depicted upon the Town Comprehensive Plan Land Use Map. The flexibility in use is intended to mitigate the impact of increasing traffic upon the highway upon residences, by allowing for limited business use of the properties. The Downtown Service District is further intended to provide an effective transition between the General Commercial and Historic Business Districts and nearby residential neighborhoods along and near the Highway without creating an undue, adverse impact on these areas. Establishments and structures within the Downtown Service District are intended to appear "residential" as opposed to simply providing a visual extension of the commercial and business districts. Toward this objective, some service-oriented businesses are allowed within the Downtown Service District, as conditional uses, and with performance criteria that speak to appearance, signage and parking. These businesses may have limited and ancillary retail use. Home occupation of these business uses is permissible in accordance with subsection XXX. Auto intensive uses such as gas stations, drive through businesses, convenience stores and similar uses that generate high traffic of items or require large parking areas are not permitted. All residential development in these districts must comply with residential design standards in Section XXX.
- (b) District Standards
 - (i) Permitted uses are identified in Table XXX.
 - (ii) Lot size and required setbacks are identified in Table XXX.
- (c) Performance Standards for Conditional Uses
 - (i) Conditional Uses, other than churches, schools, multi-family residences and community centers, shall comply with the intent of subsection 7-3-10(A).
 - (ii) All applications for conditional uses shall be accompanied by a site plan proposal detailing, at a minimum, the following information or other information deemed necessary by the Town of Ridgway:
 - a. Site plan showing setbacks, lot coverage, parking, vehicle and pedestrian access, landscaping, topographic features, utility locations, storage/trash receptacles and similar information.
 - b. Building design showing building elevations (all four sides), finish materials, door and window placement and location and types of exterior lighting fixtures.
 - c. A statement of the anticipated traffic impact on the site and on adjacent properties and roadways.

- (iii) All professional offices and service businesses allowed as a conditional use shall have no more than five employees.
- (iv) Structures must be compatible in mass and scale with nearby residences, and similar in architectural features.
- (v) Off-street parking per Town standards is required, but businesses shall be credited with half parking space for every on-street parking space that is constructed adjacent to the business and in accordance with Town specifications. No parking shall be allowed on alley ways or on Highway 62 (Sherman Street).
- (vi) Signage shall be non-illuminated and attached to the building.
- (vii)Business hours shall be between 7:30 a.m. and 5:30 p.m.
- (viii) No semi-truck traffic shall be allowed upon residential streets or alley ways.
- (ix) No food services shall be allowed unless as otherwise specified herein.
- (x) No drive-in restaurants, drive-in theatres, or any other retail stores and service establishments with drive-through facilities shall be allowed in the "DS" District.

(K) "GC" General Commercial District

- (a) Intent: This District encompasses lands along the river and Highways 550 and 62. Its purpose is to create areas for a mix of retail and commercial services, office, and other supportive uses to meet the needs of residents and tourists. A mix of higher-density housing types are also supported to provide for live/work opportunities and to promote activity and vibrancy within these areas. While more auto oriented than development within the Town Core, uses in the "GC" District should be designed with the safety and convenience of pedestrians and bicyclists in mind. Where short-term rentals are permitted, they must comply with subsection XXX.
- (b) District Standards
 - (i) Permitted uses are identified in Table XXX.
 - (ii) Lot size and required setbacks are identified in Table XXX.
- (c) Performance Standards
 - (i) No use shall be established or maintained in the "GC" District which results in an unreasonable hazard to the community, creates a public or private nuisance, or creates unreasonable smoke, dust, noise, fumes, odors, vibrations or light observable off the premises.
 - (ii) Buildings containing more than 10,000 square feet of gross floor area will be required to mitigate the visual impacts of their size by means of design, landscaping, berming and other methods of site treatment, and must be compatible with the mass and scale of existing buildings on adjacent properties, or if there are no such buildings compatible with the mass and scale of buildings in the Town generally.
 - (iii) Buildings containing more than 25,000 square feet of gross floor area shall not be allowed.
 - (iv) All uses shall follow screening requirements as described in subsection X-XX.
 - (v) All outdoor storage areas must follow the screening requirements as described in subsection X-XX.
 - (vi) Residential development:

- a. Residential development shall comply with the Residential Design Standards in Section X-X, as applicable.
- b. Residential development shall not be located along Arterial street frontages to preserve these locations for commercial services and other businesses that rely upon visibility from Highways 550 and 62.
- c. Employee housing. All employee housing units shall meet the requirements of criteria of subsection X-XX.
- (i) Drive-in restaurants, drive-in theatres, or any other retail stores and service establishments with drive-through facilities, other than banks or pharmacies, shall not be allowed in the "GC" District.
- (ii) Boarding and Rooming House(s) shall not be allowed in the "GC" District.
- (iii) A Dormitory shall not be allowed in the "GC" District.

(L) "I-1" Light Industrial -1 District

- (a) Intent: This district is to provide areas for light industrial uses that include offices and light manufacturing and fabrication. Additionally, this district is to provide opportunities for employment and serve as a transition from adjoining residential neighborhoods. Uses by right in this district, will be those that do not create an adverse impact on adjoining uses from lighting, noise, vibration, glare, smoke/fumes/odor, outside storage or other similar impacts. Landscaping is to be used to improve the appearance of the properties, breakup parking areas into smaller sections and generally buffer the industrial area from surrounding non-industrial uses. Work conducted on-site is to occur primarily inside buildings. Some on-site impacts may be associated with this district in the form of noise, truck traffic, and vibrations. However, these impacts must be mitigated at the property line.
- (b) District Standards
 - (i) Permitted uses are identified in Table XXX.
 - (ii) Lot size and required setbacks are identified in Table XXX.
- (c) Performance Standards
 - (i) All manufacturing, fabrication and repairs shall be conducted within a building unless the activity is not visible from adjoining property outside of the light industrial district within 100 yards of the district boundary.
 - (ii) Outdoor storage of supplies, machinery, equipment or products shall be screened from view from the adjacent street and properties.
 - (iii) Any outside storage of materials, equipment or supplies associated with a use by right or conditional use shall not exceed 200 percent of the total building footprint of the structure associated with that use except in the case where materials are intended for on-site wholesale or retail sales.
 - (iv) Landscaping within setbacks and street rights-of-way where an industrial zoning district is adjacent to or across the street from a non-industrial use, additional landscaping shall be provided to buffer the industrial district from adjoining use. An applicant shall submit a detailed landscaping plan for locations within which the aforementioned conditions exist when the applicant makes a request for a building permit. The plan shall indicate location, type and species of all buffering vegetation. The landscaping plan shall also include the details of irrigation systems necessary for establishment and continued survival of all plantings. The Town shall review the landscaping plan to determine if it is in conformance with landscaped buffering standards in the Ridgway Municipal Code. Unacceptable

proposals will be rejected and the building permit shall be withheld until a plan providing adequate buffering is submitted and accepted by the Town.

- (v) The maximum fence height shall be eight feet.
- (vi) Maximum building size without special review is 5,000 square feet of gross floor area. Buildings containing more than 5,000 square feet of gross floor area will be required to mitigate the visual impacts of their size by means of design, landscaping, berming and other methods of site treatment. Buildings must be compatible with the mass and scale of existing buildings on adjacent properties, or if there are no such buildings, compatible with the mass and the scale of buildings in the Town generally. In no case, shall buildings exceed 5,000 square feet of building footprint.

(vii)Fencing, parking and storage is not allowed in the front or side setbacks along any street.

- (viii) Drive-in restaurants, drive-in theatres, or any other retail stores and service establishments with drive-through facilities shall not be allowed in the "I-1" District.
- (ix) Applicants shall submit an Industrial Use Mitigation Report that details how the proposed use will conform to the following criteria. Mitigation measures shall include, at a minimum, a combination of site design, building setbacks, landscaping and screening, to minimize noise, odor, glare, vibration or lighting from emanating beyond the property boundaries in a manner that is not in conformance with these or other town regulations. An application that fails to address each of the following items or that inadequately addresses these items shall be deemed incomplete and no permits shall be issued until all criteria have been addressed.
 - a. Additional Studies. The applicant shall complete or provide funding for completion of studies by qualified personnel that the Town deems necessary to quantify and to develop recommendations for abating impacts directly associated with the proposed use.
 - b. Dust and Fly Ash. No solid or liquid particles shall be emitted in such a quantity as to be readily detectable at any point along lot lines or as to produce a public nuisance or hazard beyond lot lines.
 - c. Electrical Disturbance or Interference. No use shall:
 - 1. Create any electrical disturbance that adversely affects any operations or equipment other than those of the creator of such disturbance, or
 - 2. Otherwise cause, create, or contribute to the interference with electrical signals (including television and radio broadcasting transmissions) to the extent that the operation of any equipment not owned by the creator of such disturbance is adversely affected.
 - d. Exterior Lighting. All exterior lighting shall conform to Chapter 6, Section 5 titled "Outdoor Lighting Regulations".
 - e. Fire and Explosion. No fire or explosive hazard shall exist such as to produce dangerous exposure to adjacent property.
 - f. Glare. No direct or reflected glare shall be detectable at any Light Industrial District boundaries.
 - g. Hazardous Waste. Hazardous waste shall be those substances as defined by Federal, State or local regulations. The disposal, treatment, bulking or handling (hereinafter collectively called treatment) of hazardous waste within the municipal limits of the Town shall be permitted only when such waste is generated within the Town. Any such

treatment shall be prohibited except in conformance with all applicable Federal, State or local regulations governing hazardous waste. The temporary storage of hazardous waste other than for treatment is permitted only when it is used, manufactured or generated as a waste as part of an industrial, manufacturing or laboratory process that takes place within the Town of Ridgway. In this circumstance, hazardous waste shall be inventoried and stored inside a building with an impermeable floor and otherwise handled in strict conformance with all applicable Federal, State and local regulations. The records pertain to such inventory and storage shall be open to authorized personnel of the Town of Ridgway and/or the Ridgway Fire Department upon reasonable request.

- h. Heat. No direct or reflected heat that is dangerous or discomforting shall be detectable at any Light Industrial District boundaries.
- i. Landscaping. A landscaping plan setting forth type, size, location of all plant types and species shall be submitted in conformance with the landscaping standards of Subsection 6-1-11. The design of the landscaping plan shall adequately buffer the light industrial use from adjacent surrounding non-light industrial zone districts and breakup any parking area more than 25 spaces to avoid the appearance of large areas of parking.
- Noise. No persistent noise shall be detectable beyond the property line in excess of j. the values identified in the following table:

	Zoning of Adjacent Lot					
Zoning of lot where use is located	All Residential Zone Districts	General Commercial District	Industrial-1 District	Industrial-2 District		
Industrial-1 District	50	55	60	65		
Industrial-2 District	50	60	65	70		
All of the above levels are measured in decibels dB(A)						

All of the above levels are measured in decibels dB(A).

- 1. Impact noises are sounds that occur intermittently rather than continuously. Impact noises generated by sources that do not operate more than one minute in any hour are permissible up to a level of ten dB(A) in excess of the figures listed in the table above, except that this higher level of permissible noise shall not apply from 7:00 p.m. to 7:00 a.m. when the adjacent lot is zoned residential. The impact noise shall be measured using the fast response of the sound level meter.
- 2. Noise resulting from temporary construction activity that occurs between 7:00 a.m. and 7:00 p.m. shall be exempt from the requirements of this Section.
- 3. Noise shall be measured on a decibel or sound level meter. Noise level shall be measured at a point located within a street or public right-of-way in the town and a distance of at least 25 feet from the noise source; and/or at the common property line of the property on which the noise source is located and the adjacent property.
- 4. No use in the light industrial zone districts may generate noise that tends to have an annoying or disruptive effect upon uses outside the immediate space occupied by the use if that use is one of several located on the lot or uses located on adjacent lots.
- 5. The table above establishes the maximum permissible noise levels for the I-1 and the I-2 Zone Districts. Measurements shall be taken at the boundary line of the lot where a particular use is located, and, as indicated, the maximum permissible

noise levels vary according to the zoning of the lot adjacent to the lot on which subject use is located.

- k. Odor.
 - 1. For purposes of this Section, the "odor threshold" is defined as the minimum concentration in a year of a gas, paper or particulate matter that can be detected by the olfactory systems of a healthy observer.
 - 2. No use in the I-1 or I-2 Districts may generate any odor that reaches the odor threshold measured at the outside boundary of the immediate space occupied by the enterprise generating the odor (if there is more than one enterprise in the structure) or the lot line (if the enterprise generating the odor is the only enterprise located on a lot).
- I. Off-site Impacts. Off-site impacts that directly result from the proposed use shall be abated. The Town of Ridgway reserves the right to require an independent evaluation of off-site impacts including recommendations about mitigation measures.
- m. Radioactivity. No operation shall be permitted which causes radioactivity in violation any applicable Federal, State or local regulation.
- n. Smoke. For purposes of determining the density of equivalent opacity of smoke, Ringlemann chart, as adopted and published by the United States Department of Interior, Bureau of Mines Information Circular 8333 May 1967, shall be used. The Ringlemann number referred to in this Section refers to the number of the area of the Ringlemann Chart that coincides most nearly with the visual density of equivalent opacity of the omission of smoke observed. For example, a reading of Ringlemann No. 1 indicates a 20-percent density of the smoke observed. No smoke shall be permitted in such quantity as to become a nuisance nor shall it be detectable at any property boundaries. All measurements shall be taken at the point of emission of the smoke. In the I-1 District, no use may emit from a tent, stack, chimney or combustion process any smoke that exceeds a density or equivalent capacity of Ringlemann No. 1, except that any emission that does not exceed a density or equivalent capacity of Ringlemann No. 2 is permissible for a duration of not more than four minutes during any eighthour period if the source of such emission is not located within 250 feet of a residential district.
- o. Vehicular Traffic. Traffic to and from the site shall not overload or damage street systems to or from the site. Verification of this provision shall be a confirmed by an independent traffic analysis conducted by properly qualified individuals.
- p. Vibration. No inherent and recurrently generated vibration shall be perceptible, without instruments, at any point along in the boundary line of the property on which the use is located. Where more than one use is located on a property, then this standard shall also be measured along any wall of any other building on the property.
- q. Waste Disposal. Liquid and solid waste disposal and water service shall comply with all pertinent Federal, State and local regulations.
- r. Observations shall be made as described in the applicable subsection above. In the event that the point of measurement is not defined or if there is more than one use on the property, measurements shall be taken at the property line of the lot on which the use is located if it is the only use on the lot, or at the exterior of the building in which the use is located is more than one use exist on the same site.

(M) "I-2" Light Industrial – 2 District

- (a) Intent: This district is similar to the I-1 Light Industrial District but will allow more intensive uses. Uses by right in this district, will be those that do not create an adverse impact on adjoining uses from lighting, noise, vibration, glare, smoke/fumes/odor, outside storage or other similar impacts. Landscaping is to be used to improve the appearance of the properties, breakup parking areas into smaller screened sections and generally buffer the industrial area from surrounding non-industrial uses. Work conducted on-site may occur outside of buildings. Some on-site impacts may be associated with this district in the form of noise, truck traffic, and vibrations. However, these impacts must be mitigated at the property line.
- (b) District Standards
 - (a) Permitted uses are identified in Table XXX.
 - (b) Lot size and required setbacks are identified in Table XXX.
- (c) Performance Standards
 - (i) All manufacturing, fabrication and repairs shall be conducted within a building unless the activity is not visible from an adjacent right-of-way or adjoining property outside of the light industrial district.
 - (ii) The maximum fence height shall be eight feet.
 - (iii) Buildings containing more than 5,000 square feet of gross floor area will be required to mitigate the visual impacts of their size by means of design, landscaping, berming and other methods of site and architectural design treatments. Buildings must be compatible with the mass and scale of existing buildings on adjacent properties, or if there are no such buildings, compatible with the mass and the scale of buildings in the Town generally. In no case, shall buildings exceed 12,500 square feet of building footprint.
 - (iv) Landscaping requirements for properties zoned I-2 are set forth as required by Subsection X-XX.
 - (v) Fencing, parking and storage shall not exist in front and street side yard setbacks.
 - (vi) Drive-in restaurants, drive-in theatres, or any other retail stores and service establishments with drive-through facilities shall not be allowed in the I-2 District.
 - (vii)Applicants shall submit an Industrial Use Mitigation Report that details how the proposed use will conform to the following criteria. Mitigation measures shall include, at a minimum, a combination of site design, building setbacks, landscaping and screening, to minimize noise, odor, glare, vibration or lighting from emanating beyond the property boundaries in a manner that is not in conformance with these or other Town regulations. An application that fails to address each of the following items or that inadequately addresses these items shall be deemed incomplete and no permits shall be issued until all criteria have been addressed:
 - a. Additional Studies. The applicant shall complete or provide funding for completion of studies by qualified personnel that the Town deems necessary to quantify and to develop recommendations for abating impacts directly associated with the proposed use.
 - b. Dust and Fly Ash. No solid or liquid particles shall be emitted in such a quantity as to be readily detectable at any point along lot lines or as to produce a public nuisance or hazard beyond lot lines.
 - c. Electrical Disturbance or Interference. No use shall:

- 1. Create any electrical disturbance that adversely affects any operations or equipment other than those of the creator of such disturbance, or
- 2. Otherwise cause, create, or contribute to the interference with electrical signals (including television and radio broadcasting transmissions) to the extent that the operation of any equipment not owned by the creator of such disturbance is adversely affected.
- d. Exterior Lighting. All exterior lighting shall conform to Section X-XX titled "outdoor lighting regulations."
- e. Fire and Explosion. No fire or explosive hazard shall exist such as to produce dangerous exposure to adjacent property.
- f. Glare. No direct or reflected glare shall be detectable at any Light Industrial District boundaries.
- g. Hazardous waste. Hazardous waste shall be those substances as defined by Federal, State or local regulations. The disposal, treatment, bulking or handling (hereinafter collectively called treatment) of hazardous waste within the municipal limits of the Town shall be permitted only when such waste is generated within the Town. Any such treatment shall be prohibited except in conformance with all applicable Federal, State or local regulations governing hazardous waste. The temporary storage of hazardous waste other than for treatment is permitted only when it is used, manufactured or generated as a waste as part of an industrial, manufacturing or laboratory process that takes place within the Town. In this circumstance, hazardous waste shall be inventoried and stored inside a building with an impermeable floor and otherwise handled in strict conformance with all applicable Federal, State and local regulations. The records pertaining to such inventory and storage shall be open to authorized personnel of the Town of Ridgway and/or the Ridgway Fire Department upon reasonable request.
- h. Heat. No direct or reflected heat that is dangerous or discomforting shall be detectable at any Light Industrial District boundaries.
- i. Landscaping. A landscaping plan setting forth type, size, location of all plant types and species shall be submitted in conformance with the landscaping standards Subsection X-XX. The design of the landscaping plan shall adequately buffer the light industrial use from adjacent surrounding non-light industrial zone districts and breakup any parking area more than 25 spaces to avoid the appearance of large areas of parking.

	Zoning of Adjacent Lot				
Zoning of lot where use is located	All Residential Zone Districts	General Commercial District	Industrial-1 District	Industrial-2 District	
Industrial-1 District	50	55	60	65	
Industrial-2 District	50	60	65	70	
All of the above levels are measured in decibels dB(A).					

j. Noise. No persistent noise shall be detectable beyond the property line in excess of the values identified in the following table:

1. Impact noises are sounds that occur intermittently rather than continuously. Impact noises generated by sources that do not operate more than one minute in

any hour are permissible up to a level of ten dB(A) in excess of the figures listed in the table above, except that this higher level of permissible noise shall not apply from 7:00 p.m. to 7:00 a.m. when the adjacent lot is zoned residential. The impact noise shall be measured using the fast response of the sound level meter.

- 2. Noise resulting from temporary construction activity that occurs between 7:00 a.m. and 7:00 p.m. shall be exempt from the requirements of this Section.
- 3. Noise shall be measured on a decibel or sound level. Noise level shall be measured at a point located within a street or public right-of-way in the town and a distance of at least 25 feet from the noise source; and/or at the common property line of the property on which the noise source is located and the adjacent property.
- 4. No use in the light industrial zone districts may generate noise that tends to have an annoying or disruptive effect upon uses outside the immediate space occupied by the use if that use is one of several located on the lot or uses located on adjacent lots.
- 5. The table above establishes the maximum permissible noise levels for the I-1 and the I-2 Zone Districts. Measurements shall be taken at the boundary line of the lot where a particular use is located, and, as indicated, the maximum permissible noise levels vary according to the zoning of the lot adjacent to the lot on which subject use is located.
- k. Odor.
 - 1. For purposes of this Section, the "odor threshold" is defined as the minimum concentration in a year of a gas, paper or particulate matter that can be detected by the olfactory systems of a healthy observer.
 - 2. No use in the I-1 or I-2 Districts may generate any odor that reaches the odor threshold measured at the outside boundary of the immediate space occupied by the enterprise generating the odor (if there is more than one enterprise in the structure) or the lot line (if the enterprise generating the odor is the only enterprise located on a lot).
- I. Off-site Impacts. Off-site impacts that directly result from the proposed use shall be abated. The Town of Ridgway reserves the right to require an independent evaluation of off-site impacts including recommendations about mitigation measures.
- m. Radioactivity. No operation shall be permitted which causes radioactivity in violation any applicable Federal, State or local regulation.
- n. Smoke. For purposes of determining the density of equivalent opacity of smoke, Ringlemann Chart, as adopted and published by the United States Department of Interior, Bureau of Mines Information Circular 8333 May 1967, shall be used. The Ringlemann number referred to in this Section refers to the number of the area of the Ringlemann Chart that coincides most nearly with the visual density of equivalent opacity of the omission of smoke observed. For example, a reading of Ringlemann No. 1 indicates a 20-percent density of the smoke observed. No smoke shall be permitted in such quantity as to become a nuisance, nor shall it be detectable at any property boundaries. All measurements shall be taken at the point of emission of the smoke. In the I-2 District, no use may emit from a tent, stack, chimney or combustion process any smoke that exceeds a density or equivalent capacity of Ringlemann No. 2, except that and emission that does not exceed a density or equivalent capacity of Ringlemann No. 2 is permissible for a duration of not more than four minutes during any eight-

hour period if the source of such emission is not located within 500 feet of a residential district.

- o. Vehicular Traffic. Traffic to and from the site shall not overload or damage street systems to or from the site. Verification of this provision shall be a confirmed by an independent traffic analysis conducted by properly qualified individuals.
- p. Vibration. No inherent and recurrently generated vibration shall be perceptible, without instruments, at any point along in the boundary line of the property on which the use is located. Where more than one use is located on a property, then this standard shall also be measured along any wall of any other building on the property.
- q. Waste Disposal. Liquid and solid waste disposal and water service shall comply with all pertinent Federal, State and local regulations.
- r. Observations shall be made as described in the applicable subsection above. In the event that the point of measurement is not defined or if there is more than one use on the property, measurements shall be taken at the property line of the lot on which the use is located if it is the only use on the lot, or at the exterior of the building in which the use is located is more than one use exist on the same site.

(N) Uncompany River Overlay District

- (a) Purpose and Intent: The purpose of the Uncompany River Overlay District (UROD) is to promote the public health, safety and welfare of the citizens of the Town of Ridgway. The Town shall use the UROD to implement goals, policies and action items in the Town of Ridgway's Land Use Plan; preserve, improve and protect the river corridor as a Town amenity; regulate buildings and structures to maximize access to the Uncompany River and view corridors along the Uncompany River; utilize design and development techniques that avoid, minimize and mitigate impacts to the natural environment; and ensure aesthetic and ecological qualities of the river corridor continue to be a community asset.
- (b) Applicability: The provisions and regulations of this Subsection XXX shall apply to all land within the Town of Ridgway Official Zoning Map included as part of the UROD; and as defined within these regulations. The provisions of this Subsection XXX shall apply in addition to the applicable requirements of the underlying zoning district, the Flood Plain Management Regulations in Ridgway Municipal Code Chapter XXX, and other regulations of the Town. When the standards of this UROD conflict with any other provision of the Ridgway Municipal Code, the more stringent limitation or requirement shall apply. Within the UROD, all land use activity, development, redevelopment, renovation, and/or change in use requiring a building, development, or other land use permit (for the purposes of this Section of the Ridgway Municipal Code shall be defined as "Development") are subject to the provisions of this Subsection XXX.
- (c) Uses by Right: Uses permitted by the underlying zoning district are allowed unless specifically prohibited, provided that the use complies with this Subsection XXX, and provided any development complies with this Subsection XXX.
- (d) Conditional Uses: All conditional uses allowed within the underlying zoning district may be permitted upon approval in accordance with Subsection XXX, and provided any development complies with this Subsection XXX.
- (e) Development between 25 and 75 feet:
 - (i) Development between 25 and 75 feet from the High-Water-Mark shall be reviewed in accordance with Subsection XXX, as a conditional use. In addition to the review criteria under Subsection XXX, the following shall also apply:

- a. All of this Subsection XXX.
- b. The applicant shall provide an Ecological Characterization Study in accordance with subsection XXX which concludes that any adverse impacts to the river environment with the proposed Development can be mitigated, and the applicant shall incorporate the mitigation into the development plan and construct the mitigation with the Development.
- c. Special consideration for development shall be given so as to not deprive reasonable use of any land within the UROD.
- (f) Performance Standards:
 - Setback: All development must be setback a minimum of 75 feet from the High-Water-Mark, unless approved as a Conditional Use as further set forth under subsection 7-3-14(D) and (E).
 - (ii) Public Access:
 - a. If any proposed or existing trail, path or public access area as described in the Town's Land Use Plan or Parks and Trails Map, as amended from time to time and including the Uncompandgre RiverWay Trail, traverses a parcel proposed for development, the Town may require as a condition of development approval, dedication of a bicycle/pedestrian trail easement and/or public access easement benefiting the Town of Ridgway. The preferred dedication is for a ten-foot-wide bicycle/pedestrian public access trail easement. However, in reviewing the proposed site plan, the Town shall evaluate the nature and extent of the proposal and the proportionality between the proposal and the dedication and may determine that the ten-foot dedication is appropriate or may reduce the dedication based on the proportionality assessment. The Town may also take into consideration whether and to what extent there are existing easements over the subject property, which provide the same functions of the required public access trail easements. Any trail easements shall be located at, or above, the High-Water Mark or abutting a public right-of-way. In lieu of a trail dedication, other trail locations that provide for connectivity to existing or future trails, and are made accessible to the public through a dedicated public access easement, may be approved by the Town.
 - b. As a condition of development approval, if any proposed or existing trail, path or public access area as described in the Town's Land Use Plan or Parks and Trails Map, as amended from time to time and including the Uncompander RiverWay Trail, does not traverse a parcel proposed for development, the Town shall not seek a dedication of bicycle/pedestrian trail easement and/or public access easement benefiting the Town of Ridgway. However, parcels within the UROD are encouraged to provide public access to the Uncompander River including clearly defined access points to public trail segments. "Access" refers to the provision of access from a public right-of-way to a publicly accessible trail or path and/or to the water's edge of the Uncompander River.
 - (iii) Design Guidelines and Standards:
 - a. These Design Guidelines and Standards under this subsection 7-3-14(D)(3) shall apply to all development within the UROD, with the exception of single-family and duplex residential buildings.
 - b. Site Planning:
 - 1. Existing or historic drainage ways shall be accommodated with the development plan.

- 2. Discharge of stormwater directly into the river is prohibited. Use of landscaped/grassed catchment areas and similar design features shall be used for managing, controlling and filtering parking lot and site drainage.
- 3. Outdoor common areas, seating and/or dining is recommended on the river side of the building.
- 4. A visible and accessible public entrance from the side of the property facing the Uncompany River is encouraged for commercial properties that are open to the public.
- c. Parking and Loading:
 - 1. Parking and loading shall be sited to provide the least visual impact from public rights-of-way, including the Uncompany River corridor.
 - 2. Trees shall be incorporated to provide parking lot shading. Bollard and/or street lighting shall be used to provide lighting at critical access points.
 - 3. Site parking shall include bike racks and areas for parking strollers and other nonmotorized vehicles near the main entrance to the primary building(s) and should have a logical connection to on-site non-motorized access routes.
- d. Mass, Scale, Architectural Design and Materials:
 - 1. Total building façade length shall be less than 50 feet in length parallel to the river.
 - 2. Buildings shall avoid monolithic shapes and surfaces by incorporating solids and voids, changes in color, pattern, texture and materials at minimum along the primary façade and the façade along the linear frontage of the river.
 - 3. Use of naturally derived materials, such as stone, wood and innovative materials such as metal, or high-quality environmentally friendly wood-alternative decking and siding, shall be required.
- e. Screening and Buffers: All parking areas, outside trash receptacles, large utility boxes, mechanical systems and other unattractive views shall be screened with landscaping from public rights-of-way, including the Uncompany River corridor. Screening is not required where access is necessary but shall be screened with a gate where feasible. The purpose of screening and buffers is to promote the public health safety and welfare to conserve views along the Uncompany River corridor, and to improve the visual appearance along the river.
- f. Exceptions to these Design Guidelines and Standards may be pursued through the variance process pursuant to Subsection XXX.
- (g) Submittal Requirements: These submittal requirements are in addition to the underlying zoning district submittal requirements for the type of land use activity or development proposed. The following information must be completed and included in all applications for development or land use activity:
 - (i) A development plan showing compliance with the Performance Standards listed in subsection X-XX.
 - (ii) Survey map including property boundaries, the location of the High-Water-Mark and 75 foot setback. In the event the identification or location of the High-Water-Mark is disputed by the Town, the Town may hire a professional experienced in the identification of a High-Water Mark, to survey the High-Water Mark, and charge the cost of each survey to the Property owner.

- (iii) In addition to the above, development applicants seeking a Conditional Use in accordance with subsection X-XX are required to submit an Ecological Characterization Study completed by a professional qualified in the areas of ecology, wildlife biology or other relevant discipline. The Ecological Characterization Study shall describe, without limitation, the following:
 - a. The boundary of wetlands and riparian areas and a description of the ecological functions and characteristics provided by those wetlands and riparian areas;
 - b. The pattern, species and location of any significant native trees and other native site vegetation;
 - c. The pattern, species and location of any significant non-native trees and non-native site vegetation that contribute to the site's ecological, shade, canopy, aesthetic and cooling value;
 - d. The top of bank, the 25-foot setback and High-Water-Mark of any perennial stream or body of water on the site;
 - e. The wildlife use of the area showing the species of wildlife using the area, the times or seasons that the area is used by those species and the "value" (meaning feeding, watering, cover, nesting, roosting, perching) that the area provides for such wildlife species;
 - f. Special habitat features;
 - g. Wildlife movement corridors;
 - h. The general ecological functions provided by the site and its features;
 - i. Any issues regarding the timing of development related activities stemming from the ecological character of the area; and
 - j. Any measures needed to mitigate the projected adverse impacts of the development project on natural habitats and features along the Uncompany River corridor.
- (h) Exempt Uses and Activities: The following uses and activities are exempt from these regulations, including the Performance Standards of subsection X-XX and the submittal requirements of subsection X-XX, provided plans and specifications are approved by the Town, and all local, state and federal permitting is approved.
 - Public improvements essential for public health and safety, installed by, and/or approved by the Town, including, but not limited to, public utility buildings, facilities, systems and accessory structures;
 - (ii) Public improvements such as pedestrian and automobile bridges, trails and recreational amenities installed by, and/or approved by the Town;
 - (iii) Irrigation, drainage, flood control or water diversion structures installed by, and/or approved by the Town; and
 - (iv) Bank stabilization, river restoration and planting of native vegetation installed by, and/or approved by the Town.
 - (v) Notwithstanding Subsection X-XX of the Code, any development (as defined in subsection X-XX related to any structure within the UROD that was legally conforming prior to the date of adoption of this Section, so long as such development does not expand the building footprint of the structure and is in compliance with all other Town regulations.

(O) Land Use Table.

Table XXX, Table of Land Uses, identifies allowed land uses within each of the established zone districts. Table XXX also identifies uses that may be allowed when accessory to a principal use. The Town Manager or designee shall determine whether any use that is not specifically listed is allowed in a corresponding zone district and the level of review required, based upon the listed use which is most similar to the use not specifically listed.

- (1) Table of Land Uses Interpretation and Process
 - (a) Site Plan Approval. Nonresidential and multi-family uses identified in Table XXX must receive approval of a site plan in accordance with Section XXX, Site Plan, prior to commencing any development activity regardless of whether such use is allowed by right or requires an administrative approval or conditional use permit.
 - (b) Administrative Approvals. Any use identified as requiring Administrative Approval in Table XXX is subject to site plan review in accordance with Section XXX, Site Plan, prior to commencing any development activity.
 - (c) Conditional Uses. Any use identified as requiring a Conditional Use in Table XXX shall receive a Conditional Use Permit in accordance with Section XXX, Conditional Use Permit.
 - (d) Uses not Allowed. If a particular use does not have a letter corresponding to a zone district, that use is prohibited in the respective zone district.

Use Category		R	HR	MR	FD	HB	DS	GC	I-1	I-2
R – Allowe	ed by Right A – Administrative Approval Require	ed (C – Co	onditio	nal U	se Pe	ermit F	Require	ed	
Agricultural Uses Agriculture					R					
	Feed Storage and Sales							С		
Animal Services	Veterinary Clinic							С		R
	Kennel, Boarding Facility									R
Childcare	Day Care Facility	С	С	С			С	С		
Facilities										
Community and	Libraries					R		R		
Cultural Facilities	Museums					R		R		
	Community Center		С			R	С	R		
	Churches	С	С			R	С	R		
Educational	Schools	С	С	С		R	С	R	R	R
Facilities										
Food and	Restaurants and Taverns			С		R		R		
Beverage										
Group Living	Group Homes	С	С	R		R	С			
Household Living	Dwelling, Co-Housing Development		С	R						
	Dwellings, Duplex	R	R	R			R			
	Dwelling, Fourplex	С	R	R		R	R	С		
	Dwelling, Multiple-Family	С	С	R		R	С	R		
	Dwelling, Live-Work			С		R	R	R		
	Dwelling, Single-Family		R	R	R		R			
	Dwelling, Townhouse. No more than 2 units			R		R	R	С		
	Dwelling, Townhouse. More than 2 units.			R		R	R	С		
	Dwelling, Townhouse. No more than 4 units.		R	R		R	R	С		
	Dwelling, Townhouse. More than 4 units.		С	R		R	R	С		
	Dwelling, Triplex	С	R	R		R	R	С		

Table XXX – Land Use Table

				1						-
	Dwellings, Cluster Development	R		R						
	Employee Housing							R		
	Manufactured Homes		R							
	Manufactured Homes Park							С		
Lodging Facilities	Bed & Breakfast	С	С	С			С			
	Nursing Homes			С						
	Hotels, Motels, Lodges					R		R		
	Travel Homes Park							R		
	Campgrounds							С		
Manufacturing &	Gravel Extraction				С			Č		
Production	Manufacturing, Light					С		-	С	R
	Machine and Welding Shop					-		С		R
	Manufacturing and Industrial Use							C		.`
	Manufacturing Processing and Assembly							U U	R	С
Parks & Open	All Park and Open Space Uses	R	R	R		R	R	R		C
Space	Air Fark and Open Space Uses		ĸ			ĸ	ĸ	ĸ		
Personal Services	Professional Office					R	С	R	R	
& Office	Service Establishment					R	С	R	R	
	Funeral Homes					R		R		
Public Utilities &	Public Utility Service Facilities	R	R	R	R	R	R	R	R	R
Facilities	Government Buildings & Facilities	R	R	R		R	R	R	R	R
	Libraries					R		R		
	Depots					R		R		
Recreation	Recreation Facilities	R	R	R		R	R			
	Indoor Theaters					R		R		
	Arts and Craft Studio					R				
Retail	Retail, Limited						С			
Recail	Retail Stores			С	R	R	<u> </u>	R		
	Building Materials Business							C		
	Farm Implement, Manufactured Home, Auto							C		
	sales							C		
	Retail, Wholesale Use								С	С
Vehicles &	Automobile Body Shops							С	C	R
Equipment	Commercial Garages					R		R		ĸ
Lquipment	Parking Facilities					R		R		
	Gas Station					ĸ		к С		
								U		Р
	Truck Repair Shop									R
Manahamainan O	Carwash	-						~		R
Warehousing &	Warehouse or Storage Facility	-						С	R	
Freight	Motor or Railroad Freight Depots					_				R
Accessory Uses	Outdoor Storage			_	_	С		_	_	R
	Accessory	R	R	R	R			R	R	R
	Uses		_		-		-			
	Dwelling, Accessory	R	<u>R</u>	R	R	R	R			
	Home Occupation	R	R	R	R	R	R	R		
Temporary										
Structures & Uses										
Miscellaneous	Buildings with a gross floor area greater than			C						
	10,000 sq. ft.									

Buildings with a gross floor area greater than 7,500 sq. ft.			С		
Buildings 27' to 35 ' in height or containing more than 10,000 sq. ft. of gross floor area				С	
Developments with more than 20 parking spaces				С	
Private and Fraternal Clubs			R	R	

(P) Zone District Dimensional Standards

(1) Dimensional Standard Requirements

Dimensional standards for lot size, setbacks, and maximum height are summarized for each zone district in Table XXX, Dimensional Standard Requirements, below.

Table X-XX - Dimensional Standard Requirements:

ىر	Min. Lot			Max. Lot	Min. Se	tbacks (ft	:)		Structure
District	Use	Use Width Size (%) (ft) (sf)	Coverage (%)	Front	Rear	Side	Side on Corner Lot	Height (ft)	
R	Single-Family and Duplex	50	6,000	50	15	8	5	7.5	27
	All others	50	10,000	40	15	8	8	7.5	27
	Single Family and Duplex	25	3,000	60	15	8	3	7.5	27
HR	Residential uses with three or four dwelling units	35	5,000	60	15	8	3	7.5	35
	All others	70	10,000	50	15	8	5	7.5	35
	Single Family and Duplex	25	3,000	60	10	8	3	7.5	35
MR	Residential uses with three or four dwelling units	35	4,000	60	10	8	3	7.5	35
	All other residential and mixed uses	50	5,000	60	10	8	5	7.5	35
	Nonresidential uses	N/A	N/A	70	15	8	5	7.5	35
HB	All	25	NA	NA		8			35
GC	All	30	5,000	60	15	8	8	7.5	27
FD	All	50	35 ac.	NA	15	8	8	7.5	27
I-1	All	50	6,000	50	15	8	8	8	30
I-2	All	50	6,000	50	15	8	8	8	30
DS	All	50	5,000	50	15	8	8	7.5	27

- (2) Additional Dimensional Standards and Exceptions [created this subsection off of existing footnotes. Extensive footnotes that are generally applicable should be minimized.]
 - (a) When the rear or side lot line abuts an alley, the setback shall be a minimum of two feet.
 - (b) In the General Commercial District, a 35 feet height may be allowed if approved as a conditional use.
 - (c) HB Setbacks shall be determined as follows:
 - (i) The setback shall be eight feet, unless snow and drainage from the roof is effectively directed away from the abutting property, in which case the setback can be as little as four feet.
 - (ii) In those instances where snow and drainage is effectively directed away from the abutting property, and the foundation and wall of the structure are constructed so that a wall and foundation of a building on an abutting lot can be built up to, or abutting the property line, the setback can be eliminated.
 - (d) 3rd story Buildings: In buildings with three stories above ground, the third story shall be subject to a 15-foot front setback, and an eight-foot side setback for those sides facing a public street, in addition to other applicable setbacks as provided above. The third story setbacks may be reduced or eliminated where design of the third story provides architectural features that are aesthetically attractive to provide visual relief and contrast as an alternative to monolithic three-story facade surfaces. For purposes of this provision, such features include, but are not limited to, integration of third stories into roof lines, multiple roof lines and angles, windows, doors and balconies, and fenestration and facade designs that make a distinction between upper and lower floors, such as horizontal banding and varied building materials.
 - (e) Any reduction of the setbacks as specifically provided in these paragraphs (a), (b) and (c) shall be determined by the Town Planning Commission, pursuant to consideration of the criteria as set forth herein and in accordance with the review procedures as set forth in Subsection XXX.
 - (f) Within the I-2 District, commercial telecommunication antennae or towers that are located on Town owned property and that are in compliance with subsection XXX may have a structure height of up to 40 feet.
 - (g) If a single-family or duplex dwelling is five feet or less from the side property line, a fire suppression system is required. Fire suppression systems are required in all other buildings per the Building Regulations, see Ridgway Municipal Code Section XXX If any structure is less than five feet from the side property line, a site-specific geotechnical report is required as well as snow guards, brakes or other devices to prevent snow and ice shedding onto adjacent properties.
 - (h) Proper dimensional requirements for conditional uses shall be determined in accordance with Subsection XXX. Provided, that as a general rule, they shall be no less strict than the dimensional requirements specified for uses by right in the district concerned or as specified for the use concerned in a zone in which it is a use by right whichever is more restrictive.

7-4-5 SUPPLEMENTAL REGULATIONS

(A) Home Occupations [Brought from 7-3-18(A)]

Home Occupations may be conducted within a residential premises or accessory structure related thereto in any district as an accessory use only if the following criteria are met:

- (1) Town and State Sales Tax Licenses must be obtained if sales taxable by the Town or State sales taxes are to be made.
- (2) Only the residents of the dwelling unit may be engaged in the home occupation.
- (3) No unreasonable noise, glare, smoke, dust, vibration or odor shall be observable off the premises.
- (4) The home occupation activity shall not utilize or occupy more than 750 square feet in total, nor more than 400 square feet in a garage or other structures outside of the residence. Provided, however, accessory day care facilities shall be limited to eight or fewer children in lieu of these area limitations.
- (5) No business activity or storage of property involved in the business may take place outside of enclosed structures, except for horticultural activities.
- (6) The short-term rental of rooms, such as bed and breakfast operations, does not qualify as an accessory use pursuant to this Subsection.

(B) Offensive Businesses [Brought from 7-3-18(B)]

It shall be unlawful to maintain, own or operate any offensive or unwholesome business or establishment within the Town, including, but not limited to, rendering plants, tanneries, pig sties, feed lots, dairy farms, manufacture and storage of explosives, sugar beet pulp storage facilities, foundries, or petroleum product refineries, unless such business was lawfully in existence at the effective date of this Section, or at the effective date of annexation subsequent to the effective date of this Section. In either event, such business or establishment shall be subject to the Nonconforming Use Regulations of Subsection XXX of these regulations, and all other applicable regulations of the Town.

(C) Use and Location of Travel Homes [Brought from 7-3-18(D)]

- (1) Travel homes may be occupied only in the following circumstances:
 - (a) Within a licensed travel home park for a maximum period of six months in any one 365day period.
 - (b) Upon private property for temporary occupancy by out-of-town guests for a period not to exceed 30 days in any year for any tract of property.
 - (c) Upon property for which a permit has been issued by the Town, pursuant to subsection XXX.
- (2) Travel homes may be parked, if unoccupied, upon private property if in compliance with zoning setbacks, or temporarily upon public streets, if registered under State law and lawfully parked. Provided, however, they may not be parked in a manner which creates a traffic hazard.

(D) Garage and Yard Sales [Brought from 7-3-18(E)]

- (1) Notwithstanding restrictions of Town Zoning Regulations, or junk, litter or nuisance ordinances, garage and yard sales may be conducted within the Town consistent with the conditions set out herein.
- (2) No premises shall be used for a garage or yard sale for more than 48 hours at one time or for more than two such sales in any calendar year.

- (3) The sale shall be conducted so that no traffic hazards or nuisances are created.
- (E) Bed and Breakfast Operations [Brought from 7-3-18(F)]
 - (1) Residents of a dwelling unit in the "R" and "HR" Districts may rent rooms on a short-term basis (and may provide meals to such boarders) if a Conditional Use Permit is approved by the Planning Commission pursuant to Sections XXX and XXX, and the operation will comply with the criteria of this Subsection.
 - (2) The application shall not be granted unless the Planning Commission determines that the following criteria are met:
 - (a) There is at least one additional off-street parking space for each room to be rented in addition to the off-street parking required for the residential dwelling unit.
 - (b) No more than three rooms shall be rented in any dwelling unit. Such rooms shall be an integral part of the dwelling unit.
 - (c) The meals to be served shall be served from the kitchen which is part of the dwelling unit itself.
 - (d) The operation will not create a public or private nuisance.
 - (e) Only the permanent residents of the dwelling unit shall be employed in the operation.
 - (f) The Permittee will obtain a sales tax license and remit sales tax and lodging occupation tax.
 - (3) The Town Council may revoke any permit if it determines following a hearing with reasonable notice to the holder of the permit that the above criteria or limits of any permit are not being met.
- (F) Accessory Dwelling Units [Brought from 7-3-18(G)]
 - (1) The creation of Accessory Dwelling Units (ADU) is generally encouraged as an effective means to improve housing affordability, provided that each ADU complies with the following standards.
 - (2) ADUs are only allowed as accessory to a single-family detached dwelling. Only one ADU per single-family detached dwelling unit is permitted.
 - (3) The accessory dwelling unit must be constructed in accordance with applicable requirements of Town Building Codes. It may be attached or detached to the principal residential unit. Applicable dimensional requirements for a single-family dwelling as set out in subsection 7-3-15(A) must be met for the premises.
 - (4) One off-street parking space shall be provided for the accessory dwelling unit in addition to any other required off-street parking.
 - (5) The accessory dwelling unit may not exceed 800 square feet of gross floor area.
 - (6) One of the dwelling units on the property must be, and remain, owner occupied.
 - (7) A minimum of a 90-day rental period shall be required by written lease, except as described in subsection (12) below.
 - (8) The accessory dwelling unit must be owned together with the principal residential unit, and the lot or parcel upon which they are located, in undivided ownership.
 - (9) The accessory dwelling unit may be served off of the water or sewer tap for the principal residence, in which case it shall not be subject to additional tap fees.

- (10) The burden shall be upon the owner of any accessory dwelling unit to provide adequate proof to the Town that the criteria of this Section are met. In the event that the Town determines that the criteria have not been shown to be satisfied the unit may not be occupied as a residence.
- (11) A dwelling unit constructed before a principal single-family home, which meets these criteria, may be converted to an accessory dwelling unit following construction of a new principal dwelling unit.
- (12) An accessory dwelling unit, as defined in Section XXX either attached or detached to the primary dwelling, may be utilized as a short-term rental only under the following circumstances:
 - (a) Tap fees are paid at 30 percent pursuant to Ridgway Municipal Code subsection 9-1-9(c)(2); and
 - (b) One hundred percent of monthly water, sewer, trash and recycling services are paid on a monthly basis pursuant to Ridgway Municipal Code Chapter 9; and
 - (c) The lot size upon which both dwelling units are sited is a minimum of 6,000 square feet.

(G) Telecommunication Antenna and Tower Regulations [Brought from 7-3-18(H)]

- (1) Telecommunication towers and antennae shall be located, and comply with the following provisions:
 - (a) Noncommercial television and telecommunications receivers and amateur radio antennae, which qualify as an accessory use to the main use on the premises, may be located on such premises.
 - (b) Antennae for "personal wireless services" as defined in 97 USC 332(c)(2) shall be limited to the GC Zoning District, or upon Town owned property in other zoning districts pursuant to leases or permits with the Town, with terms and conditions adequate to ensure safety and reasonable compatibility with the neighborhood in which they are located, including requirements for camouflaging where appropriate.
 - (c) Commercial radio, television and other telecommunications transmitters and receivers shall be restricted to the GC Zoning District.
 - (d) Additional receivers or transmitters may be installed on existing telecommunication towers regardless of the zoning district.
- (2) All telecommunication antennas and towers shall be limited to the maximum structure heights set out in Section XXX, unless a variance is obtained pursuant to Section XXX, or allowed in accordance with the following exceptions:
 - (a) Telecommunication antennas, receivers and transmitters may be located on lawfully existing towers and structures, as long as they are not above the tower structure.
 - (b) A variance to the height limitations otherwise applicable may be obtained for an amateur radio antenna for noncommercial use pursuant to the review procedure of Section XXX if the Planning Commission determines that the following criteria are met:
 - (i) A higher tower is necessary to be reasonably adequate for the domestic communications purposes;
 - (ii) No reasonable alternative exists;
 - (iii) No adverse impacts will be created with respect to other property in the area.

- (c) A variance to the height limitations otherwise applicable may be obtained for personal wireless service antennae if the Planning Commission determines pursuant to the review procedure of Subsection XXX that the following criteria are met:
 - (i) Space is not available at a commercially reasonable price on an existing tower or structure located in a technically feasible location, and no other location is available which will provide reasonably adequate service in compliance with the height limitations set out above, and
 - (ii) No adverse effect on property values in the area will be caused, and no safety hazard will be created.
 - (iii) The design and color of the tower and appurtenances shall be reasonably compatible with the site and surrounding area.
- (d) Commercial telecommunication antennae or towers up to 40 feet in height may be installed upon Town owned property within the "I-2" Light Industrial 2 Zoning District.
- (3) A final decision to deny a variance shall be in writing and supported by a substantial written record.
- (4) All towers and structures shall be subject to the building setback requirements of Subsection XXX and applicable provisions of Town building codes and other ordinances and regulations.

(H) Short-Term Rental Regulations [Brought from 7-3-18(1)]

- (1) Intent and Purpose: Establish standards and procedures by which residential short-term rentals can be provided in a manner that protects both the quality of experience and the character of the Town. It is the Town's intent to establish short-term rental regulations to promote a mix of lodging options, support the local economy, while also upholding the integrity of the Town.
- (2) Short-term rentals shall comply with the provisions of this subsection (I) and shall be licensed per Chapter 8, Section 5 of the Municipal Code.
- (3) Permitted Use of Short-Term Rentals:
 - (a) For short-term rentals not in the "HB" Historic Business or "GC" General Commercial Districts, the structure involved:
 - (i) Shall be a single-family dwelling structure; or
 - (ii) Shall be a single residential unit in structures with mixed uses; or
 - (iii) Shall be a property with two dwelling structures owned by the same owner, in which one of the dwelling structures may be used as a short-term rental as long as the second dwelling unit is owner occupied.
 - (iv) Shall not be a multiple family dwelling or structure as short-term rentals are prohibited in multiple family structures.
 - (b) In the HB and GC Districts, a maximum of five short-term rentals are allowed per building or structure.
- (4) Performance Standards for Short-Term Rentals:
 - (a) The unit being rented shall be a dwelling unit, as defined pursuant to Section XXX shall not have more than five bedrooms, nor be leased or used to any group containing more than ten people over the age of 18.
 - (b) The unit shall have a minimum of two off street parking spaces available and any additional spaces necessary to accommodate the tenant's vehicles off street.

- (c) There shall be an owner's agent available to be at the unit within 20 minutes, who is on call full time to manage the property during any period the unit is rented. The name, address and phone number of the agent must be kept current on file with the Town, and posted in the short-term rental.
- (d) Adequate animal resistant trash and recycle containers shall be provided, and information on placement for collection shall be provided, in the short-term rental as stated in Ridgway Municipal Code Section 9-2.
- (e) The unit shall be maintained in compliance with applicable Town ordinances and regulations. The rental of residential units as provided herein shall not unreasonably annoy or interfere with the use or enjoyment of public or private property or which constitutes a health or safety hazard.
- (f) The owner must have current State and Town sales tax licenses, a Town business license at such time the Town has business licensing, and collect and remit sales taxes and lodging taxes.

(I) Marijuana [Brought from 7-3-18(J)]

- (1) The cultivation, manufacture, distribution, storage, or sale of marijuana shall not be a lawful use by right, accessory use (including as a home occupation), conditional use, or lawful nonconforming use in any zoning district of the Town of Ridgway, except as provided in this subsection (J).
- (2) A Medical Marijuana Center, Medical Marijuana Optional Premises Cultivation Operation, and Medical Marijuana-Infused Products Manufacturing Facility, licensed under Article 43.3 of Title 12 CRS, a Primary Care Giver registered under C.R.S. 25-1.5-106, and a Marijuana Cultivation Facility, a Marijuana Testing Facility, a Marijuana Product Manufacturing Facility or a Retail Marijuana Store licensed by the State of Colorado pursuant to Article XVIII, Section 16 of the Colorado Constitution and Article 43.4 of the Title 12, CRS, may be located within the I-1 and I-2 Zoning Districts and the General Commercial Zoning District east of Liddell Drive extended, as a use by right if they meet the following provisions:
 - (a) They must be operated lawfully under applicable provisions of State Law.
 - (b) They must comply with the performance standards of the I-1 and I-2 Zoning Districts, or General Commercial Zoning Districts, as applicable.
 - (c) They must have valid State and Town sales tax licenses and collect and remit sales tax on sales of Marijuana in accordance with State Law and Town ordinances.
 - (d) A Certificate of Occupancy for each building must be obtained prior to establishment of the use therein.
 - (e) The cultivation, manufacturing, storage, distribution and sale of Marijuana, must be confined to an enclosed building.
 - (f) They must be located in structures with commercial and industrial uses only, and are not allowed in buildings with residential uses.
 - (g) No storage facilities are permitted off the licensed premises.
 - (h) The building in which the licensed activities take place may not be located within 1,000 feet of a school, an alcohol or drug treatment facility, the principal campus of a college, university or seminary, or a residential childcare facility. The distance referred to shall be measured from the nearest property line of the land use for the above listed uses to the nearest portion of the building in which licensed activity takes place, using a route of direct pedestrian access. This restriction shall not affect the renewal or reissuance of a license

once granted, or apply to a license in effect actively doing business before any of the above uses was constructed.

- (3) Cultivation.
 - (a) A patient, validly registered under State Law, may cultivate Medical Marijuana at the patient's residence for the Patient's own use only, if in compliance with the limitations of State Law and if the plants cannot be seen or smelled off the premises.
 - (b) An individual may cultivate Marijuana at the individual's residence, only if in compliance with the limitations of Subsection (16)(3)(b) of Article XVIII of the Colorado Constitution and other applicable state law, including the requirement that the growing take place in an enclosed locked place, is not conducted publicly or openly and is not made available for sale.
 - (c) The use of a compressed flammable gas as a solvent in the extraction of THC or other cannabinoids in a residential setting is prohibited.
 - (d) Co-op or collective grow operations are not allowed without a state license.
- (4) Delivery of Marijuana, or Medical Marijuana by a licensed Medical Marijuana business, licensed Marijuana establishment, Primary Care Giver, or any other person, from a location outside of Town, to a location within Town, is allowed, only if lawful under, and in full compliance with State Law, and the delivering person has a Town sales tax license if taxable sales may occur, and collects and remits Town sales taxes on the sale of the delivered Marijuana and Medical Marijuana.
- (5) The below listed terms shall be defined as indicated for purposes of this subsection (J):
 - (a) "Medical Marijuana", "Medical Marijuana Center", "Optional Premises Cultivation Operation", and "Medical Marijuana-Infused Products, Manufacturing", shall have meanings as defined in CRS, Title 12, Article 43.3.
 - (b) "Primary Care Giver" shall have the meaning as defined in C.R.S. 25-1.5-106.
 - (c) "Patient" shall have the meaning as defined in Section 14(1) of Article XVIII of the Colorado Constitution.
 - (d) "State Law" shall include, but not be limited to, Section 16 and Section 14(1) of Article XVIII of the Colorado Constitution, C.R.S. 25-1.5-106, Article 43.3 and 43.4, Title 12, CRS; and any rules or regulations promulgated pursuant thereto.
 - (e) "Marijuana", "Marijuana Cultivation Facility", "Marijuana Testing Facility", "Marijuana Product Manufacturing Facility" or a "Retail Marijuana Store" shall have the meaning defined in Article XVIII, Section 16 of the Colorado Constitution, and Article 43.4, Title 12, CRS.
- (6) Storage of Marijuana off of the licensed premises is not permitted in the Town.
- (7) Marijuana clubs, businesses or other places of assembly where customers, members, or the like, are regularly invited for the purpose of using or consuming marijuana or marijuana products on site, are prohibited in the Town.
- (J) Manufactured Homes [Brought from 7-3-18(K)]
 - (1) Manufactured homes, as defined in Subsection 7-3-2, that have more than 500 square feet of living area, are only permitted on the following described property:
 - (a) All of Blocks 4, 9 and 29;
 - (b) Block 28, Lots 11 through 20;

- (c) Block 32, Lots 1 through 18;
- (d) Block 33, Lots 6 through 10; and
- (e) Lot 1 of Mitchell Subdivision No. 2.
- (2) The limitations of this subsection shall not apply to any manufactured home that was placed on a property not referenced in subsection (K)(1) above prior to June 9, 1993 in Ordinance 02-1993 that met all applicable building at safety codes at time of installation.
- (3) Manufactured Homes are subject to the provisions of Section 6-3, Regulations for Manufactured Homes, Travel Homes, and Other Factory-Built Housing.
- (4) Manufactured Home Parks are subject to the provisions of Section 8-1, Manufactured Home Park and Travel Home Park Regulations.

(K) Employee Housing [Brought from 7-3-18(L)]

The creation of employee housing is generally encouraged as an effective means to improve housing affordability and to support the viability and retention of employment generating uses, provided that each complies with the following standards.

- (1) Employee housing units are only allowed as accessory to a nonresidential use.
- (2) One employee housing unit is allowed for the first 2,500 square feet of gross floor area in the structure. Structures that exceed 2,500 square feet of gross floor area are allowed one additional unit per 2,500 square feet, up to a maximum of three units per nonresidential use.
- (3) The employee housing unit must be constructed in accordance with all applicable building and safety codes.
- (4) The employee housing unit must be owned together with the structure occupied by the nonresidential use, and the lot or parcel upon which they are located, in undivided ownership.
- (5) The employee housing unit must be served off of the water or sewer tap for the principal structure, in which case it shall not be subject to additional tap fees.
- (6) If the employee housing unit has been offered to current and prospective employees of the nonresidential use for 45 days after the prior tenant vacates and the unit remains vacant, the unit can then be offered to other households where at least one of the occupants is employed at an establishment located within Ouray County.
- (7) Short-term rental of employee housing is not permitted.
- (8) The burden shall be upon the owner of any employee housing unit to provide adequate proof to the Town that the criteria of this Section are met. In the event that the Town determines that the criteria have not been shown to be satisfied the unit may not be occupied as a residence.

(L) Parking Standards [Brought from 7-3-15]

(1) Off-Street Parking Requirements. The following off street parking requirements shall apply unless otherwise indicated in all districts, except the Historic Business District. The requirements for the Historic Business District are specified in subsection X-XX:

Use	Required parking spaces			
(a) Residences	Single-Family and Duplex: 2 spaces per dwelling unit.			
	All Other Residential: 1 space per dwelling unit			
(b) Medical offices and clinics	3 spaces per examination room			
(c) Hospitals	1 space for each 3 beds			
(d) Pharmacies	1 space per 200 sq. ft. of customer floor space			

(e) Bus stations	1 space per 400 sq. ft. gross floor area
(f) Funeral homes and mortuaries	1 space for each 6 seats in main chapel
(g) Restaurants and Lounges	1 space per 100 sq. ft. customer floor area
(h) Hotels and Motels	1 space per guest room
(i) Walk-up restaurants	1 space per 50 sq. ft. customer floor area
(j) Bowling alleys	3 spaces per lane
(k) Gas stations	4 spaces, plus 2 spaces for each enclosed auto space
(I) Beauty shops	2 spaces for each chair
(m) Industrial uses	1 space for every 2 employees on shift plus adequate
	visitor parking
(n) Churches	1 space for each 6 seats in main chapel
(o) Nursing homes	1 space for each 3 beds
(p) Professional office space	1 space per 300 sq. ft. gross floor area
(q) Retail establishments	1 space per 250 sq. ft. gross floor area
(r) Studio residence	1 space per unit (600 sq. ft. total living area)
(s) Day care facilities not qualifying	1 space for each 10 children plus 1 drop off space,
as an accessory use	plus one space per staff person
(t) All other uses	1 space per 350 sq. ft. gross floor area

- (2) Parking spaces shall be sized and designed in accordance with standard Town specifications and shall be a minimum of eight feet by 20 feet in size.
- (3) Maneuvering Area: Off-street parking shall provide sufficient off-street space to allow an automobile to enter, maneuver, and exit without backing onto any public street. Backing onto alleyways is permissible except where otherwise prohibited by plat note.
- (4) For purposes of this Subsection, "gross floor area" is the heated square footage of a building measured along the outside enclosing walls, excluding interior parking areas and outdoor common areas; "customer floor area" is the aggregate amount of internal floor area generally used by the public, or 15 percent of the total floor area, whichever is greater.

(M) Fence, Hedge, and Wall Regulations [Brought from 6-4-1]

- (1) No fence, rail or freestanding wall shall exceed six feet in height within the Town, except for those located within the I-1 and I-2 Light Industrial Districts which may not exceed eight feet in height.
- (2) In the Residential and Historic Residential Zoning Districts, fences, rails or freestanding walls located within the area between the property line and the front set back line may not exceed four feet in height, except for fences designed and intended to exclude deer may be up to six feet high if they are substantially transparent at sight angles up to 45 degrees from perpendicular to the faces of the fence, and are constructed out of a:
 - (a) Mesh;
 - (b) Woven wire;
 - (c) Rails and pickets or similar components which have a width no greater than their depth.
- (3) No fence, freestanding wall or hedge or other plantings shall be constructed or maintained on corner lots in a place or at a height which unreasonably creates a traffic hazard by obstructing vision from vehicles on abutting streets.

- (4) Electrically charged fences are not allowed within the Town unless their location is made inaccessible to persons who would not know that the fence is electrified by virtue of another fence or structure.
- (5) Barbed wire fences may be allowed only I-1 and I-2 Light Industrial Districts, and only if the barbed wire is a minimum of six feet above the ground. No barbed wire fence may be maintained in other districts unless necessary to confine livestock lawfully kept within the Town.
- (6) All fences shall be maintained in good and safe condition.
- (7) Enforcement
 - (a) It shall be unlawful for any person to violate any provision of this Section.
 - (b) Any violation of the provision of this Section is hereby declared to be a nuisance and may be abated in accordance with law.
 - (c) In addition to any of the remedies the Town may have, it may maintain an action in a court of competent jurisdiction to enjoin any violation of, or compel compliance with, any of the provisions of this Section.

(N) Outdoor Lighting Regulations [Brought from Ch. 6, Sec. 5]

- (1) General Provisions
 - (a) All non-exempt outdoor light fixtures and illuminating devices permanently or temporarily installed outdoors, including, but not limited to, devices to illuminate signs, shall meet the following requirements:
 - (i) They shall be shielded so no light rays are emitted at angles which will allow the light to pass directly off of the premises appurtenant to the fixture.
 - (ii) They shall be shielded so that no light rays are emitted by the installed fixture at angles below the horizontal plane.
 - (iii) All fixtures designed to illuminate signs or structures shall be mounted above the area of the sign or structure to be illuminated.
 - (iv) Blinking, flashing, rotating or moving lights are prohibited.
 - (v) Correlated color temperature (CCT) is limited to 3,000 kelvin per fixture.
 - (vi) The following lumen limits are established to prevent over lighting and are not intended to be achieved. Each site should use the lowest amount of lumens needed for the site to provide safety and functionality.
 - a. Single-Family Residential Sites shall be limited to 5,100 lumens. Single Family Residential Sites that include an accessory dwelling unit shall be limited to 6,500 lumens. Each lighting fixture shall be limited to 850 lumens.
 - b. Multifamily Residential Sites, Mixed Use Sites and Nonresidential Sites shall be limited to 25,000 lumens per net acre plus 2,000 lumens per unit beyond the first. Each lighting fixture shall be limited to 1,500 lumens.
 - (vii) Lighting for all nonresidential uses shall be extinguished one hour after close of business unless there is a public safety hazard that is best mitigated by the use of lighting. Lighting intended for security purposes shall use Adaptive Controls.
 - (viii) If any of the above are in conflict with the Town building codes adopted pursuant to Municipal Code Section 6-1, the regulations of the adopted building code shall apply.

- (b) The following are exempt from the provisions of subsection (1).
 - (i) Lights used to illuminate athletic fields of other community special event areas. Such lights shall be turned off one hour after the conclusion of the event and should be designed or placed to minimize light falling beyond the area in use.
 - (ii) Signs which are illuminated by interior light sources, such as neon signs, provided such signs are lit only during the property owner's business hours.
 - (iii) Official traffic control devices and lights owned and operated by or pursuant to proper authority of the United States of America, the state of Colorado or any of their agencies, and such other lights as are specifically required by federal or state law.
 - (iv) Official traffic control lights owned and operated by the Town of Ridgway.
 - (v) Repealed by Ordinance 16-2006.
 - (vi) Lawful vehicle lights.
 - (vii)Repealed by Ordinance 10-2007.
 - (viii) Holiday lights. Holiday lights should only be in use from November 15 to January 31.
 - (ix) Artwork that is outdoors and on public property. Such artwork shall receive a permit by the Town of Ridgway prior to installation. Such artwork shall be public and accessible to all people and may be illuminated, pursuant to the following:
 - a. Artwork shall not contain lighting that exceeds 500 lumens within the entire structure, nor more than 2,500 degrees kelvin.
 - b. All public art that is illuminated shall include a dimmer and timer to aid the compliance with the Dark Skies Association's Outdoor Lighting Requirements, and shall have the ability to be automatically turned off. In any event such lighting shall be automatically turned off by 10:00 p.m. nightly.
 - c. No structure may contain lighting that is cast upward or outward, but may be diffused in a way such that the lighting emits a soft glow.
 - d. All structures shall be lit internally.
 - e. All illuminated public art is subject to review and approval by Town staff for compliance with these regulations.
- (c) Public Outdoor Lighting.
 - (i) New public lighting owned and operated by the Town of Ridgway, including street lights, walkway lights, external building lights, holiday lights and other lights to ensure safety, shall be allowed as recommended by the Town Manager in situations where a public health hazard exists which can only be mitigated by artificial light at night and shall be in compliance with subsection (A).
 - (ii) Adaptive controls or curfews shall be employed in all new public outdoor lighting installations.
 - (iii) All Town owned lighting shall comply with the requirements of Section 6-5 within five years from the effective date of this Section.
- (2) Noncompliant Lights
 - (a) Lights which were lawfully existing and in use at the time they became nonconforming with the requirements of this Section X-X by virtue of the initial adoption of this Section,

subsequent amendment to this Section or by annexation into the Town, may continue to be used and operated subject to the limitations of this Section.

- (b) The right to operate a lawful nonconforming light shall terminate upon any of the following:
 - (i) Replacement of the light fixture.
 - (ii) Non-use of the light fixture for a period of six months.
 - (iii) Damage to the light fixture so that the cost of repair is 50 percent or more of the cost to replace it with a conforming fixture.
- (c) The right to exceed the lumen limits established in Subsection X-X-X as a lawful nonconforming site shall terminate upon any of the following:
 - (i) Replacement of 50 percent or more of the light fixtures on the site.
 - (ii) Damage to the light fixtures so that the cost of repair is 50 percent or more of the cost to replace them with conforming fixtures.
- (d) No alteration may be made to lighting on a site which would increase the amount or degree of the nonconformity.
- (3) Administration and Enforcement
 - (a) The provisions of this Section shall be administered by the building official or other authorized Town officer or employee.
 - (b) It shall be unlawful to violate any provision of this Section.
 - (c) Any continuing violation of this Section is hereby declared to be nuisance, which may be abated by the Town in any lawful manner, or enjoined by a court of competent jurisdiction.
 - (d) No building permit or occupancy permit shall be issued for work which has noncomplying light fixtures.

7-4-6 SIGN REGULATIONS

(A) Compliance Required

It shall be unlawful to erect or maintain any sign except in conformity with the requirements of this Subsection. Signs not in conformity with the provisions of this Subsection are hereby declared to be a nuisance which may be abated by the Town in any lawful manner.

(B) Signs Allowed Without a Permit

The following may be erected, maintained and used without a sign permit as long as they are properly maintained in accordance with the requirements of this paragraph (B) and paragraph (F) and with other applicable requirements of this Subsection, State law and Town ordinances and regulations, and are not prohibited by paragraphs (C) or (D)

- (1) Official traffic control devices, signs, and notices erected, owned and maintained by the United States, the state of Colorado, the Town of Ridgway or any of their political subdivisions for official governmental purposes.
- (2) Any pennant, motto, or insignia of any nation, state, political subdivisions, religious, civic, or fraternal organization, or school except devices which are used to promote business activity.
- (3) Works of art unless they are used to promote business activity.
- (4) Temporary decorations, displays and banners which are customarily displayed and associated with holidays or celebrations and banners associated with Town endorsed civic events.

- (5) Scoreboards, unless used to advertise business activity.
- (6) Public utility warning signs, construction warning signs, and signs warning of other hazards, with no sign face larger than ten square feet in area.
- (7) Identification signs incidental to the use of vehicles attached to the vehicle.
- (8) Traffic control devices with no sign face larger than three square feet.
- (9) One or more temporary signs with an aggregate sign face area of no more than four square feet in the Residential and Historic Residential Zoning Districts and 16 square feet in all other zoning districts, for the premises upon which they are located. Signs identifying a project and contractors involved therein shall only be allowed during the construction period. All "for sale" signs shall be taken down when the sale of the premises is closed.
- (10) One bulletin board per street frontage not over 20 square feet in area for the purpose of announcing events of civic interest, which is owned and maintained by a charitable or religious institution.
- (11) Memorial signs and tablets, or cornerstone signs identifying the building and its date of construction. Such signs shall be cut into masonry surface, inlaid so as to be part of the building or constructed of incombustible materials.
- (12) Signs upon vending machines, gasoline pumps, or packages of goods which relate to the contents thereof.
- (13) Temporary signs advertising Town approved civic events during the period of the event. All such signs may be erected only with the approval of the Town Council except for those displayed in Town Parks which may be approved by Town Administrative Staff.
- (14) Signs within buildings which are located no closer than six inches to any window or which are not legible from distances of five feet or more.
- (15) Temporary signs on the Ridgway School Ball Field fence, provided they do not face Highway 62, that they are only up during baseball season, and that all such signs be controlled and administered by the Ridgway School Administration.
- (16) Signs devoted to noncommercial speech which do not exceed ten square feet in area.

(C) Prohibited Signs and Devices

The following are hereby prohibited within the Town:

- (1) Animated or flashing signs visible outside any building.
- (2) Balloons, or pennants, or other wind-powered devices designed to attract attention, except they may be used for civic events up to a maximum of seven days.
- (3) The operation of search lights to promote business activities.

(D) Off-Premises Signs Restricted

A sign may identify or advertise only that activity or use conducted upon or related to the premises upon which the sign is located except in the following circumstances:

- (1) Directional signs owned by the Town. The expense of construction and maintenance shall be charged to the businesses or organizations advertised.
- (2) Signs authorized pursuant to subsection X-XX.
- (3) Signs allowed by paragraphs (B)(1), (4), (10), and (13).
- (4) Signs with a message devoted solely to non-commercial speech.

(5) Tourist oriented directional signs owned and erected by the Colorado Department of Transportation pursuant to C.R.S. 43-1-420(3), which meet conditions set out in Town resolutions as in effect from time to time.

(E) Permits

- (1) Except for the signs specified in paragraph (B), no sign may be erected and maintained until a Sign Permit has been issued by the building official. Applications for a standard sign permit issued pursuant to this subsection X-XX shall be submitted to the Town on forms supplied by the Town accompanied by an application fee of \$35.00. Applications for permits issued pursuant to subsection X-XX, for signs erected over Town-owned streets and alley rights-of-way pursuant to a revocable right-of-way permit, shall be submitted to the Town on forms supplied by the Town accompanied by an application fee of \$75.00.
- (2) The Building Inspector shall grant a permit only for signs which will be in compliance with the requirements of this Subsection.
- (3) The total sign face area of signs required to have a permit per property, other than those restricted by subsection (6), shall not exceed the lesser of one square foot per foot of lineal street frontage of the property abutting Town streets or 150 square feet. When more than one building/and or business is on the property, the property street frontage shall be allocated among the buildings and/or businesses accordingly, unless otherwise approved through a Master Sign Plan. Total sign face area in excess of 150 square feet shall not be allowed for any property unless approved through a Master Sign Plan applicable to that property.
- (4) A Building Permit is also required for any sign with a cost or value over \$1,000.00
- (5) No permit for a sign shall be allowed in the Residential Districts.
- (6) The total sign face area of signs required to have a permit for businesses within the Downtown Services Zoning District shall not exceed 12 square feet per business. All signs within said District shall be non-illuminated and attached to the building structures, no higher than the roof line.

(F) Performance Criteria

All signs shall meet the requirements of this paragraph (F) whether a permit is required or not.

- (1) All signs shall be maintained in good, legible and safe condition.
- (2) No sign shall be erected or maintained which creates a traffic or other safety hazard.
- (3) All signs shall be constructed and maintained in accordance with any applicable provisions of the Town's building codes.
- (4) All signs shall be erected and maintained in accordance with applicable requirements of State law.
- (5) No part of any sign shall be above the roof or parapet of the highest building on the property and no higher than 35 feet. No part of any freestanding sign shall be higher than 20 feet above finished grade.
- (6) No sign may be erected or maintained which creates a public or private nuisance, or which unreasonably interferes with the reasonable enjoyment of the adjacent property by reason of unreasonable light, shade or other effects.
- (7) No sign shall be larger than 32 square feet in area, except a freestanding sign with more than one business advertised may have a sign face up to 56 square feet, unless approved through a Master Sign Plan applicable to the building. No sign shall have more than two sign faces.

- (8) Signs may be erected only on property which the sign owner has a legal right to erect such sign.
- (9) All temporary signs must comply with the size restrictions set forth in subsection X-XX. Portable or wheeled signs displayed outside of buildings must be located so as to not impede with vehicular or pedestrian traffic, or create a traffic hazard or safety hazard or other nuisance, and must be removed at times when the advertised use or activity is not open for business.
- (10) No more than 50 percent of any sign face may be internally illuminated.
- (11) Materials. Signs lit with a dark-skies compliant external source are recommended over internally lit signs. A "halo" type sign, which uses solid letters with a light source behind them, illuminating the wall around the letters, are acceptable. If internally illuminated signs must be used, illumination of letters and graphics is allowed; however, illumination of the background is prohibited.

(G) Signs in Public Rights-of-Way

Signs, other than signs belonging to the Town or sponsored by the Town, conforming to size limits of this Subsection 7-3-17, may be erected over Town-owned streets and alley rights-of-way pursuant to a revocable right-of-way permit issued pursuant to either paragraph (1) or (2) of this subsection only on the following conditions, in addition to other applicable requirements of this Subsection:

- (1) Projecting signs:
 - (a) The sign must be supported and attached to a building.
 - (b) The sign may extend no more than five feet from the building. If the sign is printed on a retractable awning, the awning may extend no more than ten feet from the building. A sign may extend no more than five feet across Town owned right-of-way. If the sign is printed on a retractable awning, the awning may extend no more than ten feet across Town owned right-of-way.
 - (c) No part of the sign may be less than ten feet above the ground over Town right-of-way, except for a sign printed on an awning, the awning shall be at least seven feet above the ground.
 - (d) That portion of any sign face located over the Town right-of-way shall be no larger than 20 square feet in area.
 - (e) No more than one sign per business may extend over the Town right-of-way.
 - (f) No sign with its face parallel to the wall of the building to which it is attached, except for those printed on an awning, may extend more than 12 inches from the building, nor more than 12 inches over public property.
 - (g) Plans for signs over Town rights-of-way must be submitted with applicable fee, reviewed and approved by the Town Administrative Staff.
 - (h) The revocable permit may be revoked by the Town at any time for any reasonable reason.
 - (i) Proof of insurance shall be provided to the Town.
 - (j) The sign may identify or advertise only that activity or use conducted upon or related to the abutting premises.
- (2) Portable signs:
 - (a) The sign may identify or advertise only that activity or use conducted upon or related to the abutting premises.

- (b) No more than one sign per business may be placed on Town right-of-way.
- (c) The proposal for a portable sign on Town right-of-way must be submitted with applicable fee, reviewed and approved by the Town Administrative Staff.
- (d) The revocable permit shall specify the authorized location, and may be revoked by the Town at any time for any reasonable reason.
- (e) Proof of insurance shall be provided to the Town.
- (f) The sign must be located so that it does not interfere with Town use, impede vehicular or pedestrian traffic, or create a traffic or safety hazard or other nuisance.
- (g) The sign must be removed at times when the advertised use or activity is not open for business.

(H)General Provisions

- (1) The area of a sign face shall include the surface area of a sign, including non-structural trim and decoration, but excluding supports or uprights. The face area of a sign painted or hung on a wall of a building, or on an awning, shall include all the area within a perimeter surrounding all words, symbols, designs and coloring, distinctive from the wall upon which it is painted. Only one side of double-faced signs that convey the same message on both faces shall be included for purposes of this calculation.
- (2) As used in this Subsection, "sign" means and includes any object, device, or message which is used to advertise, identify, display, direct, attract attention, or convey any message concerning any object, person, institution, organization, business, products, service, event, or location by any means, including words, letters, figures, designs, symbols, fixtures, colors, motion, illumination, or projection, and anything else commonly known as a "sign".

(I) Nonconforming Signs

- (1) All signs shall at all times be maintained in strict conformity with the performance criteria of paragraphs (F)(1), (2), (3), (4), (6) or (8). All Master Sign Plans previously approved by the Town under subsection 7-3-12(J) prior to April 15, 2019 shall be maintained in strict conformity with such Town approval. Any signs not in compliance with these specific performance criteria and/or Master Sign Plans approved prior to April 15, 2019 shall be removed.
- (2) All signs shall at all times be maintained in strict conformity with the performance criteria of paragraph (F). Any sign not in compliance with paragraph (F) shall be removed.
- (3) The right to maintain a nonconforming sign shall be terminated and the sign removed or brought into full compliance with this Subsection under the following conditions:
 - (a) Abandonment of the sign, abandonment or termination of the related business, an interruption in continuance of the business for six months.
 - (b) A violation of any of the performance criteria of paragraph (F)(1), (2), (3), (4), (6) or (8).
 - (c) The destruction of the sign, removal of the sign or damage of the sign, such that the cost of replacement or repair is greater than 50 percent of the replacement cost of the original sign.
 - (d) The creation of any additional violation of or nonconformity with these regulations.
- (4) A list of nonconforming signs shall be developed and maintained by the building inspector with owners notified and given a copy of paragraph (I).

(J) Master Sign Plans

- (1) Purpose: To provide flexibility for the amount of signage and size of signs for multi-tenant buildings and developments to ensure signage is available for business and facility wayfinding and identification. To protect the health, safety and welfare of the community while preserving Town aesthetics.
- (2) Applicability:
 - (a) A Master Sign Plan shall be encouraged for all properties with multi-tenant buildings and/or multiple buildings in which three or more nonresidential tenants or businesses are present.
 - (b) Any property with multiple-tenant buildings or multiple buildings in which three or more nonresidential tenants existing at the time of adoption of this Section that does not have a Master Sign Plan is encouraged to apply for a Master Sign Plan at the time of application for a new sign at the site.
 - (c) Any property owner with multi-tenant and/or multiple buildings in which two or more nonresidential tenants or businesses are present, may apply for a Master Sign Plan.
- (3) General Regulations:
 - (a) All signs subject to a Master Sign Plan shall apply for and receive a sign permit before any sign may be installed.
 - (b) All signs on the site shall conform at all times to the approved Master Sign Plan and other applicable sign regulations.
 - (c) Master Sign Plan shall run with the property for which it was issued and not with individual tenants or businesses.
 - (d) Applications for a Master Sign Plan shall be submitted to the Town on forms supplied by the Town accompanied by the fee per Subsection X-XX. At a minimum the applicant shall submit the following information to the Town:
 - (i) Identification of the property for which the Master Sign Plan application shall apply;
 - (ii) Proof of property ownership, or partial ownership, and signatures from all property owners included in the proposed Master Sign Plan;
 - (iii) Total sign area allowed per Subsection X-XX and the total sign area requested with the Master Sign Plan;
 - (iv) Site plan showing location of all existing and proposed signs on property, with distance from property lines;
 - (v) Building elevations/pictures showing location of all existing and proposed signs on property, with height of all signs from the ground;
 - (vi) Dimensions and type of all existing and proposed signs, including the unit number/address for each;
 - (vii)Any proposed lighting for the signs, including location, type, kelvin and lumens for each fixture;
 - (viii) Proof that the criteria for approval have been met.
 - (e) Through these Master Sign Plan regulations the following deviations from the specified dimensional requirements may be considered.
 - (i) A free-standing sign may be up to 30 percent larger than the 56 square feet limitation of subsection X-XX.

(ii) Up to 30 percent more than the allocated square footage per subsection X-XX of sign area may be allowed.

Deviations shall not be considered for any other sign regulations in the Ridgway Municipal Code.

- (4) Criteria for Approval of the proposed Master Sign Plan:
 - (a) Will not be contrary to the public health, safety or welfare;
 - (b) Will not create traffic hazards;
 - (c) Provides for adequate assurances of safety from natural conditions such as wind, snow and ice as it relates to the proposed signs;
 - (d) Will not unreasonably interfere with neighboring commercial businesses or properties;
 - (e) Provides for signs that are reasonably necessary to operate the business or businesses on the property;
 - (f) The burden shall be on the applicate to show that these criteria have been met.
- (5) Review Procedure:
 - (a) Within 14 days of receipt of a completed application accompanied by the applicable fee for a Master Sign Plan, or a minor change to an existing Master Sign Plan, the Town will administratively approve or deny the application according to the Criteria for Approval. It shall not be necessary for the Town to provide written findings or conclusions, except upon request of the applicant.
 - (i) To the extent an application for a Master Sign Plan or minor change is denied in whole or in part, the requesting party may appeal to the Planning Commission as set forth in paragraph (5)(b) of this subsection. Such appeal shall be in writing and submitted within seven days of the Towns decision and review shall be de novo.
 - (b) Within 14 days of receipt of a completed application accompanied by the applicable fee for a major change to a Master Sign Plan, or an appeal of a denial of a Master Sign Plan, or minor change to a Master Sign Plan, the Planning Commission will set a hearing:
 - (i) The hearing shall be heard at the next regularly scheduled Planning Commission meeting for which proper notice of the hearing can be made, and no later than 40 days after receipt of a completed application accompanied by the applicable fee for a major change to a Master Sign Plan, or an appeal of a denial of a Master Sign Plan, or minor change of a Master Sign Plan. A hearing that must be continued due to time constraints or other delays, may be continued for an additional seven days beyond the 40-day deadline, assuming the hearing was commenced within the 40-day deadline. By mutual agreement, the applicant and the Planning Commission may also extend the 40-day and seven-day deadlines set forth in this subsection.
 - (ii) At the scheduled hearing, the applicant and other interested parties may appear and present such evidence and testimony as they may desire. Anyone presenting evidence or testimony shall be subject to cross-examination by other interested parties, although the Planning Commission may limit testimony, evidence and cross-examination which is merely cumulative and is not required to follow any set procedure during the hearing, nor strictly follow the Rules of Evidence as applied by the Court. The hearing should be tape recorded or otherwise electronically recorded. The application, or other interested party may, if so desires, have the hearing recorded by a court reporter, at the applicant's sole expense. The burden is upon the applicant in all cases to establish that the applicable criteria for any action are met.

- (iii) Notice of the hearing shall be posted at Town Hall at least ten days before the hearing, and posted visibly for each street frontage abutting the property for at least ten days prior to the hearing, in addition to any other notice required by Town regulations.
- (iv) The Planning Commission shall announce its decision according to the Criteria for Approval within 14 days of completion of the hearing. It shall not be necessary for the Planning Commission to provide written findings or conclusions, except upon request of the applicant, or other party appearing or participating in the in the hearing. The decision of the Planning Commission with respect to an application for major change of to a Master Sign Plan, or an appeal of a denial of a Master Sign Plan or minor change to a Master Sign Plan shall be final, subject only to review under Rule 106 of the Colorado Rules of Civil Procedure. Upon the filing of an appeal under Rule 106, the Town shall cause a transcript of any tape recording of the hearing to be made and certified to the court, and the party filings such appeal or such review, shall pay the Town the reasonable cost incurred in producing such transcript, unless such party has a transcript produced by a court reporter at the applicant's expense.
- (v) The Planning Commission may approve the requested action only upon finding that all applicable criteria and requirements of these Master Sign Plan regulations or other Town ordinances have been met. If it determines such criteria have not been met, the application shall be denied. The application may be granted upon conditions or limitations which the Planning Commission determines are necessary in order to ensure that the applicable criteria are met. Such conditions or limitations shall be provided to the applicant and interested parties in writing as part of the decision, subject only to review under Rule 106 of the Colorado Rules of Civil Procedure.
- (6) Amendments to Approve Master Sign Plans:
 - (a) Minor Changes: Minor changes are those changes that do not alter the overall characteristics of the existing Master Sign Plan and that create no adverse impacts on adjacent uses, infrastructure, or public safety. Examples of what may be considered a minor change include, but are not limited to:
 - (i) Changes in the location of a sign;
 - (ii) Replacement of existing signs that are the same size or smaller than the existing sign; and
 - (iii) Changes in the number of signs, as long as the aggregate square footage remains the same.
 - (b) Major Changes: Major changes are those that can alter the overall character of the Master Sign Plan and which could create adverse impacts on adjacent uses or public infrastructure. Examples of what may be considered a major change include, but are not limited to:
 - (i) Changes in the total square footage of the Master Sign Plan; and
 - (ii) Requests for deviations per subsection X-XX.

7-4-7 LANDSCAPE REGULATIONS

(A) Intent

(1) The purpose of this Section is to provide clear landscaping requirements that will contribute to high quality development and sustainable, water-saving practices. Landscaping is an important element of the character of the Town of Ridgway that is both functional and aesthetic and the Town's top objective is to prioritize low-water use and regionally appropriate design for materials and vegetation. These landscaping regulations will endeavor to achieve the following:

- (a) Preserve and enhance a well-maintained landscape that preserves the overall quality and character of the community.
- (b) Conserve water resources.
- (c) Provide visual buffers and screening.
- (d) Provide separation between pedestrian and vehicular uses.
- (e) Mitigate adverse effects of drainage and weeds.
- (f) Allow residents creativity and flexibility and landscape design.
- (2) Drought-tolerant, water-wise plants are to be used whenever possible and appropriate. Water wise is a term used throughout this chapter to describe the method of planting which works to promote water conservation by minimizing the amount of native vegetation removed, limiting new vegetation to native and drought tolerant species, limiting the amount and type of irrigation, and other related measures to conserve water and create a native landscape.
- (3) Landscaping should be used to promote the visual aesthetic of the development from main travel corridors, as well as the pedestrian experience within, through shade trees, plantings, context-appropriate public art and seating. Buffers and medians facilitate drainage during storm events and provide valuable areas for snow storage during the winter. Landscaping that is sustainable, visually appealing, and regionally appropriate is required for all new development.

(B) Applicability

- (1) This chapter establishes minimum landscaping standards which apply to all residential and nonresidential properties within the Town of Ridgway.
- (2) The following projects shall comply with the landscaping standards set forth in this chapter:
 - (a) Projects which require a site plan review;
 - (b) New commercial, residential, or mixed use construction;
 - (c) New landscape projects and rehabilitation projects that exceed 25 percent of the lot size;
 - (d) Change of use; or
 - (e) Public rights-of-way improvements.
- (3) A building permit for new construction or landscape improvements shall not be issued until a conforming Landscape Plan is approved by the Town. A permanent Certificate of Occupancy will not be issued until the Town determines that the landscaping contemplated by the approved plan has been properly installed. A temporary Certificate of Occupancy may be issued if completion of landscaping improvements is delayed by winter weather.
- (4) All standards and policies adopted within the Town of Ridgway Water Conservation and Management Plan, Master Plan, and Commercial Design Guidelines should be implemented with the landscape regulations of this chapter.

(C) Site and Landscape Plan Development

- (1) Landscape Plan Requirements.
 - (a) A landscape plan, as set forth in this Section, shall be required for all projects identified in subsection X-XX and shall be submitted to the Town for approval.

- (b) The landscape plan shall be drawn to scale of one inch equals 40 feet, or larger, and may be included on the Site Plan. The landscape plan shall include the following information:
 - (i) Property lines and dimensions;
 - (ii) Building footprint, driveways, and vehicle circulation;
 - (iii) Existing and finished grade;
 - (iv) North arrow and scale;
 - (v) Name of applicant and landscape consultant or architect (if applicable);
 - (vi) Legend indicating all proposed plant materials with common and botanical names, indication of drought tolerant plants, sizes, maximum spacing, caliper size, and quantities;
 - (vii)Method of establishing and maintaining plant materials;
 - (viii) Surface drainage characteristics and any proposed structures, including, but not limited to, inlets, retention/detention ponds, swales, permeable surfaces, down spouts;
 - (ix) Location of all plant material, other natural features, including, but not limited to, wetlands, water bodies, rock outcroppings, detention areas, retaining walls, and buildings and paved areas (existing and proposed);
 - (x) Plantings should be shown as they would be at full maturity;
 - (xi) Identification and percentage of ground surfaces and materials by types, such as paving, sod, mulch, edger, seed mixes, shrubs, and flower beds;
 - (xii)Clearly labeled locations and calculations for amounts of required landscaping, including the square footage and percentage of required landscape area, living materials, and non-living materials as well as required and provided number of trees, drought tolerant plantings, and any required landscaping, including islands and trees, within parking areas;
 - (xiii) Identify any existing trees, shrubs, or live groundcover that will remain on the property and how they will be protected from damage during construction;
 - (xiv) The location and square footage of all areas;

(xv)Identify construction debris storage and staging areas; and

(xvi) Additional information as may be required by the Town.

(D) Water Conservation

- (1) Water Conservation Planting: All landscaping should be designed to incorporate water conservation materials and techniques through application of water wise landscape principles. In general, water wise landscaping and drip irrigation are required while large irrigated areas requiring spray heads are strongly discouraged.
- (2) Regionally Appropriate: All landscaping should be regionally appropriate and materials shall be suitable for local soil conditions and climate. To help guide plant selection, a list of recommended and prohibited species is included in Subsection X-XX, Species List.

(E) Landscaping Required

- (1) Purpose: The purpose of this section is to establish minimum landscaping requirements for residential, non-residential and mixed uses.
 - (a) All areas on a lot must be treated with landscaping.

- (b) Landscaped area may include a combination of trees, shrubs, groundcovers (live and nonlive), decorative landscape stone or rock, or other landscaping material that does not conflict with other provisions of this Chapter.
 - (i) Live ground cover is considered to be material such as native grasses wildflowers, turf and planting beds.
 - (ii) Non-live ground cover is considered to be material such as bark mulch, flagstone, rock, gravel, artificial turf or the like.
 - (iii) The minimum live and non-live ground cover percentages, as seen in the landscaping requirements table, count as part of the overall minimum landscaped area, not in addition to.
- (2) At least 25 percent of the required landscape area shall be provided in the front yard of the property. The landscaping requirements table below demonstrates the required landscape area for all parcels in all zoning districts.

Landsca	aping Require	ments						
Zoning District	Min. Required Landscaped Area ²	Min % of Required Landscaped Area Live Ground Cover	Min. % of Required Landscaped Area Non-Live Ground Cover	Min. # of Trees for Required Landscaped Area ³	Min. # of Shrubs for Required Landscaped Area ⁴			
Resider	ntial Uses	-						
R	50%	20%	30%	1 for every 2,000 sq. ft.	2 for every 3,000 sq. ft.			
HR	40%	20%	20%	1 for every 2,000 sq. ft.	2 for every 3,000 sq. ft.			
MR	30%	20%	20%	1 for every 2,000 sq. ft.	2 for every 3,000 sq. ft.			
FD1	50%	20%	30%	1 for every 2,000 sq. ft.	2 for every 3,000 sq. ft.			
DS	50%	20%	30%	1 for every 2,000 sq. ft.	2 for every 3,000 sq. ft.			
Non-Re	esidential or M	ixed Uses						
НВ	See X-XX(C) Below							
GC	30%	10%	20%	1 for every 2,000 sq. ft.	2 for every 3,500 sq. ft.			

Landscaping Requirements								
Zoning District	Min. Required Landscaped Area ²	Min % of Required Landscaped Area Live Ground Cover	Min. % of Required Landscaped Area Non-Live Ground Cover	Min. # of Trees for Required Landscaped Area ³	Min. # of Shrubs for Required Landscaped Area ⁴			
I-1	30%	5%	15%	1 for every 2,500 sq. ft.	2 for every 4,000 sq. ft.			
I-2	30%	5%	15%	1 for every 2,500 sq. ft.	2 for every 4,000 sq. ft.			

¹See subsection X-XX (B) for exemptions for uses that are non-residential in the FD zoning district.

² For all residential uses that are single-family and duplex dwellings, a maximum of one acre of area shall be used to calculate the minimum required landscape area.

³ The minimum number of trees are a sum total of all required trees. Any additional tree requirements (such as street trees) shall be counted as part of this minimum number of required trees.

⁴ Four shrubs can be counted for one required tree. A minimum of one tree is always required per lot.

- (3) Historic Business (HB) District: This district is intended to provide for zero lot lines and full lot coverage. Therefore, there is no minimum required landscaped area as defined in this chapter. However, the following shall apply:
 - (a) Right-of-way landscaping shall be required pursuant to Subsection X-XX.
 - (b) If a parking lot is provided on-site, parking lot landscaping shall be required pursuant to Subsection X-XX.
 - (c) Required landscaped area for properties zoned HB is required for any area not used for a building or parking lot.

(F) General Landscape Standards

- (1) Trees: Trees shall have a minimum caliper of one and one-half inches for deciduous trees and a five-foot minimum height for evergreens. In the case of fractional requirements for the number of trees, the number required shall be rounded up to the next whole number. Existing trees that are in good health, as determined by the Town Manager, shall be counted as one and one-half trees for the minimum tree requirement.
- (2) Shrubs: Shrubs shall be a minimum five-gallon size. Decorative grasses are to be counted as shrubs. In the case of fractional requirements for the number of shrubs, the number required shall be rounded up to the next whole number.
- (3) Groundcover: Area can be made up of vegetative materials, organic or inorganic mulch, flowerbeds, or other acceptable landscape material. Groundcover must be adequate to ensure that dust cannot blow from the property and that the soil is stabilized to ensure that erosion is kept to a minimum, it must also remain free of noxious weeds as defined as Ouray County Weed Manager.

- (4) Turf: No more than 1,500 square feet or ten percent of the required landscaped area, whichever is less, can be high water turf. High water turf should only be used in areas of high use. Native, non-irrigated grass may be used in area of low use, low visibility areas.
- (5) Species Diversity: To prevent uniformity and insect or disease susceptibility, species diversity is required, and extensive monocultures of trees are prohibited. Species diversity does not apply to existing trees. The following requirements shall be met:

Number of required trees on site	Maximum percentage of any one species
1—5	No diversity
6—19	33%
20 or more	25%

- (6) Irrigation: To ensure best practices for water conservation, all new landscaping shall comply with the following irrigation standards:
 - (a) Irrigation should be limited to between the hours of 6:00 P.M. and 9:00 A.M.
 - (b) All irrigation systems shall be automatic and have moisture sensors installed.
 - (c) Where possible, non-potable irrigation systems should be used to irrigate landscape.
- (7) Screening and Buffering:
 - (a) Screening and landscape buffers soften the less desirable impacts of development and can provide a certain element of safety in commercial areas where significant pedestrian interactions are more likely to occur. Buffers should be constructed to mitigate the view, light pollution (including light trespass and glare), noise, heat, and odor impacts of vehicles, pavement, and higher intensity uses, and other potential negative effects of development.
 - (b) Buffering shall be provided when a non-residential use is adjacent to a residential use. It shall be the responsibility of the non-residential use to provide the adequate buffer from the residential use in a manner consistent with these regulations. The buffer should include a mix of trees, fencing, landscape berms, and other materials appropriate to mitigate visual, audible, and other impact the non-residential use may have on the residences.
 - (c) Mechanical Equipment: Ground mounted or rooftop equipment, shall be screened from public rights-of-way on all sides to its full height. Ground level mechanical equipment shall be screened with landscaping, berms, fences, or architectural walls. Rooftop units shall be screened with materials and colors to match the building.
 - (d) Storage Areas: All open storage areas shall be screened from public rights-of-way and adjacent property by use of landscaping, berms, fencing, or a combination of landscaping and other structural elements to a height of six feet.
 - (e) Fencing can be used as a method for screening and buffering, provided the fencing meets the requirements of Section X-X.
 - (f) Additional landscape screening above the minimum requirements of this Section may be required when it is determined by the Town Manager, Town Manager's designee, Planning

and Zoning Commission, or Town Council to be in the best interest of the affected properties.

- (8) Sight Triangles: All plant material, walls, fences, berms and/or structures shall not exceed 24 inches in height when located on any corner within a triangular area formed by the curb lines and a line connecting them at points 15 feet from the intersection of the curb lines.
- (9) Existing Plantings: Existing trees, shrubs, and live groundcover that are in good health should be retained and not destroyed during the construction process. The health of the trees shall be determined by the Town Manager. These plants will be counted towards the required landscaping.
- (10) Revegetation: Development activities should only disturb, clear, or grade the area necessary for construction. All areas disturbed by grading or construction, not being formally landscaped, shall be revegetated with native seeding and/or other approved plant materials in a method acceptable to the Town.
- (11) Slopes: Removal of existing vegetation, including ground cover and trees, is strongly discouraged on slopes greater than 30 percent. Development on slopes greater than 15 percent shall maintain the maximum vegetative cover possible to protect soils, prevent land slippage, and retain wildlife habitat and open space resources. A minimum of 50 percent of vegetation on slopes greater than 15 percent shall not be disturbed during development.
- (G) Parking Lot Landscape Standards
 - (1) Islands or Rain Gardens: A landscape island and/or rain garden shall be provided in parking lots along the ends of the parking rows. Islands for parking lots in residential uses shall be used to separate rows of six or more parking spaces and shall include a minimum of one tree. For nonresidential uses, islands shall be used to separate rows of 12 or more parking spaces and shall include a minimum of two trees. Islands shall be a minimum of six feet wide and as long as the adjacent parking space(s).
 - (2) Trees shall be incorporated with parking lot design as to provide parking lot shading.
 - (3) Catchment areas: Landscaped or grassed catchments areas and similar designs should be used for managing, controlling and filtering parking lot and site drainage and should be included as part of an overall site drainage plan.

(H) Right-of-Way Landscape Standards

(1) Street trees: A landscape area shall be established along the public right-of-way for all non-residential uses and shall be a minimum of five feet wide. Such trees shall be placed in the center of the landscape area, not within the site triangle, and 20 feet away from any streetlight. A minimum of one tree per 50 linear feet of right-of-way is required. Street trees shall have a minimum caliper of two and one-half inches for deciduous trees and a six-foot minimum height for evergreens.

(I) Exceptions or Deviations

- (1) Affordable Housing: Landscaping requirements for affordable housing projects may be reduced, based on the determination of the Town Manager. Whenever possible, deviations from these standards for the purpose of preserving affordable housing or deed restricted housing should be identified and provided for in the appropriate document establishing the affordability and/or deed restricted provisions for the projects.
- (2) Non-Residential Uses on Properties Zoned FD: If the proposed use in the FD zone district is intended to be permanent, these landscape standards shall apply. If, however, an existing use is intended to be redeveloped, the Town Manager may waive these requirements until such time the property redevelops. Such decision is the sole discretion of the Town Manager.

- (3) High-Water Turf: High-water turf may be allowed in areas of high-water use such as drainages, swales, or downspout locations.
- (4) Administrative approval for deviations from a required standard: Deviations from the landscape requirements for up to ten percent may be considered for administrative approval by the Town. To request a deviation, a letter explaining the unique situation or hardship preventing the project from meeting the minimum landscape requirements shall submitted to the Town Clerk and will be at the sole discretion of the Town Manager for approval.

(J) Species List

- (1) Preferred Species: A list of recommended species for use in Colorado is available from the Ouray Country Weed Manager and the Colorado State University Extension Service. The lists are not all inclusive but do recommend a variety of plants known to do well in our region of Colorado. In general, plants that are not recognized as hardy or suited to the local climate should be kept to a minimum. Water wise, drought-tolerant plants are to be used whenever possible and appropriate and regionally appropriate species are preferred.
- (2) Prohibited Species.
 - (a) Siberian elm and Chinese elm (Ulmus); Cottonwoods that bear cotton (Populus); Purple Loosestrife (Lythrum slaicaria); Russian Olive (Elaeagnus angustifolia); and Kentucky Blue Grass (Poa pratensis) are prohibited.
 - (b) The Town Manager is authorized to prohibit additional species with similar nuisance properties.

(K) Installation Standards

- (1) Living materials shall be adequately watered and maintained to become established. Once established watering requirements should be minimized.
- (2) Trees should also be installed in such a way that they will not infringe on solar access, views from the adjoining properties, or block a sight distance triangle.
- (3) Easements shall remain clear of all obstacles which may prevent such easement from operating within its intended purpose.
 - (a) Retaining walls are prohibited from being located in any established easement.
 - (b) Trees may only be permitted in utility easements upon written approval of the easement holder.

(L) Maintenance Requirements

- (1) Following completion of the landscaping, the owner or occupant of the property shall maintain it in good condition thereafter. Failure to so maintain the landscaping is unlawful and is hereby declared to create a nuisance.
- (2) Where approved trees, shrubs, or other landscaping materials die or are removed, it shall be the responsibility of the property owner to replace them with materials of a comparable nature and size to those originally approved. This continuing obligation shall continue until the property is redeveloped at which time the redeveloper shall comply with the requirements of this Chapter as they apply to the proposed development at that time.

(M) Enforcement

(1) Any violation of this Chapter shall be a violation of the Ridgway Municipal Code and shall be enforced pursuant to Chapter 2, Section 4, Administrative Enforcement of the Ridgway Municipal Code.

7-4-8 RESIDENTIAL DESIGN STANDARDS

(A) Legislative Declaration

Ridgway is defined in part by architecture and neighborhoods that vary in age and character. A goal of the Town's Master Plan is to create a well-integrated community that meets the needs of residents of various income levels, ages and stages of family life cycles. One way of achieving this is to encourage a mix of housing types and densities, rather than segregating them into separate districts. In accomplishing this, it is acknowledged that the visual appearance of a property affects more than just the property involved. New and altered structures impact the surrounding neighborhood both in character and property value. These standards have been adopted to encourage a mix of housing types, while helping to ensure that this will not be detrimental to the character of the neighborhoods or to property values in general.

(B) Applicability

- (1) Unless otherwise excepted, the regulations set out in this Section 6-6 shall apply to:
 - (a) Construction of any residential building, including without limitation construction of Single-Family, Duplex, Townhouse, Triplex, Fourplex, Cluster Housing, Co-Housing, Multiple-Family structures, and Accessory Dwelling Units;
 - (b) New residential subdivisions;
 - (c) Major additions or renovations to an existing residential structure;
 - (d) Structures that contain only residential uses that are included as part of a mixed-use development.
- (2) Once subjected to these requirements, all residential development and appurtenant sites shall thereafter be maintained in conformity with these requirements.

(C) Exceptions

These regulations shall not be applicable to manufactured homes, as defined in Subsection X-XX and subject to supplemental standards in subsection X-XX.

(D) Development Standards

- (1) Foundations:
 - (a) The foundation must enclose the space beneath the perimeter of the structure. Foundations may be constructed of masonry or concrete.
 - (b) Perimeter foundations and all supports under the structure must meet the frost depth as required in Section 6-1.
 - (c) All foundations and interior supports shall be poured on undisturbed or compacted soil.
 - (d) All portions of foundations that are above the adjacent finished grade by more than six inches shall be finished using the same siding materials as the dwelling or complementary materials such as stucco, stone or brick. Cosmetically equivalent split faced block or other block with design finish or other materials may be allowed with prior approval of the Town.
 - (e) Unfinished masonry blocks, plywood, other materials or earth backfill that exceeds a grade of two-foot horizontal for each one foot of raise are not permitted.
 - (f) Exceptions to the above standards may be allowed where foundations must be stepped to address a slope in the natural grade of the site. However, such deviations to these standards shall be kept to the minimum required to address the specific site condition.

(2) Exterior Siding:

- (a) Exterior siding shall be made of non-reflective metal or vinyl lap, wood, simulated wood grain products, painted or colored stucco, brick, stone, or any combination of these materials, or other cosmetically equivalent materials with prior approval of the Town.
- (b) Materials intended to be painted or finished in any manner, such as wood products or stucco, shall not be accepted until painted or finished.
- (3) Roof Structure:
 - (a) Provide varied roof forms or roof forms that are compatible with those used on adjacent homes.
 - (b) Sloped roofs must have an overhang at the eaves and gable ends of not less than 12 inches excluding rain gutters measured from the vertical side of the dwelling. This required overhang shall not apply to areas over porches, alcoves and other appendages, which together do not exceed 25 percent of the length of the façade on which they are located. Flatter roofs are permitted only if any equipment on the roof is screened from view from each street on which the lot fronts, and from abutting lots, provided, however, that screening that would interfere with the efficient operation of rooftop solar equipment shall not be required.
 - (c) A-frame designs are not permitted.
 - (d) Mansard roofs are only permitted if the base of the roof is above the second story of the structure.
- (4) Sidewalks: Sidewalks shall be installed in accordance with Town specifications along the adjoining street frontages prior to issuance of a Certificate of Occupancy unless the Town allows execution of a recordable covenant to participate in an assessment district, in cases where immediate construction is not practical.
- (5) Mechanical Equipment:
 - (a) Propane storage tanks shall not be placed in the front or street side yard unless placed underground. Propane tank placement must also meet applicable code requirements, which in most cases require that the tank be no less than ten feet from any property line and ten feet from any building.
 - (b) Swamp coolers, AC units, heat pumps and other mechanical equipment shall not be placed in the front yard. When placed in the street side yard, mechanical equipment should be screened from view from the street using landscaping, walls or fences which are complimentary to the building design.
- (6) Street Address Number: Each residence shall display the street address number in a location that is easily visible from the street with each character not less than four inches nor more than eight inches in height.
- (7) A landscaping plan pursuant to RMC X-X, shall be submitted for all new residential plans as required by Subsection X-X.
- (8) Additions to Existing or New Homes: Any additions or exterior remodeling shall respect the architectural character, detailing, lines and proportions of the existing structure. Additions shall be so integrated into the existing structure that they are difficult to identify as being added and shall appear to have been a part of the original design of the structure. A "face lift" on the existing building may be used in accomplishing this result. Attached or detached garages, carports, patio covers or walls should be designed in the same architectural style as the main structure and be built of similar or compatible materials.

(E) Architectural Standards

- (1) The design of all new residential development and major additions shall meet each of the following architectural design objectives. Corner lots shall meet these objectives on both the front and side street elevations.
 - (a) Provide relief and contrast to the building's front and side street elevations incorporating solids and voids to break up plain wall surfaces.
 - (b) Provide variation of building mass and height, responding to the existing development context and adjacent zoning districts.
 - (c) Garage doors shall not dominate the front elevation.
 - (d) No two detached Single-family dwellings, Duplex dwelling structures, Townhome, Triplex dwelling structures, or Fourplex dwelling structures of substantially similar elevations shall be located adjacent to each other.
- (2) The Town Manager or his/her designee shall promulgate design guidelines to provide assistance in meeting these requirements.

(F) Deviations

- (1) The Planning and Zoning Commission may approve deviations from one or more of the requirements of this Section 6-6 on the basis of finding that:
 - (a) The proposed structure will be compatible and harmonious with structures in the immediate vicinity; and either
 - (b) The proposed architecture or construction standards provide compensating features that meet the intent and objectives of these standards; or
 - (c) The proposed structure(s) support(s) the expansion of workforce housing options within the Town of Ridgway.
- (2) Requests for deviations shall be reviewed pursuant to the procedures of Subsection 7-3-23, subject to the fees set in Subsection 7-3-25.

(G) Enforcement and Administration

- (1) The Town Manager or his/her designee shall be responsible for the interpretation, administration and enforcement of the provisions of these regulations, as amended, and of any decisions entered by the Planning and Zoning Commission, Board of Adjustment or Town Council, pursuant to such section.
- (2) No building permit, occupancy permit, or other permit or license shall be issued, nor shall any other action of approval be taken or allowed by the Town for any property which is not in compliance with the provisions of these regulations and any decision issued pursuant hereto.
- (3) Whenever necessary to make an inspection to enforce any of the provisions of these regulations or any provision of a decision entered, pursuant to this Subsection, or whenever there is reasonable cause to believe that a violation of any provision of these regulations or of any decision issued pursuant to this Subsection exists, the Marshal, Town Manager, or their authorized representative shall have the right to enter upon such building or premises at all reasonable times for purposes of inspection or to perform any other duty imposed by this Subsection. Prior to entry, he shall identify himself and request permission to enter from the occupant or person in charge of the premise if they can be found by reasonable efforts. If entry is refused, he shall have recourse to any remedy provided by law to secure entry.

- (4) The Town may maintain an action in a court of competent jurisdiction to enjoin any violation of these regulations or of the terms of any decision entered pursuant to this Subsection. In the alternative, the Town may issue an administrative citation under Section 2-4.
- (5) It shall be unlawful to violate any of the provisions of these regulations, or the terms of any decision entered pursuant to this Subsection. Any person convicted of such a violation may be punished by a fine of up to \$300.00. Each day any violations continues shall constitute a separate violation.
- (6) Continuing violations of this Subsection, or the terms of any decision issued pursuant to this Subsection, are hereby declared to be a nuisance and may be abated in any lawful manner.
- (7) In addition to the fees contained in this Chapter 6, the applicant shall reimburse the Town for all out-of-pocket costs incurred during the review including legal fees, postage, notice and publishing costs, map costs, engineering fees, etc., together with wages and associated payroll costs for contract employees, plus ten percent to cover overhead and administration. The Town shall bill the applicant periodically as such costs are incurred. Payment is due within 30 days. Bills not paid by the due date shall accrue interest at the rate of one and one-half percent per month or part thereof. No plat shall be recorded, improvement accepted, lien released, building permit issued, tap approved or other final approval action taken until all fees then due are paid to the Town. Such fees may be certified to the County Treasurer for collection as delinquent charges against the property concerned.

7-4-9 REGULATIONS FOR MANUFACTURED HOMES, TRAVEL HOMES, AND OTHER FACTORY-BUILT HOUSING. [Brought in from Ch. 6, Sec. 3 and Ch. 8, Sec. 1]

(A) Manufactured Home Park Design Requirements.

- (1) Manufactured home parks may be located only where allowed by Town Zoning Regulations, and shall be a minimum of two acres.
- (2) All manufactured home parks shall, as a minimum, comply with the regulations for manufactured home parks issued by the State of Colorado and the requirements of this Section. In the event of any conflict between the State regulations and the requirements of this Section or other ordinances and regulations of the Town, those regulations which are more stringent shall apply.
- (3) Each manufactured home space may have only one manufactured home located on it and shall comply with the dimensional requirements of this Subsection. All spaces shall be adequately identified by a number or letter.
 - (a) Minimum Lot area: 2,500 square feet.
 - (b) Minimum Setbacks:
 - (i) Front: Ten feet.
 - (ii) Rear: Eight feet.
 - (iii) Side on Corner Space: Seven and one-half feet.
 - (iv) Side: Five feet.
 - (c) Accessory structures which are not attached to the manufactured home are not subject to the rear and side yard setbacks, but shall be set back a minimum of two feet.
- (4) The manufactured home park developer shall provide the following improvements:
 - (a) A Town water system to serve each lot, including fire hydrants and fire mains.

- (b) A sanitary sewer system.
- (c) Fifty-foot wide streets with a minimum paved width of 30 feet.
- (d) A storm drainage system.
- (e) Street signs, streetlights.
- (f) Concrete valley pans four feet in width, or curbs, gutters and four-foot wide sidewalks shall be installed on each side of each street.
- (g) A park or playground occupying at least five percent of the area of the manufactured home park to be maintained by the manufactured home park owner.
- (5) Arrangements to provide public utilities, including, if available, gas, electricity, telephone and cable television, shall be made with the utility companies for service to each space.

(B) Travel Home Park Design Requirements

- (1) Size and Location: Travel home parks may be located only where allowed by Town Zoning Regulations and shall be a minimum of two acres in area.
- (2) All travel home parks shall, as a minimum, comply with applicable State of Colorado Regulations for campgrounds and recreation areas and the requirements of this Subsection. In the event of any conflict between State Regulations and the requirements of this Section or other Town ordinances or regulations, those regulations which are more stringent shall apply.
- (3) Dimensional Requirements:
 - (a) All travel homes and any accessory structures shall be at least ten feet from any other travel home and accessory structure.
 - (b) The number of travel homes in the park shall not exceed 25 travel homes per acre.
- (4) Eight percent of the gross area of the travel home park, or 2,500 square feet, whichever is greater, shall be developed and maintained as a park or playground by the park owner.
- (5) The travel home park developer shall provide the following improvements:
 - (a) A water system, including fire hydrants and fire mains.
 - (b) A sanitary sewer system.
 - (c) Paved streets with a minimum paved width as follows:
 - (i) One-way/no parking: 11 feet
 - (ii) One-way/parking on one side: 18 feet;
 - (iii) Two-way/no parking: 24 feet;
 - (iv) Two-way/parking on one side: 27 feet;
 - (v) Two-way/parking on both sides: 34 feet.
 - (d) A storm drainage system.
 - (e) Street signs and security lights.
 - (f) A service building meeting the requirements of applicable State and Town regulations.
- (6) Plans for all improvements shall be submitted with the site plan and shall be approved by the Town prior to the approval of any licenses by the Town Council. All required improvements shall comply with Town design and construction standards and specifications.

- (7) Easements: The Town may require reasonable utility easements to be dedicated to the public for the purpose of public and Town utilities.
- (C) Maintenance of Manufactured Homes and Travel Home Parks
 - (1) All manufactured home parks and travel home parks shall be maintained in accordance with the requirements of this Section, applicable State of Colorado Department of Public Health and Environment Regulations, and other applicable regulations of the Town or State.
 - (2) The Town Manager or designee, shall have the right to enter upon any manufactured home park or travel home park at any reasonable time for the purpose of inspecting the premises to determine compliance with this Section or other applicable ordinances and Town and State regulations.

(D) Nonconforming Manufactured Home Parks and Travel Home Parks

- (1) Any manufactured home park or travel home park which at the effective date of this Section, or at the time of annexation, if annexed subsequent to the effective date of this Section, which was lawfully existing and maintained in accordance with previously applicable County or Town regulations and ordinances, but which does not conform or comply with all of the regulations provided for in this Section, may be continued to be maintained and used only in compliance with the provisions and limitations imposed by this Subsection in addition to the limitations of Sections 6-3 and 7-X. Manufactured home parks, or travel home parks which were unlawful or illegal and not in compliance with previously applicable regulations shall remain unlawful and illegal and subject to abatement or other enforcement action. All manufactured home parks and travel home parks shall comply with applicable State regulations immediately.
- (2) If the manufactured home park or travel home park is nonconforming with respect to dimensional requirements or other general requirements of the design standards of this Section, the following provisions shall apply:
 - (a) If the nonconformity is abandoned, removed or corrected for any length of time, such nonconformity may not be reestablished.
 - (b) No alteration may be made which would increase the amount or degree of the nonconforming feature. Changes may be made which would decrease the degree or amount of deviation from the requirements of this Section.
 - (c) If any existing manufactured home is removed from a site or space within or without a manufactured home park, no manufactured home may be moved onto such site or space which would have the effect of increasing the degree or amount of the nonconformity with this Section.

(E) Administration and Enforcement

- (1) The Town Manager or designee shall administer and enforce this Section.
- (2) It shall be unlawful for any person to violate any provision of this Section.
- (3) Any person convicted of a violation of any of the provisions of this Section shall be punished by a fine of not more than \$300.00. Each day during which any violation is committed or permitted to continue shall be considered to constitute a separate offense.
- (4) Any violation of the provisions of this Section is hereby declared to be a nuisance and may be abated in accordance with law.
- (5) In addition to any other remedies the Town may have, it may maintain an action in a court of competent jurisdiction to enjoin any violation of or compel compliance with any provision of this Section.

(6) The Town may refuse to issue any permits required by Town ordinance or grant water or sewer taps if the applicant is in violation of any of the provisions of this Section.

7-4-10. NONCONFORMING USES [Brought in from Sec. 7-3-20]

- (A) Any use, building or structure which at the effective date of this Section or at the time of annexation, if annexed subsequent to the effective date of this Section, was lawfully existing and maintained in accordance with the previously applicable County or Town Regulations and Ordinances but which does not conform or comply with all of the regulations provided for in these Zoning Regulations, may continue to be maintained and used as a lawful nonconforming use only in compliance with the provisions and limitations imposed by this Subsection. Uses, structures or buildings which were unlawful or illegal and not in compliance with previously applicable Regulations shall remain unlawful, illegal, and subject to abatement or other enforcement action.
- (B) If a use, building or structure is lawfully nonconforming in that it is not a "Use By Right", or a "Conditional Use" which has been approved pursuant to the review provisions of Subsection X-XX, the following shall apply:
 - (1) If the building, manufactured home or structure involved in the use is removed or if it is destroyed or damaged so that repair, replacement or reconstruction will cost more than 50 percent of the fair market value of the building, manufactured home or structure after repair, it shall no longer be lawful to use the building, manufactured home or premises except in compliance with the Use Regulations for the District within which it is located.
 - (2) If the nonconforming use is abandoned or discontinued for a period of six months, then the premises may only be used in compliance with the Use Regulations for the District within which it is located.
 - (3) The use may be continued only substantially as it existed at the effective date of this Section or of annexation, and no material change in the type of use shall be allowed, unless the Planning Commission determines, following the hearing procedure provided in Subsection X-XX, that the criteria set out in Subsection X-XX will be met, and that the new use is a more restrictive use than the existing nonconforming use. Any change in use allowed pursuant to this provision shall not affect the future status of the use as a nonconforming use for all purposes of this Subsection.
 - (4) The extent or area of the premises utilized for or by the nonconforming use, building or structure, may not be materially extended or enlarged, or substantially structurally altered, unless the Planning Commission determines, following the review procedure of Subsection X-XX, that the criteria set out in Subsection X-XX will be met.
- (C) If the use, building or structure is nonconforming with respect to dimensional requirements, design and performance standards, or other provisions not related to "use", the following provision shall apply:
 - (1) If the nonconformity of the building, use, or structure is abandoned, removed, or corrected, such nonconformity may not be reestablished.
 - (2) If the building, manufactured home or structure is damaged so that the cost of replacing or restoring it is greater than 50 percent of its fair market value after replacement, the building, manufactured home or structure may be repaired or replaced only in compliance with these Zoning Regulations.
 - (3) If the building or structure is damaged in such a way as to remove the nonconformity, the nonconforming feature may not be reestablished by any repair or reconstruction, unless it is unfeasible to repair the building without reestablishing the nonconforming feature.

- (4) No alteration may be made to the use, building, or structure which would increase the amount or degree of the nonconforming feature. Changes in the use, building, or structure may be made which will decrease the degree or amount of deviation from the requirements of this Section.
- (D) This Subsection shall not apply to signs. Nonconforming signs shall be governed by the provisions of Subsection X-XX.
- (E) Manufactured Homes and Factory-Built Housing:
 - (1) Notwithstanding the foregoing provisions of this Section, a lawful nonconforming manufactured home owned and occupied by the owner of the land upon which it sits may be replaced by another manufactured home to be owned and occupied by said owner if the Planning Commission determines following the review procedure of Section 7-3-23 that the criteria set out in Section 7-3-19 will be met, and that the replacement manufactured home will comply with all other applicable Town regulations including the provisions of Chapter 6-3.
 - (2) Notwithstanding any of the foregoing provisions of this Subsection 7-3-20 any Factory-Built Housing, which is nonconforming as to restrictions on use or design and performance standards, which for a period of six months is either unoccupied or does not have any authorized use of Town supplied water occur on the premises, shall be removed from the premises unless the structure has previously been issued a permit pursuant to Subsection 6-3 and it is erected on a permanent foundation complying with the requirements of the Town Building Code.

Chapter 7: Land Development Regulations

SECTION 5 – SUBDIVISION REGULATIONS

7-5-1. GENERAL PROVISIONS.

- (A) These Regulations shall be known and may be cited as the Town's "Subdivision Regulations".
- (B) These Regulations shall apply within the corporate limits of the Town.
- (C) The purposes of these Regulations are to:
 - (1) Promote and protect the public health, safety and welfare.
 - (2) To insure that new development bears its fair share of the cost of providing improvements and services resulting from the development of subdivisions.
 - (3) To set forth uniform procedures and standards for the handling of subdivisions.
 - (4) To insure adequate and safe public services such as water, sewer, fire protection, streets and storm drainage.
 - (5) To implement the Town's Master Plan and Development Regulations.
 - (6) To encourage development which limits hazards due to erosion, flood, soil conditions, and excessive slopes.
 - (7) To obtain land for parks, schools, and other public purposes.
 - (8) To protect the quality of the water, air and environment.
 - (9) To encourage energy conservation, use of solar energy, clustered development, and infilling.
 - (10) To encourage development which will not adversely affect adjacent property, or historical or recreational values.
 - (11) To discourage development inconsistent with existing services and infrastructures.
 - (12) To provide for safe and efficient flow of vehicles.
- (D) These Regulations shall not create any liability on the part of the Town or any officer or employee thereof arising from reliance upon these regulations or any administrative act or failure to act pursuant to these regulations.

(E) Interpretation

- (1) In interpreting and applying provisions of these Subdivision Regulations they shall be regarded as a minimum required for the protection of the public health, safety and welfare. They shall be liberally construed to further the purposes specified in Subsection X-XX above.
- (2) Whenever a provision of these Regulations and any other provision found in another Town ordinance or applicable law contains any restrictions or regulations covering the same subject matter, the restriction or regulation which is more restrictive or imposes a higher standard or requirement shall govern.

(F) Enforcement

(1) Whoever, being the owner or agent of the owner of any land located within a subdivision transfers or sells, agrees to sell, or negotiates to sell any land by reference to or exhibition of, or by use of a plat of a subdivision before such plat has been approved by the Planning Commission and recorded or filed in the office of the Ouray County Clerk and Recorder, shall pay a penalty of \$100.00 to the Town of Ridgway for each lot or parcel so transferred or sold, or agreed or negotiated to be sold. The description of such lot or parcel by metes and bounds in the instrument of transfer or other document used in the process of selling or transferring shall not exempt the transaction from such penalties, or from the remedies provided in this Subsection. The Town may enjoin such transfer or sale or agreement by action for injunction brought in any court of competent jurisdiction and may recover the penalty by civil action in any court of competent jurisdiction.

- (2) It shall be unlawful to erect, construct, reconstruct, use, or alter any building or structure, or to use any land in violation of any of these Subdivision Regulations or to otherwise violate any provision of these Subdivision Regulations or any provision of a Subdivision Improvements Agreement approved pursuant to these Regulations. Any person convicted of such a violation may be sentenced to a term of imprisonment not to exceed 90 days, or fined an amount not to exceed \$300.00, or be sentenced to both such fine and imprisonment; provided, however, no person under the age of 18 years shall be subject to any term of imprisonment, except for contempt of court. A separate offense shall be deemed committed during each day during which any violation continues.
- (3) No septic tank permit, building permit or occupancy permit shall be issued for the development of property with respect to which a violation of these Subdivision Regulations or a Subdivision Improvements Agreement approved pursuant to these Regulations has occurred until the violation has been remedied satisfactorily to the Town.
- (4) The Town may bring an action in a court of competent jurisdiction to enjoin or abate any violation of these Subdivision Regulations or of a Subdivision Improvements Agreement entered into pursuant to these Subdivision Regulations.

7-5-2 SUBDIVISION APPLICATIONS AND REVIEW PROCEDURES

This Section outlines the review procedures that are common to all applications regulated within Section 5, Subdivision Regulations, unless otherwise stated in these Land Development Regulations. Table XXX identifies the various application types and associated review procedures regulated by this article. The submittal requirements, review procedures, and approval criteria for each application type are laid out in subsequent sections of this article as identified in Table XXX. All documents and materials identified in this Section, and the particular application type section shall be required.

(A) Table XXX – Subdivision Application Types and Processes

	Pre- Application Meeting (§X.XX)	Completeness Review (§X.XX)	Referrals (§X.XX)	Notice of Hearing (§X.XX)	Town Manager or their designee	Planning Commission (§X.XX)	Town Council (§X.XX)
R=Required; O=Optional; PH=Required Public Hearing; Rec=Recommendation; D=Decision							
Minor Subdivision Plat (§7-5-XX)	R	R	R	R Posting	Rec	R PH / Rec	R PH / D
Major Subdivision (Section 7-5-XX)							
Sketch Plan (§7-5-XX)	R	R	R	R Posting		R PH / D	

Table XXX, Subdivision Application Types and Processes

Preliminary Plat (§7-5-XX)	R	R	R	R Posting	Rec	R PH / Rec	R PH / D
Final Plat (§7-5-XX)	0	R	R	R Posting	Rec	R PH / Rec	R PH / D
Resubdivisions							
Plat Amendments (§7-5-XX)	R	R	R	R Posting	Rec	R PH / Rec	R PH / D
Lot Splits (§7-5-XX)	R	R	R	R Posting	Rec	R PH / Rec	R PH / D
Boundary or Lot Line Adjustment (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Townhome (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Building Footprint (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Condominium (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Exempt Division of Land (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Lot Consolidation (§7-5-XX)	0	R	R	R Posting	Rec	R PH / D	
Replat (§7-5-XX)	0	R	R	R Posting	Rec		R PH / D
Right-of-Way Vacation (§7-5-XX)	0	R	R	R Posting	Rec		R PH / D

(B) General Application Review Procedures

The following procedures shall apply to all classifications of development applications which are required under this Chapter.

(1) Pre-Application Meeting.

If the applicant or Town Manager or their designee, requests a pre-application meeting, the following process shall be followed:

(a) Prior to the formal submission of the application, the applicant shall contact the Town Manager or designee to schedule and request an informal pre-application meeting. Following receipt of a request, the pre-application meeting should be set for a date within ten (10) days of the date of the applicant's request. The Town Manager or their designee shall advise the applicant of the date and time of the pre-application meeting.

- (b) The applicant shall be prepared to discuss the proposed application with the Town Manager or their designee. The applicant is encouraged to present such plats, plans, diagrams, or other preliminary information sufficient to permit the conceptual review of the proposed application.
- (c) The purpose of the pre-application meeting is to assist the applicant in understanding the town's application review processes and to permit the Town Manager or their designee to determine the applicable process(es) and regulations for the proposed application.
- (2) Application Submittal Requirements.

All of the following information and materials shall be submitted to the Town of Ridgway in a form acceptable to the Town Manager or their designee. Additional information and materials required to be submitted for specific application types identified in Table XXX are specified in subsequent sections of this Section and shall also be submitted in order to receive a determination of completeness.

(a) Basic Application Materials.

The following materials are required for all applications regulated by Chapter 7, Section 6, Subdivision Regulations, unless waived by the Town Manager or designee.

- (i) Application Form. An application form for the request shall be obtained from the Town of Ridgway. Completed application forms and accompanying materials shall be submitted to the Town by the owner or applicant.
 - a. Authorized Agent. If the applicant is not the owner of the land based on Ouray County Assessor records, the applicant shall submit a letter signed by the owner consenting to the submission of the application.
 - b. Applicant is Not the Sole Owner. If the applicant is not the sole owner of the land, the applicant shall submit a letter signed by all owners or an association representing all the owners, by which all owners consent to or join in the application.
- (ii) Fees. All application fees shall be in compliance with Section 7-1-6, Fees and Costs.
- (iii) Proof of Ownership. Proof of Ownership in the form of a copy of the property deed or a title commitment which has been issued within sixty (60) days of the application submittal along with copes of all documents listed in the exceptions.
- (iv) Legal Description. Legal description of the property subject to the development application.
- (v) Mineral Interest Owners. List of all mineral interest owners with interests severed from the subject property.
- (vi) Vicinity Map. A map locating the project limits, parcel(s), and property within Ridgway. The vicinity map shall clearly show the boundaries of the subject property and all property within a three-mile radius of the subject property.
- (vii) General Written Narrative. A general written narrative identifying the development team, existing conditions of the property, proposed uses, density, lot layout, end users, financing, public dedications (including rights-of-way, parks, open space, infrastructure), and describing the purpose of the project, how the request meets the applicable approval criteria, furthers the goals and objectives specified in the

Master Plan, and identifying any potential impacts on adjacent properties and public infrastructure and how those impacts are proposed to be mitigated.

(3) Completeness Review.

When a completeness determination is required pursuant to Table X-X.X, the following shall apply:

- (a) Within ten (10) days following receipt of an application, the Town Manager or their designee shall administratively review the application and determine whether it includes all the application content requirements of the Ridgway Municipal Code for the requested application type.
- (b) All plans, reports, maps and other information required for the application must be complete and legible A failure of the application to meet the requirements of the zoning regulations and this Ridgway Municipal Code may delay the processing of the application until the application is sufficient and complete.
- (c) When the Town Manager or their designee determines that the application is complete as submitted, the Town Manager or their designee shall schedule the application for review in accordance with the provisions set forth in this Section 5 Subdivision Regulations.
- (d) In the event the Town Manager or their designee determines that the application is incomplete, the Town Manager or their designee shall inform the applicant in writing of the deficiencies in the application. No further processing of the incomplete application shall be undertaken until the Town Manager or their designee determines that the applicant has remedied the application's deficiencies.
- (4) Referral Agencies.

In accordance with Table X-X.X, applications shall be referred to any of the below referral agencies the Town Manager or their designee determines is necessary to the complete and comprehensive review of the request. Referral of applications to other agencies shall be for a minimum time frame of fourteen (14) days. However, the time frame for review and comment may be extended if the application presents technical issues which require additional review, additional information is provided by the applicant, or the application is modified. Referral agencies include, but are not limited to, the following:

- (a) Bureau of Land Management (BLM)
- (b) Colorado Department of Transportation (CDOT)
- (c) Colorado Division of Reclamation, Mining & Safety
- (d) Colorado Division of Water Resources
- (e) Colorado Parks and Wildlife
- (f) Colorado State Forest Service
- (g) Ditch companies
- (h) Fire Protection District(s) or department(s)
- (i) Ouray County Departments (Assessor, Clerk & Recorder, Attorney, Health Department, Building Department, Road & Bridge, Sheriff Office, etc.) as appropriate
- (j) Town of Ridgway Departments (Town Clerk, Town Attorney, Engineering Department, Building Department, Public Works Department, Police Department, etc.) as appropriate
- (k) Water Conservation District(s)

- (I) San Miguel Power Authority
- (m) School district(s)
- (n) Soil Conservation District
- (o) Utility service providers and districts
- (p) US Army Corp of Engineers
- (q) US Environmental Protection Agency (EPA)
- (r) US Forest Service
- (s) Xcel Energy / Public Service of Colorado
- (t) Any other entity or agency deemed necessary by the Town Manager or their designee
- (5) Staff Report.

The Town Manager or their designee shall review the application to determine if the proposal satisfies the applicable standards. The Town Manager or their designee shall prepare a staff report discussing whether the applicable standards of the Ridgway Municipal Code have been satisfied. The staff report should identify issues raised through staff and referral agency review, potential mitigation requirements, any recommended conditions for approval, and any additional information pertinent to the review of the application.

(6) Notice Requirements.

All public notices of hearings required by these Subdivision Regulations shall include the date, time, place, and purpose of the hearing, a general description of the property affected, and any other information deemed appropriate to apprise the public of the general nature of the action proposed. Errors or inaccuracies in the notice shall not be deemed sufficient cause to postpone or invalidate a hearing except where such errors are substantive in material and are found to have reasonably mislead or misinformed the public.

(a) Notice by Posting

When notice by posting is required for a public hearing by Table X-X.X, notice of the hearing shall be posted at Town Hall ten (10) days before the hearing and posted, visible from each street frontage abutting the property, for at least ten (10) days prior to the hearing in addition to any other notice required by Town regulations.

- (i) Mineral Estates Notice. Per 24-65.5-103, C.R.S. if the surface estate and mineral estate are severed, the owners of severed mineral estates shall be entitled to notification of not less than thirty (30) days before the date scheduled for the public hearing for the application. A copy of the notice shall be given to the Town along with the applicant's certification of compliance with said notification requirements. Provided this notice is not required if notice was previously sent and such certification previously provided with respect to the same surface development, or the application is only platting an additional single lot, unless a mineral estate owner has requested notice pursuant to 24-6-402(7), C.R.S.
- (7) Public Hearings.

When an application requires a public hearing before the Planning Commission or the Town Council, in accordance with Table X-X.X, the following shall apply:

(a) The Town shall set the date and time of a public hearing. Notice of the public hearing shall be issued in accordance with Table X-X.X and Section XXX.XX, Notice Requirements.

- (b) At the public hearing, the reviewing body shall review the application for conformance with the applicable review standards and approval criteria for the request.
- (c) Any public hearing or other action of the body may be continued or postponed at any time to a specified date and time in order to permit preparation of additional information for further review by the reviewing body.
- (d) When required, the Planning Commission recommendation shall be forwarded to the Town Council. Following a public hearing, the Town Council shall approve, approve with conditions, or deny the application or continue the matter to a date certain.
- (e) The applicant shall bear the burden of presenting sufficient competent evidence at the public hearing to support the standards for approval set forth by this Ridgway Municipal Code. Any decision by the reviewing body to recommend, or to act to, approve, conditionally approve, or deny an application shall be based upon a consideration of all evidence presented during the public hearing. Where evidence presented is contradictory, the reviewing body shall weigh such evidence and judge the credibility and sufficiency of the evidence prior to rendering a decision.
- (8) Post Approval.
 - (a) Review. Prior to recording of the approved documents, the applicant shall submit all final documents reflecting any conditions of approval to the Town Manager or their designee for final review and acknowledgement.
 - (b) Recording. Any documents required to be recorded with the Ouray County Clerk and Recorder shall be fully executed by the applicant and filed for execution by the town and recorded. Recording of all documents shall be completed within a reasonable period of time from the date of approval by the approving body.
 - (c) Approval of Subdivision Improvement Agreement. A final plat shall not be filed for recording until the Board has approved an Improvement Agreement pursuant to this article.
 - (d) Effective Upon Recording. A plat does not become effective until it is properly filed for recording with the Ouray County Clerk and Recorder.
 - (e) Public Sale of Lots. A division of land becomes complete and eligible for public sale of lots and development only after the plat and associated approved documents have been properly recorded with the Ouray County Clerk and Recorder.

(C) Major Subdivision

(1) General Provisions.

Division of land applications which are defined as a major subdivision in Chapter 7-X-X, Definitions, shall be reviewed in compliance with the provisions of this Section X.XX(2), Review Procedures. Major subdivisions require three separate stages of approval:

- (a) Sketch Plan Review. The process for sketch plan review is set forth in Section X.XX, Sketch Plan Review.
- (b) Preliminary Plat. The process for preliminary plat review is set forth in Section X-XX, Preliminary Plat Review.
- (c) Final Plat. The process for final plat review is set forth in Section X-XX, Final Plat Review.
- (2) Review Procedures
 - (a) Sketch plan Review. The sketch plan review process is intended to review at a conceptual level the feasibility and design characteristics of the proposed subdivision based on the

applicable standards set forth in this Section 5, Subdivision Regulations, and Section 4, Zoning Regulations. The sketch plan review process is set forth in Section X-XX, Sketch Plan Review, and requires the following:

(i) Review Flowchart. Figure X, Sketch Plan Flowchart, depicts the sketch plan application review process described in greater detail in this section.

Figure X, Sketch Plan Flowchart

[Insert Flowchart]

- (ii) Pre-Application Meeting. A pre-application meeting may be held in accordance with the provisions set forth in Section X-XX, Pre-Application Meeting.
- (iii) Application Submittal Requirements. The following are the application materials required to be submitted for a sketch plan request. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.
 - a. Basic Application Materials. All materials set forth in Section X-XX, Basic Application Materials.
 - b. Sketch Plan. The applicant shall submit a copy of the sketch plan map at a size and scale legible and suitable for non-technical review of the proposal. The sketch plan map shall include the following information and supplemental materials. The Town Manager or designee may require, or the applicant may wish to submit, a more detailed version of all or part of the sketch plan map.
 - 1) A title clearly identifying the plat as a "Sketch Plan";
 - 2) Standard certificate blocks as provided by the town;
 - 3) Legal description of the property;
 - 4) North arrow, scale, and legend;
 - 5) A vicinity map at a suitable scale;
 - 6) Boundary lines, corner pins, and dimensions of the subject property, including land survey data to identify the parcel with section corners, distance and bearing to corners, quarter corners, township and range;
 - 7) Existing and proposed topographic contours at vertical intervals sufficient to show the topography affecting the development and storm drainage;
 - 8) Significant on-site features including: natural and artificial drainage ways, streams, ponds, waterways, wetland areas, irrigation ditches, hydrologic features and aquatic habitat; geologic features and hazards including slopes, alluvial fans, areas of subsidence, rock outcrops and rockfall areas, radiological and seismic hazard areas, soil types and landslide areas; vegetative cover; dams, reservoirs, excavations, and mines; and any other on-site and off-site features that influence the development;
 - 9) Existing and proposed parking areas, driveways, emergency turn-outs and emergency turnarounds, sidewalks, and paths and their dimensions;
 - 10) Existing and proposed roads, railroad tracks, irrigation ditches, fences and utility lines on or adjacent to the parcel and their dimensions;

- 11) Uses and grantees of all existing and proposed easements and rights-ofway on or adjacent to the property and their dimensions; and
- 12) Schematic and narrative representation of the proposed land use(s) including:
 - a) Existing and proposed zoning of land to be subdivided;
 - b) Total proposed subdivision area in acres and a percentage breakdown of areas devoted to specific land uses, with acreage and square footage, (e.g. percentage and area of residential development and/or nonresidential development; percentage and area of open space; percentage and area of parking and driveways, and so forth);
 - c) Approximate lot sizes;
 - d) Total number, size, general location, and type of proposed dwelling units;
 - e) Location, size, and use of major improvements;
 - f) Total number of square feet of proposed nonresidential floor space;
 - g) Off-street parking areas and anticipated number of spaces;
 - h) Recreation areas and open space;
 - i) School sites;
 - j) Approximate location of wastewater treatment system, including location and size of leach field, service lines, and treatment facilities to serve the proposed use;
 - k) Source and capacity of the water supply, including approximate location and size of well(s) and/or water lines to serve the proposed use;
 - Location and size of existing and proposed utilities and service facilities; and
- 13) Current and proposed grading and drainage patterns including:
 - a) Drainage arrows depicting surface flow;
 - b) Drainage facilities and improvements; and
 - c) A grading plan depicting existing and proposed site contours at two-foot intervals.
- c. Land Suitability Analysis. The land suitability analysis is a written analysis of conditions on-site and off-site which have an influence on the proposed use of the land. The land suitability analysis shall include the following information:
 - 1) A description of site features such as streams, areas subject to flooding, lakes, high ground water areas, vegetative cover, climatology, and other significant natural and man-made features;
 - 2) A description of the existing drainages and impoundments, natural and manmade;
 - 3) A description of soil characteristics of the site;
 - 4) A description of the geologic characteristics of the area including any potential natural or man-made hazards;
 - 5) A description of the topography and the slope determination;

- 6) A description of the source of water supply, the existing and future domestic and agricultural requirements, and the capacity of the source of water supply to meet existing and future requirements. The description shall include detail of historic irrigation, tailwater issues, and water demands;
- 7) A description of the relationship of the subject parcel to floodplains, the nature of soils and subsoils and their ability to adequately support waste disposal, the slope of the land, the effect of sewage effluents, and the pollution of surface runoff, stream flow and groundwater;
- 8) A description of the Floodplain and Flood Fringe designations affecting the subject property;
- 9) A description of the existing environmental conditions:
 - a) Existing flora and fauna habitat, wetlands, migration routes;
 - b) Significant archaeological, cultural, paleontological, and historic resource areas; and
 - c) Potential radiation hazard that may have been identified by the state or the Ouray County Public Health Department.
- 10) A description of the existing and historic use of adjacent property and neighboring properties within a 300' radius;
- 11) A description of all easements defining, limiting or allowing use types and access;
- 12) Access:
 - a) A description of historic public access to or through the site; and
 - b) A description of access to adjoining roads and sight distance and intersection constraints.
- d. Conceptual Landscape Plan. The landscape plan shall comply with all requirements in Section 7-4-7, Landscape Regulations.
- e. Supplemental Materials. The following items are required to be submitted to the Town of Ridgway:
 - 1) Conceptual drainage plan or study calculating historic and proposed surface and stormwater flows and how such flows will be managed.
 - 2) Conceptual traffic statement or study identifying current and proposed traffic counts and proposed trip generation along with any needed or anticipated improvements to mitigate the projects use on the public transportation network and infrastructure.
 - 3) Proof of minimum guaranteed water supply appropriate for the requested use.
 - a. Additional Requirements
- f. Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.
- (iv) Completeness Review.

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section X.XX, Completeness Review.

(v) Evaluation by Staff and Review Agencies.

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section X.XX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

(vi) Staff Report.

A staff report shall be prepared and provided to the reviewing body in accordance with Section X.XX, Staff Report.

(vii)Review and Action by the Planning Commission.

The Planning Commission shall review the sketch plan application in a manner consistent with Table XXX to evaluate compliance with applicable standards. The final decision to approve, approve with conditions, or deny a conditional use permit shall be made by the Planning Commission in a manner consistent with Table XXX and be based upon the criteria set forth in Section XXX, Approval Criteria.

- a. The Planning Commission may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to making a final decision.
- (b) Preliminary Plat Review. The preliminary plat review process will consider the feasibility and design characteristics of the proposed subdivision based on the applicable standards set forth in Article 7-5-XX, Design Standards. The preliminary plat process will also evaluate preliminary engineering documents.
 - (i) Review Flowchart. Figure X, Preliminary Plat Flowchart, depicts the preliminary plat application review process described in greater detail in this section.

Figure X, Preliminary Plat Flowchart

[Insert Flowchart]

- (ii) Pre-Application Meeting. A pre-application meeting may be held in accordance with the provisions set forth in Section X-XX, Pre-Application Meeting.
- (iii) Application Submittal Requirements. The following are the application materials required to be submitted for a preliminary plat request. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.
 - a. Basic Application Materials. All materials set forth in Section X-XX, Basic Application Materials.
 - b. Preliminary Subdivision Plat. The preliminary subdivision plat shall contain the following information submitted to the Town of Ridgway on 24" x 36" sheets at a scale suitable for technical review of the application.
 - 1) A title clearly identifying the plat as a "Preliminary Subdivision Plat";
 - 2) Standard certificate blocks as provided by the town;
 - 3) Legal description of the property;
 - 4) North arrow, scale, and legend;
 - 5) A vicinity map at a suitable scale;

- 6) The name and address of the owner(s) of record of the land being platted and the same information for the applicant(s), if other than the owners;
- 7) The name, address, and seal of the certifying registered land surveyor and the other individuals preparing the preliminary plat;
- 8) The township, range, section and quarter section(s);
- 9) Location and full description of all monuments as required by this article and by Title 38, Article 51, C.R.S.:
 - a) Permanent monuments shall be set on the external boundary of the subdivision pursuant to §38- 51-101, C.R.S. and
 - b) Block and lot monuments shall be set pursuant to §38-51-101, C.R.S.
- 10) Information adequate to locate all monuments shall be noted on the plat;
- 11) The location, layout, dimensions, areas, and uses of all lots and blocks numbered consecutive.
- 12) The location, layout, dimensions, areas and uses of all outlots and tracts labeled consecutively by letters and include a table identifying ownership and maintenance responsibilities.
- 13) Site data in chart form presenting:
 - Total area of the proposed subdivision; total area of the developed buildings, driveways and parking areas; total area of non-residential floor space;
 - b) Total number of proposed lots; breakdown of the lot total by number of lots per use (i.e. residential use, business or commercial and industrial use, and other public and nonpublic uses);
 - c) Total number of proposed off-street parking spaces;
 - d) Total number of dwelling units; total number of dwelling units per structure proposed; and
 - e) Total gross density proposed.
- 14) Boundary lines, corner pins, and dimensions of the subject property, including land survey data to identify the parcel with section corners, distance and bearing to corners, quarter corners, township and range;
- 15) Topography at the following minimum contour intervals:
 - a) Subdivision with one or more lots less than two (2) acres in size, topography shown at two (2) foot contour intervals.
 - b) Subdivision with all lots two (2) acres or greater in size, topography shown at five (5) foot contour intervals.
 - c) Areas having slopes thirty (30) percent or more, or other significant topographic conditions, topography shown at five (5) foot contour intervals.
- 16) Significant on-site features including: natural and artificial drainage ways, streams, ponds, waterways, wetland areas, irrigation ditches, hydrologic features and aquatic habitat; geologic features and hazards including slopes, alluvial fans, areas of subsidence, rock outcrops and rockfall areas, radiological

and seismic hazard areas, soil types and landslide areas; vegetative cover; dams, reservoirs, excavations, and mines; and any other on-site and off-site features that influence the development;

- 17) Known, identified or designated one hundred (100) year flood plains and localized areas subject to periodic flooding. The distance between the mean identifiable high water mark of any creeks, streams or rivers and the nearest proposed development within the site shall also be shown;
- 18) Existing and proposed parking areas, driveways, emergency turn-outs and emergency turnarounds, sidewalks, and paths and their dimensions;
- 19) Public Access to the site, and internal circulation. Location, dimension, alignment and names of all existing and proposed streets, drives, alleys and roads on or adjoining the property. The general location and right-of-way width for all arterials and collectors shall be shown;
- 20) The location of any preliminary engineering for any existing or proposed wastewater systems, water mains, culverts, storm drains, sidewalks, gutters, fire hydrants along with the width and depth of pavement or subgrading to be provided, the depth of burial of all underground lines, pipes and tubing and typical cross sections of the proposed grading of roadways and sidewalks;
- 21) Uses and grantees of all existing and proposed easements and rights-of-way on or adjacent to the property and their dimensions; and
- 22) The location, use and gross square footage of proposed structures within the subdivision;
 - a) Anticipated number of employees for proposed commercial or industrial uses.
- 23) Building envelopes in hazardous areas to protect trees and other natural resources, if deemed appropriate by planning staff;
- 24) Location and layout of lots and blocks, with lots and blocks numbered consecutively, and the dimensions and acreage of each lot;
- 25) Areas for landscaping, and delineation of the type and extent of vegetative cover on the site;
- 26) Zoning districts on the site and any zoning changes to be requested;
- 27) Existing land uses and zoning on adjoining properties;
- 28) Public or private sources of utility services and facilities; and
- 29) Location and dimension of land to be held in common, open space devoted to community use, and land to be dedicated to town.
- c. Preliminary Landscape Plan. The landscape plan shall comply with all requirements in Section 7-4-7, Landscape Regulations.
- d. Land Suitability Analysis. If updates, amendments, or modifications are needed pursuant on the review and approval of a sketch plan, an updated land suitability analysis may be required. The components which shall be included in such an analysis are set forth in Section X-XX, Land Suitability Analysis.
- e. Preliminary Engineering Reports and Plans. The following items are required to be submitted to the Town of Ridgway:

- Preliminary plan and profile design of all proposed streets, sidewalks, trails, walkways, and bikeways; Conceptual traffic statement or study identifying current and proposed traffic counts and proposed trip generation along with any needed or anticipated improvements to mitigate the projects use on the public transportation network and infrastructure.
- Preliminary plan and profile design of all surface drainage and storm sewer conveyance facilities including, but not limited to, inlet locations, size and location of pipes, retention or detention facilities, and required water quality and erosion control measures;
- 3) Preliminary engineering design of any bridges, culverts, or other drainage structures to be constructed;
- 4) Mitigation of any geologic hazard(s) impacting the project site;
- 5) Preliminary plan and profile design of all wastewater collection and water

supply and distribution system improvements necessary; and

- 6) Preliminary cost estimates for all public improvements.
- f. Land located within the Uncompany River Overlay District. For all parcels located in the Uncompany River Overlay District, excluding subdivisions of existing structures that do not include any additional site development, an Ecological Characterization Study completed by a professional qualified in the areas of ecology, wildlife biology or other relevant discipline. The ecological characterization study shall describe, without limitation, the following:
 - 1) The boundary of wetlands and riparian areas and a description of the ecological functions and characteristics provided by those wetlands and riparian areas;
 - 2) The pattern, species and location of any significant native trees and other native site vegetation;
 - 3) The pattern, species and location of any significant non-native trees and nonnative site vegetation that contribute to the site's ecological, shade, canopy, aesthetic and cooling value;
 - 4) The top of bank and High-Water Mark of any perennial stream or body of water on the site;
 - 5) The wildlife use of the area showing the species of wildlife using the area, the times or seasons that the area is used by those species and the "value" (meaning feeding, watering, cover, nesting, roosting, perching) that the area provides for such wildlife species;
 - 6) Special habitat features;
 - 7) Wildlife movement corridors;
 - 8) The general ecological functions provided by the site and its features;
 - 9) Any issues regarding the timing of development-related activities stemming from the ecological character of the area;
 - 10) Any measures needed to mitigate the projected adverse impacts of the development project on natural habitats and features along the Uncompany River corridor; and

- 11) Twenty-five-foot and 75-foot development setback area from the High-Water Mark.
- g. Supplemental Materials.
 - 1) Draft improvement agreement meeting all standards and requirements set forth in Section X.XX, Subdivision Improvements Agreement.
 - 2) Preliminary drainage plan or study calculating historic and proposed surface and stormwater flows and how such flows will be managed.
 - 3) Preliminary traffic statement or study identifying current and proposed traffic counts and proposed trip generation along with any needed or anticipated improvements to mitigate the projects use on the public transportation network and infrastructure.
 - 4) Draft covenants, restrictions, and by-laws, if applicable.
 - 5) Proof of minimum guaranteed water supply appropriate for the requested use.
- h. Additional Requirements.

Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.

(iv) Completeness Review.

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section X.XX, Completeness Review.

(v) Evaluation by Staff and Review Agencies.

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section X.XX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

(vi) Staff Report.

A staff report shall be prepared and provided to the reviewing body in accordance with Section X.XX, Staff Report.

- (vii)Review and Recommendation by Planning Commission. The Planning Commission shall review the preliminary plat application in a manner consistent with Table X-XX to evaluate compliance with applicable standards. Following its review of the application, the Planning Commission shall provide a recommendation to approve, approve with conditions, or deny the application to the Town Council based on the review criteria set forth in Section X.XX, Approval Criteria.
 - a. The Planning Commission may, in its sole discretion, continue or postpone the meeting to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to making a final decision.
- (viii) Review and Action by Town Council. The final decision to approve, approve with conditions, or deny a Preliminary Plat shall be made by the Town Council in a manner consistent with Table X-XX based upon the review criteria set forth in Section X-XX, Approval Criteria.

- a. The Town Council may, in its sole discretion, continue or postpone the meeting to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to making a final decision.
- (c) Final Plat Review. Unless otherwise provided by this Ridgway Municipal Code, the applicant must receive preliminary plat approval before beginning the final plat process. The final plat review process will evaluate the final plat to be recorded, final engineering documents, reports, and studies.
 - (i) Review Flowchart. Figure X, Final Plat Flowchart, depicts the final plat application review process described in greater detail in this section.

Figure X, Final Plat Flowchart

[Insert Flowchart]

- (ii) Pre-Application Meeting. A pre-application meeting may be held in accordance with the provisions set forth in Section X-XX, Pre-Application Meeting.
- (iii) Application Submittal Requirements. The following are the application materials required to be submitted for a final plat request. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.
 - a. Basic Application Materials. All materials set forth in Section X-XX, Basic Application Materials.
 - b. Final Subdivision Plat. The final subdivision plat shall contain the following information submitted to the Town of Ridgway, in a format prescribed by the Town. The final plat shall be prepared in a clear and legible manner measuring 24" x 36" with clear margins of two (2) inches on the left-hand side and one-half(1/2) inch on the remaining sides at a scale suitable for technical review of the application.
 - 1) A title clearly identifying the plat as a "Final Subdivision Plat";
 - 2) Legal description of the property;
 - 3) North arrow, scale, and legend;
 - 4) A vicinity map at a suitable scale;
 - 5) Scaled at one (1) inch to two-hundred (200) feet;
 - 6) The name and address of the owner(s) of record of the land being platted and the same information for the applicant(s), if other than the owners;
 - 7) The name, address, and seal of the certifying registered land surveyor and the other individuals preparing the final plat;
 - 8) The township, range, section and quarter section(s);
 - 9) Location and full description of all monuments as required by this article and by Title 38, Article 51, C.R.S.:
 - a) Permanent monuments shall be set on the external boundary of the subdivision pursuant to §38- 51-101, C.R.S. and
 - b) Block and lot monuments shall be set pursuant to §38-51-101, C.R.S.
 - 10) Information adequate to locate all monuments shall be noted on the plat;

- 11) Boundary lines, corner pins, and dimensions of the subject parcel(s), including land survey data to identify the subject parcel by section corners, distance and bearing to these corners, quarter corner and township and range;
- 12) The lengths of all arcs, radii and tangents. Sufficient data shall be shown for all curved lines on the plat to enable reestablishment of the curves in the field;
- 13) Lot location and layout;
- 14) All lots and blocks shall be numbered consecutively;
- 15) The dimensions of all lots and acreage of each lot shown to two decimal places;
- 16) No ditto marks shall be used for dimensions;
- 17) All unidentified angles will be presumed to equal ninety (90) degrees;
- 18) Location and width of existing and proposed roadways, road rights-of-way and parking areas within the site;
- 19) All street and road names shall be shown;
- 20) If any road in the subdivision is a continuation or approximately a continuation of an existing public road, the conformity or the amount of conformity of the new road to the existing roads shall be accurately shown;
- 21) Names and widths of all existing or recorded streets and roads intersecting the plat boundaries or paralleling them within two hundred (200) feet, the names and map numbers of all bordering subdivisions, and any municipal limits within two hundred (200) feet of the boundaries of the plat; Area of the site, area of individual parcels, and areas of all development including developed driveways, parking and buildings;
- 22) The boundary lines and dimensions, shown accurately, of all easements, alleyways, sidewalks or paths, and similar features, including all other rights-of-way not otherwise or explicitly mentioned;
- 23) The purpose and owner(s) of all easements and statements from all utility companies, as applicable, that the stated services will be provided to the proposed development after platting. A plat note may be necessary to provide complete information regarding the purpose of the easement;
- 24) The boundary lines and dimensions, shown accurately, of all property to be reserved and dedicated, with the means of access to such property clearly shown and its intended uses noted;
- 25) A legally acceptable land description and dedication block placed on the plat by the applicant dedicating streets, rights-of-way, utility easements, public sites and other such features. The transfer to the town of dedicated land shall take place by a legally acceptable instrument prior to or concurrent with Final Plat acceptance, but before recording of the final plat;
- 26) The names of abutting subdivisions or, in the case of abutting unplatted property, the notation "unplatted" shall appear;

- 27) Identification of lots with slope in excess of thirty (30) percent and any other lots where special studies are required prior to obtaining a development permit;
- 28) Delineation of all known, identified or designated one hundred (100) year floodplains and localized areas subject to periodic inundation along the required stream setback lines, if any;
- 29) All lands within the boundary of the subdivision shall be accounted for as a lot, tract, parcel, open space, street, right-of-way, alley and so forth, and all areas of such lands shall be shown on the plat to the nearest one hundredth of an acre;
- 30) All plat notes required by the town under preliminary plan approval or as a condition of final plat approval;
- 31) Standard certificate blocks as provided by the town;
- c. Final Landscape Plan. The landscape plan shall comply with all requirements in Section 7-4-7, Landscape Regulations. '
- d. Final Engineering Reports and Plans. The following items are required to be submitted to the Town of Ridgway:
 - 1) Final plan and profile design of all proposed streets, sidewalks, trails, walkways, and bikeways;
 - Final plan and profile design of all surface drainage and storm sewer conveyance facilities including, but not limited to, inlet locations, size and location of pipes, retention or detention facilities, and required water quality and erosion control measures;
 - 3) Final engineering design of any bridges, culverts, or other drainage structures to be constructed;
 - 4) Mitigation of any geologic hazard(s) impacting the project site;
 - 5) Final plan and profile design of all wastewater collection and water supply and distribution system improvements necessary; and
 - 6) Final cost estimates for all public improvements.
- e. Supplemental Materials. The following items are required to be submitted to the Town of Ridgway:
 - 1) Final improvement agreement meeting all standards and requirements set forth in Section X.XX, Improvement Agreement.
 - 2) Final drainage plan or study calculating historic and proposed surface and stormwater flows and how such flows will be managed.
 - 3) Final traffic statement or study identifying current and proposed traffic counts and proposed trip generation along with any needed or anticipated improvements to mitigate the projects use on the public transportation network and infrastructure.
 - 4) Covenants, restrictions, and by-laws, if applicable.
 - 5) Proof of minimum guaranteed water supply appropriate for the requested use.
- f. Additional Requirements.

Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.

(iv) Completeness Review.

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section X.XX, Completeness Review.

(v) Evaluation by Staff and Review Agencies.

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section X.XX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

(vi) Staff Report.

A staff report shall be prepared and provided to the reviewing body in accordance with Section X.XX, Staff Report.

- (vii)Review and Recommendation by Planning Commission. The Planning Commission shall review the final plat application in a manner consistent with Table X-XX to evaluate compliance with applicable standards. Following its review of the application, the Planning Commission shall provide a recommendation to approve, approve with conditions, or deny the application to the Town Council based on the review criteria set forth in Section X.XX, Approval Criteria.
 - a. The Planning Commission may, in its sole discretion, continue or postpone the meeting to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to making a final decision.
- (viii) Review and Action by Town Council. The final decision to approve, approve with conditions, or deny a Final Plat shall be made by the Town Council in a manner consistent with Table X-XX based upon the review criteria set forth in Section X-XX, Approval Criteria.
 - a. The Town Council may, in its sole discretion, continue or postpone the meeting to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to making a final decision.
- (ix) Post Approval. The applicant shall follow the post approval procedures in accordance with Section X.XX, Post Approval, including recording the final plat with the Ouray County Clerk and Recorder.
- (3) Approval Criteria.

The following criteria shall be found to be met by the application and submittal materials in order for the Planning Commission and/or Town Council to recommend approval or approve each stage of a major subdivision:

- (a) All of the required prior approvals for the subdivision and development were issued and remain valid and effective;
 - (i) For a sketch plan, no prior approval is required.
 - (ii) For a preliminary plat, a finding must be made that a sketch plan was approved or conditionally approved by the Town Council not more than twelve (12) months prior

to the date of submission of an application for preliminary plat approval or that the sketch plan is currently valid and effective as the result of the approval of an extension of the effective date of the sketch plan.

- (iii) For a final plat, a finding must be made that a preliminary plat for the subdivision was approved or conditionally approved by the Town Council not more than twelve (12) months prior to the date of submission of an application for final plat approval or that the preliminary plat is currently valid and effective as the result of the approval of an extension of the effective date of the preliminary plat.
- (b) The proposed subdivision complies with all applicable requirements for the zone district(s) in which the property is located;
- (c) The proposed subdivision substantially complies with all other applicable requirements of this code, regulations, standards, and resolutions;
- (d) Adequate capacity of water and wastewater utilities are currently available to serve the entire subdivision and development;
- (e) The proposed subdivision is consistent with the applicable portions of the Master Plan in the reasonable judgement of the approving body; and
- (f) The application:
 - (i) For sketch plan approval, meets or satisfies all applicable requirements of the subdivision regulations;
 - (ii) For preliminary plat approval, is in substantial conformance with the approved sketch plan and the preliminary plat meets or satisfies all applicable requirements of the subdivision regulations; or
 - (iii) For final plat approval, is in substantial conformance with the approved preliminary plat and the final plat meets or satisfies all applicable requirements of the subdivision regulations

(D) Minor Subdivision.

- (1) Applicability. Subdivisions which meet all of the following criteria may be processed in accordance with the procedures outlined in this Subsection:
 - (a) All lots or tracts are adjacent to a dedicated, maintained and accepted public street.
 - (b) The improvements required by Subsection X-XX of these regulations are already in existence and available to serve each lot.
 - (c) Each lot will meet requirements of the Town Zoning Regulations without the necessity for any variance and no variance has been granted within the three previous years.
 - (d) No part of the subdivision has been approved as part of a minor subdivision within three years prior to the date of submission of the minor subdivision plat.
 - (e) A State Highway Access Permit has been obtained for any access to a State highway and Town driveway and access requirements will be met.
 - (f) The subdivision meets the Design Standards of these Subdivision Regulations.
- (2) Procedures. [Review and approval procedures to be inserted]
- (E) Plat Amendments.
 - (1) Applicability. Amended plats of subdivision plats previously approved by the Town, or parts of such plats, which do not make or require a material change in the extent, location, or type of

public improvements and easements provided, and are consistent with the Design Standards of these Regulations may be submitted, approved and recorded in accordance with the provisions of this Subsection in lieu of other procedures provided for subdivision by these regulations, if all required improvements are in and available to serve each lot.

(2) Procedures. [Review and approval procedures to be inserted]

(F) Lot Splits.

- (1) Applicability. A lot previously created by a subdivision plat which has been approved and accepted by the Town and recorded in the Ouray County records, may be subdivided or split by deed or other instrument, if the criteria of this Subsection are met, the split has been approved by the Town, and an indication of Town approval is included upon the deed or other instrument prior to recording.
- (2) Procedures. [Review and approval procedures to be inserted]

(G) Boundary or Lot Line Adjustment.

- (1) Applicability. Boundary or lot line revisions are minor amendments to platted or unplatted property which do not result in any of the following:
 - (a) The creation of any additional lot(s);
 - (b) The consolidation of any lots;
 - (c) The creation of an unbuildable lot; or
 - (d) The creation of a lot that does not have legal access from a public right-of-way or perpetual easement.
- (2) Procedures. [Review and approval procedures to be inserted]

(H)Townhome

- Applicability. Any division of a single-unit or multi-unit structure or structures into two or more fee simple estates consisting of townhouses for the purpose, whether immediate or future, of sale or building development.
- (2) Procedures. [Review and approval procedures to be inserted]

(I) Building Footprint

- (1) Applicability. means any division of a single-unit or multi-unit structure or structures into individually owned building footprint lots for the purpose, whether immediate or future, of sale or building development.
- (2) Procedures. [Review and approval procedures to be inserted]

(J) Condominiumization.

- (1) Applicability. The condominiumization of buildings shall require review and approval of a condominium subdivision in accordance with the provisions of this Section 7-5.XX, Condominium Subdivision. This section shall apply to all new condominium projects and conversions of existing buildings to condominiums.
- (2) Procedures. [Review and approval procedures to be inserted]

(K) Exempt Division of Land.

(1) Applicability. To provide procedures and standards by which an exempt division of land may be approved. An application for an exempt division of land typically involves the creation of not more than two (2) lots from a single parent parcel of land thirty-five (35) acres in size or larger. Nothing in this Section 4.08, Exempt Division of Land, shall be interpreted or administered in a manner inconsistent with Colorado Senate Bill 35.

(2) Procedures. [Review and approval procedures to be inserted]

(L) Lot Consolidation.

- (1) Applicability. A lot consolidation is when two (2) or more lots, tracts, or parcels less than two (2) acres each are consolidated into one (1) lot deleting the common boundary line. The consolidation of lots two (2) acres and larger are not required to obtain approval under this Section 7-5-XX, Lot Consolidation, however, all other provisions of this Article and Land Development Code shall apply to any proposed development on the new parcel. The consolidation of lots less than two (2) acres in size are required to go through the lot consolidation process outlined herein. A lot consolidation shall not be allowed for any lot, tract, or parcel more than one time. Furthermore, a lot consolidation shall not result in any of the following:
 - (a) The modification or alteration of any public right-of-way;
 - (b) The creation of any additional lots;
 - (c) The creation of an unbuildable lot; or
 - (d) The creation of a lot that does not have legal access from a public right-of-way or perpetual easement.
- (2) Procedures. [Review and approval procedures to be inserted]

(M) Replat.

- (1) Applicability. A replat is required for any request to amend or revise a recorded plat that would not be defined as another type of special land division.
- (2) Procedures. [Review and approval procedures to be inserted]

(N) Right-of-Way Vacation.

- (1) Applicability. The vacation of interests in rights-of-way owned or otherwise held by the Town of Ridgway shall be in accordance with the provisions of this Section 7-5-XX, Right-of-Way Vacation, and Part 3 of Article 2 of Title 43, C.R.S.
- (2) Procedures. [Review and approval procedures to be inserted]

7-5-3 Subdivision Required Improvements

- (A) The following improvements shall be constructed at the expense of the subdivider in accordance with the design standards provided by these Regulations:
 - (1) Survey monuments.
 - (2) A sewer collection system connected to the Town's sewage system shall be required and dedicated to the Town.
 - (3) A domestic water distribution system connected to the Town's system and dedicated to the Town.
 - (4) A fire prevention system.
 - (5) Electricity, telephone and CATV.
 - (6) Streets within and adjacent to the subdivision as necessary to provide access to each lot. Existing streets maintained by the Town for public use shall be improved by the subdivider to

the extent necessary to provide access to abutting lots and to provide proper drainage, grade and sidewalk grade. Streets shall be paved in circumstances where required by Town street specifications. Streets shall be dedicated to the Town.

- (7) Street signs, stop signs or similar traffic central devices.
- (8) A storm drainage system.
- (9) Street lights.
- (10) Curb and gutter shall be provided along paved streets and where required by Town specifications. Concrete sidewalk shall be provided along all abutting streets except when the Planning Commission and Town Council determine that sidewalk is necessary on only one side of a local street because of the shortness of the street, unusual topographical factors or other circumstances which alleviate the need for such sidewalk. In those cases where the proper grade of the sidewalk cannot be determined, the Planning Commission and Town Council may authorize the execution and recording of an agreement on forms provided by the Town to join in an improvement district to install the sidewalk at such time as sidewalk construction becomes feasible instead of immediate construction.
- (11) Public trail easements shall be provided and constructed as described in the Town's Land Use Plan or Parks and Trails Map, as amended from time to time, and including the Uncompany RiverWay Trail. The Town may waive this requirement if the property at issue has existing trail easements dedicated to the Town of Ridgway.

(B) Subdivision Improvements Agreement.

(1) Applicability.

All applicants granted subdivision approval, or approval of public improvements deemed necessary to comply with required adequate public improvements as set forth in these Land Development Regulations, shall timely, completely, and satisfactorily construct or install all required improvements and infrastructure as called for in these Land Development Regulations and/or as may have been specified as a condition of approval. All improvements and infrastructure intended for public use shall be dedicated and/or transferred to the town, or appropriate agency, free of all liens and encumbrances.

(2) Agreement and Guarantee.

No final division of land shall be executed by the town and no building permits shall be issued for any lot, parcel or property within a division of land as regulated by this Article 5, Subdivision Regulations involving or requiring the installation of public improvements unless and until an improvement agreement is prepared and executed pursuant to this Section X,XX, Subdivision Improvement Agreement. Such agreement shall be recorded simultaneously with the final division of land with the Ouray County Clerk and Recorder.

- (a) Contents of Agreement. Such agreement shall, at a minimum, set forth:
 - (i) Construction specifications for required public and private improvements;
 - (ii) A construction and completion schedule;
 - (iii) Security and guarantees concerning the timely and satisfactory completion of the improvements; and
 - (iv) The terms and conditions for the acceptance of the improvements by the town.
- (b) Timing of Agreement. The improvement agreement shall include a requirement that all improvements be maintained by the developer/subdivider at the cost of the developer/subdivider until such improvements have been fully accepted by the town.

- (c) Agreement to Run with the Land. The improvement agreement shall run with the land and bind all successors, heirs, and assignees of the developer/subdivider.
- (d) Security. The improvement agreement shall include a requirement for the posting of adequate financial security to ensure the timely, complete, and satisfactory construction or installation of all improvements and infrastructure as called for in the agreement.
 - (i) Amount of Security. Security shall be in an amount not less than one-hundred and fifteen (115) percent of the engineers cost estimate to complete all improvements or infrastructure and may be provided by letter of credit, cash escrow, or other financial instrument as approved by the Town Council within its sole discretion.
 - (ii) Letter of Credit. If a developer/subdivider posts a letter of credit as security, it shall:
 - a. Be irrevocable;
 - b. Be for a term, inclusive of renewals, sufficient to cover the completion, maintenance, and warranty periods as required in Section 4.14.B.2, Timing of Agreement; and
 - c. Require only that the town present the letter of credit on demand and an affidavit signed by the Town Manager attesting to the town's right to draw funds under the letter of credit.
 - (iii) Cash Escrow. If a developer/subdivider posts a cash escrow, the escrow instructions shall provide:
 - a. That the developer/subdivider shall have no right to a return of any of the funds except as provided in Section 4.14.B.4.d, Reduction of Security; and
 - b. That the escrow agent shall have a legal duty to deliver the funds to the town whenever the Town Manager presents an affidavit to the agent attesting to the town's right to receive funds, whether or not the developer/subdivider protests that right.
 - (iv) Reduction of Security
 - c) Upon preliminary acceptance of a public improvement or public infrastructure, the town shall release all but fifteen (15) percent of the amount of financial security posted to secure the successful and timely completion of same, so long as the developer is not in default of any provision of the improvement agreement.
 - d) The residual fifteen (15) percent retained by the town shall act as security for the developer's/subdivider's guarantee that the public improvements and infrastructure remain free of defect during the applicable warranty period. The developer/subdivider may at any time during the preliminary acceptance or warranty period offer to provide a substitute or supplemental form of financial security to that security as originally posted with and/or retained by the town. The town may accept substitute or supplemental forms of security in its sole discretion.
 - (v) Temporary Improvements. The applicant shall build and pay for all costs of temporary improvements required by the town and shall maintain those temporary improvements for the period specified by the Town Council. Prior to construction of any temporary facility or improvement, the developer/subdivider shall file with the town a separate public improvements agreement and a letter of credit or cash escrow in the agreed upon amount for temporary facilities, which agreement and credit or escrow shall

ensure that the temporary facilities will be property constructed, maintained, and removed.

- (vi) Special Districts
 - a. Required public improvements shall be made by the developer/subdivider, at its expense, without reimbursement by the town or any improvement district except that, as may be allowed under state law, the developer/subdivider may form or cause to be formed a special district or districts to construct and finance the construction of required public improvements excluding lot improvements on individual lots.
 - b. If the developer/subdivider does form or cause to be formed a special district for the purposes identified in this section, the town shall not release the developer/subdivider from its obligations under any public improvements agreement nor shall the town release any security, in whole or in part, until the special district has sold bonds or otherwise certifies to the town that it has an absolute right to raise revenues sufficient to construct, maintain, and warrant the quality of the required public improvements.

(vii)Failure to Complete Improvements

- a. For developments/subdivisions without an executed agreement or security, improvements shall be completed within a period specified by the town, or the associated development/subdivision application approval shall be deemed to have expired.
- b. In those cases where a public improvements agreement has been executed and security has been posted and required public improvements have not been installed within the terms of the agreement, the town may:
 - 1) Declare the agreement to be in default and require that all the improvements be installed regardless of the extent of the building development at the time the agreement is declared to be in default;
 - 2) Suspend or revoke authorization for subdivision, including without limitation, suspension or revocation of previously issued building permits and suspend issuance of further building permits until the improvements are completed and record a document to that effect for the purpose of public notice;
- c. No certificate of occupancy shall be processed or issued by the town for any lot or building within a development prior to the complete and satisfactory installation of all development improvements or infrastructure required to serve such lot or building, and the payment of any and all development fees then due to the town by the developer/subdivider;
- d. Obtain funds under the security and complete improvements itself or through a third party;
- e. Assign its right to receive funds under the security to any third party, including a subsequent owner of the subdivision for which improvements were not constructed, in whole or in part, in exchange for that subsequent owner's promise to complete improvements in the subdivision; and/or
- f. Exercise any other rights available under the law.

7-5-4 DESIGN STANDARDS.

- (A) All subdivisions shall conform to the minimum design standards of, this Section. The Town Council may allow deviation from these standards if it determines that unusual topography or a hardship exists, or that alternative standards will more effectively protect the quality of the subdivision and the public welfare, or more effectively achieve the purposes of these Subdivision Regulations.
- (B) All subdivisions shall be developed in accordance with the Town's Master Plans, Zoning Regulations, Floodplain Regulations, and other applicable Town ordinances, regulations and specifications.

(C) Streets, Alleys, Lots and Blocks:

- (1) All streets and alleys shall be constructed and designed in accordance with Town Street and Road Specifications.
- (2) All lots shall have access to a street connected to the public street system. In order to ensure access by emergency service responders, any new subdivision street system must be connected by at least two separate routes to the state highway system.
- (3) Access to any public highway under the jurisdiction of the State Department of Highways shall be subject to the provisions of the State Highway Access Code.
- (4) Driveways and street access shall be subject to subsection 14-5-15(B).
- (5) Streets shall be aligned to join with planned or existing streets and shall be designed to bear a logical relationship to the topography.
- (6) Intersections shall approximate right angles as closely as possible.
- (7) Cul-de-sacs shall be permitted, provided they are not more than 500 feet in length and have a turn-around diameter of at least 100 feet. Surface drainage shall be toward the intersecting street, or if this is not possible, a drainage easement shall be required through the cul-de-sac.
- (8) Dead-end streets, with the exception of cul-de-sacs, shall be prohibited unless they are designed to connect with future streets in adjacent land that has not been platted, in which cases a temporary turn-around easement of 80 feet shall be required.
- (9) Restriction of access shall be required when a subdivision or portion thereof adjoins an arterial highway. Marginal access streets, reverse frontage with screen planting contained in a nonaccess reservation, deep lots or similar treatment shall be required to reduce the impact of the traffic on residential properties and to avoid interference with the movement of the traffic on thoroughfares.
- (10) Half streets shall be prohibited.
- (11) Reverse curves on major arterials shall be joined by a tangent at least 200 feet in length.
- (12) Reserve strips controlling access to streets, are permitted only if control of such strips is given to the Town.
- (13) Street, alley and easement right-of-way widths and grades shall not be less than the following:

	Width	Minimum Grade	Maximum Grade
Arterial Highways	120'	0.5	5%
Major Streets	100'	0.5	5%
Collector Streets	80'	0.5	7%
Local Streets	60'	0.5	7%
Marginal Access Streets	40'	0.5	7%
Alleys (where permitted)	20'		
Easements	20'		

- (14) Alleys shall be provided in commercial and industrial areas, except that this requirement may be waived where other provisions are made and approved for service access.
- (15) Block lengths and widths shall be suitable for the uses contemplated and shall be adequate for requirements pertaining to minimum lot sizes and dimensions.
- (16) Lots with double frontage shall be avoided, except where essential to separation from major arterials or from incompatible land uses.
- (17) Side lot lines shall be substantially at right angles or radial to street lines.
- (18) The Town may require any street, sidewalk and related infrastructure, on a steep slope, or where there is any evidence to suspect problems due to instability, or other adverse soil conditions, to be owned and maintained by the lot owners or an owners' association, or may require an extended warranty of maintenance and repair from the subdivider. A slope easement shall be dedicated to the Town to accommodate the area of any cut or fill off of the right-of-way and an additional ten feet beyond the cut or fill. Such easement shall allow the Town to maintain the slope, cut and fill, and street improvements. Additionally, such easements may be accompanied by a plat not holding the Town harmless on account of any sloughing or disturbance due to maintenance, the cut or the fill.

(D) Public Utilities and Utility Easements:

- (1) Utility easements shall be a minimum of 20 feet centered on the rear or side lot lines, or where appropriate, ten feet on either side of a street.
- (2) All utilities shall be installed underground unless existing utilities are overhead and the existing poles can be used.

(E) Water and Sewer Systems:

Water, fire prevention and sewer systems shall be designed by a professional engineer, and constructed in accordance with good engineering practices to Town design and construction standards and specifications.

(F) Curb, Gutter and Sidewalks:

Curb, gutter and sidewalks shall be designed and constructed in accordance with Town design and construction standards and specifications and good engineering practices.

(G) Monuments:

Monuments shall be placed at the corners of all street intersections, at the intersections of the boundary of the subdivision with street right-of-way lines, at angle points and points of curve in each street, and at points of change and direction of the exterior of the subdivision and at other locations required by statute. The top of the monument shall have a metal cap set flush to identify the location. Lot corners shall be marked as required by law. Monuments shall be constructed as provided in Town street and road specifications.

(H) Drainage Systems:

Drainage systems shall be provided in accordance with the final plat as approved. Drainage easements shall generally direct the flow to the front of the lots or to natural drainage ways as such exist, utilizing a minimum 20-foot easement. Where water courses or ditches traverse the subdivision, lots and improvements shall be designed and provided to protect against flooding in accordance with the Town's Flood Plain Regulations. The drainage system shall be designed to avoid increasing the discharge to property outside the subdivision unless agreed to by the owner of any property affected.

(I) Other Improvements:

Any other improvements provided shall comply with any applicable Town standards and specifications and shall be designed and constructed in accordance with good engineering practices.

(J) Plat Notes:

- (1) Plat notes and covenants may be required by the Town as appropriate to implement the provisions of these regulations, and to hold the Town harmless from risks associated with natural hazards and conditions or other risks, which should be borne by the subdivider. Plat notes shall be on Town approved forms, run with the land and bind all successors in interest thereto.
- (2) Any plat notes on prior Town Subdivision or PUD plats, or plats of survey which created new parcels, including those notes requiring release by the Town Council, shall not be enforceable by the Town, and are superseded unless reiterated on the plat. Plat notes which are intended to benefit lot owners within the subdivision will be reiterated unless such owners sign a document to indicate their concurrence with the proposed plat notes.
- (3) Plat notes on prior Town plats are superseded unless reiterated or incorporated by reference on the plat.
- (4) Plat notes may be required in the following circumstances.
 - (a) To set out maintenance requirements of the lot owners, enforceable by the Town, for various improvements such as drainage, detention and retention facilities, commonly owned areas, private streets and other private improvements.
 - (b) To require engineered foundations in areas of steep slopes or other questionable soil conditions together with provisions giving notice of, and holding the Town harmless from, potential problems due to slopes, cut and fill areas, adverse soil conditions or other natural hazards.

Chapter 7: Land Development Regulations

SECTION 6 – PLANNED UNIT DEVELOPMENT (PUD)

7-6-1 GENERAL PROVISIONS [Essentially all new language, process, and standards except as otherwise noted.]

(A) Authorization

Planned Unit Developments (PUD) are authorized by state statute at Title 24, Article 67, C.R.S., Planned Unit Development Act of 1972.

- (B) General Provisions [Brought in from Sec. 7-3-16]
 - (1) The intent of this Subsection is to encourage the development of unique projects and tracts of land in accordance with an overall development plan by providing flexibility with respect to dimensional and density requirements, and to promote the purposes of the Planned Unit Development Act of 1972.
 - (2) An application for a PUD zoning is a type of rezoning. A PUD zoning application shall be accompanied by a PUD development plan and a PUD development guide. The review process for PUD zoning applications is set forth in Section X.XX, Review Procedures. Upon approval, the applicable zoning district standards shall be those established by the PUD development plan and the PUD development guide.

(C) Intent

These PUD regulations and standards are intended to:

- (1) Allow flexibility in the development of medium and large-scale sites with unique characteristics;
- (2) Permit development in a manner varying from standards and regulations set forth in this Land Development Regulations in exchange for innovative design and creative land use that might otherwise not be permitted by traditional zoning districts when narrowly construed;
- (3) Promote the unified and integrated development and use of land at its highest feasible economic and visual values while protecting the natural physical environment of the town;
- (4) Foster development that arranges various land uses in appropriate relationship to each other, to commonly shared open space, and to common facilities;
- (5) Provide a greater variety in type, design, and layout of buildings and open space;
- (6) Utilize land and public services more efficiently; and
- (7) Provide a range of housing options at market and affordable rates.

(D) Application

A PUD may be requested for land located in any zoning district. A land use application and all submittal requirements shall be submitted to the Ridgway Town Hall as set forth in this Section 6, Planned Unit Development.

(E) Eligibility

A PUD should not be permitted on a project area of less than two (2) acres in area. Such area may include one (1) or more contiguous lots, tracts, parcels, or properties.

(1) The project area may be reduced if the following applies:

- (a) Common and/or dedicated open space is provided commensurate with requested reduction; or
- (b) If the layout and design of land uses and amenities provided in the PUD warrant an increase in density or a reduction of project size.
- (2) The applicant may request a reduction in project area in conjunction with the PUD Zoning application and the request will be considered by the Planning Commission and Town Council as part of the overall request.

(F) Permitted Uses

- (1) Any use that is allowed by right or by conditional use permit within the underlying zone district may be allowed in a PUD.
- (2) Uses that are consistent with the intent of applicable portions of the Master Plan in the reasonable judgment of the Town Council and compatible with the site's physical and environmental characteristics may be allowed in a PUD.

(G) Coordination with Subdivision and Zoning Regulations

The PUD is a type of customized zoning district. All standards and regulations set forth in Section 4, Zoning Regulations and Section 5, Subdivision Regulations, as applicable, apply to the PUD and such criteria shall be met in addition to all standards and criteria set forth in this Section, unless specifically permitted to be waived or varied by the Town Council.

- It is the intent of these Land Use Regulations that subdivision hearings and review under Section 5, Subdivision Regulations may cover only a portion of the entire project when the development is built in stages or phases.
- (2) At the discretion of the applicant and subject to approval by the Town Council as a part of the PUD review, the applicant may choose to delay initiation of review of a subdivision application until final approval of PUD is obtained for the entire project area.

(H) Modification of Requirements

The Town Council may waive or modify specifications, standards, and requirements such as density, setbacks, height restrictions, land dedications, improvement standards, architectural design standards, use standards, and related requirements that would otherwise be applicable to a particular land use provided such waiver or modification is found to further the objectives of these PUD regulations and the community goals, policies, and objectives.

7-6-2 PUD STANDARDS [New language. What additional standards should we include in exchange for allowing a PUD?]

(A) General Provisions

The following provisions apply to all PUD application requests:

(1) Conformity with the Master Plan.

The proposed PUD shall be consistent with the applicable portions of the Master Plan in the reasonable judgement of the approving body.

(2) Relationship to Surrounding Area.

The PUD will not have an adverse effect on the surrounding area. The PUD shall be compatible with the scale, intensity, and type of uses located on adjacent and nearby properties.

- (B) Affordable Housing [New language intended to further to community goals to increase affordable housing options and development within Ridgway. These standards reflect a summary of discussions with developers, Planning Commission, Town Council. Any suggested changes, amendments, or additions are encouraged.]
 - (1) The PUD development shall restrict the ownership, use, and occupancy of residential dwelling units in accordance with these standards. Such restrictions shall be in effect in perpetuity, shall not expire, and shall survive any foreclosure, unless the restrictions are otherwise released or modified with the written consent of the Town. A deed restriction shall be recorded on each unit to be restricted under these standards.
 - (2) All PUD developments shall provide, at minimum, the following:
 - (a) A minimum of 25% of housing units shall be restricted in accordance with these standards.
 - (b) Any owner of a restricted unit shall maintain his/her sole residence and abode in Ouray County, Colorado, or provide written intent of his/her desire and intent to do so within 30 days of purchasing the restricted unit.
 - (c) At the time of purchase of a restricted unit, including the original property transfer and all subsequent resales and transfers of property, at least one person in the household shall earn the majority of their income in Ouray County, or from an employer based in Ouray County.
 - (d) At the time of purchase, including the original property transfer and all subsequent resales and transfers of property, the household income will be 120% or less of the Area Median Income (AMI) for the unit, as the same are determined by the United States Department of Housing and Urban Development (HUD), as adjusted annually. Proof of this must be presented to the Town in advance of any transfer of a restricted unit. Proof shall include written documentation, such as income tax returns, verifying annual income for the prior year. HUD income limits are derived from the most recent data provided by HUD regarding AMI for Ouray County.
 - (e) No short-term rentals shall be permitted for the restricted units.

(C) Installation of Electric Vehicle Spaces

(1) All new development within a PUD shall comply with Table X.XX, EVSE Installed and EV Capable Space Requirements with regards to minimum number of spaces required for the provision of Electric Vehicle Supply Equipment (EVSE) installed and Electric Vehicle (EV) Capable parking spaces.

[These space requirements come from Ch. 65 of the Building Construction Standards and are consistent with Energy Code requirements.]

Table X.XX, EVSE Installed and EV Capable Space Requirements.

Total Number of Parking Spaces	Minimum Number of EVSE Installed Spaces	Minimum Number of EV Capable Spaces		
1-10	1	-		
11-15	2	3		
16-19	2	4		
20-25	2	5		
26+	2	20% of total parking spaces		

7-6-3 GENERAL PUD REVIEW PROCEDURES. [New language]

This section outlines the review procedures that are common to all PUD applications. Table X-XX, PUD Application Types and Processes, identifies the various PUD application types and their associated review procedures regulated by this article. The submittal requirements, review procedures, and approval criteria for each application type is laid out in subsequent sections of this article as identified in Table X-XX. All documents and materials identified in Section X-XX, General PUD Review Procedures and the particular application type section shall be required.

(A) Table of PUD Application Types and Processes

PUD applications shall be processed in accordance with Table X-XX, PUD Application Types and Processes.

	Pre- Application Meeting	Completeness Review	Referrals	Notice of Hearing	Planning Commission	Town Council	Recording
R= Required; O-Optional; PH=Public Hearing; Rec = Recommendation; D= Decision							
PUD Zoning	R	R	R	R Posting	R PH/Rec	R PH/D	R
Major PUD Amendment	R	R	R	R Posting	R PH/Rec	R PH/D	R
Minor PUD Amendment	0	R		0	R PH/Rec	R PH/D	R

Table X-XX, PUD Application Types and Processes

(B) Pre-Application Meeting

If the applicant or Town Manager or their designee, requests a pre-application meeting, the following process shall be followed:

- (a) Prior to the formal submission of the application, the applicant shall contact the Town Manager or their designee to schedule and request a pre-application meeting. Following receipt of a request, the pre-application meeting should be set for a date within ten (10) business days of the date of the applicant's request. The Town Manager or their designee shall advise the applicant of the date and time of the pre-application meeting.
- (b) The applicant shall be prepared to discuss the proposed application with the Town Manager or their designee. The applicant is encouraged to present such plats, plans, diagrams, or other preliminary information sufficient to allow a conceptual review of the proposed application.
- (c) The purpose of the pre-application meeting is to assist the applicant in understanding the town's application review processes and to allow the Town Manager or their designee to determine the applicable process(es) and regulations for the proposed application.

(C) Application Submittal Requirements

All of the following information and materials shall be submitted to the Town of Ridgway in a form acceptable to the Town Manager or designee. Additional information and materials required to be submitted for each specific application type identified in Table XXX are set forth in subsequent sections of this Section and shall also be submitted in order to receive a determination of completeness.

(a) Basic PUD Application Materials

The following materials are required for all applications regulated by Section 6, Planned Unit Development, unless waived by the Town Manager or their designee.

- (i) Application Form. An application form for the request shall be obtained from the Town. Completed application forms and accompanying materials shall be submitted to the Town by the owner or applicant.
 - a. Authorized Agent. If the applicant is not the owner of the land based on Ouray County Assessor records, the applicant shall submit a letter signed by the owner consenting to the submission of the application(s).
 - b. Applicant is Not the Sole Owner. If the applicant is not the sole owner of the land, the applicant shall submit a letter signed by all owners or an association representing all the owners, by which all owners consent to or join in the application.
- (ii) Fees. All application fees shall be in compliance with Section 7-1-6, Fees and Costs.
- (iii) Proof of Ownership. Proof of Ownership in the form of a copy of the property deed or a title commitment which has been issued within sixty (60) days of the application submittal along with copies of all documents listed in the exceptions.
- (iv) Legal Description. Legal description of the property subject to the development application.
- (v) Mineral Interest Owners. List of all mineral interest owners with interests severed from the subject property.
- (vi) Vicinity Map. A map locating the project limits, parcel(s), and property within Ridgway. The vicinity map shall clearly show the boundaries of the subject property and all property within a three-mile radius of the subject property.
- (vii) General Written Narrative. A general written narrative identifying the development team, existing conditions of the property, proposed uses, density, lot layout, end users, financing, public dedications (including rights-of-way, parks, open space, infrastructure), and describing the purpose of the project, how the request meets the applicable approval criteria, furthers the goals and objectives specified in the Master Plan, and identifying any potential impacts on adjacent properties and public infrastructure and how those impacts are proposed to be mitigated.

(D) Completeness Review

When a completeness determination is required pursuant to Table X-X.X, the following shall apply:

- (a) Within ten (10) days following receipt of an application, the Town Manager or their designee shall administratively review the application and determine whether it includes all the application content requirements of the Ridgway Municipal Code for the requested application type.
- (b) All plans, reports, maps, and other information required for the application type must be complete and legible. A failure of the application to meet the requirements of Chapter 7, Land Use Regulations and the Ridgway Municipal Code may delay the processing of the application until the application is sufficient and deemed complete.
- (c) When the Town Manager or designee determines that the application is complete as submitted, the Town Manager or designee shall process the application for review in accordance with the provisions set forth in this Section 6, Planned Unit Development.

(d) In the event the Town Manager or designee determines that the application is incomplete, the Town Manager or designee shall inform the applicant in writing of the deficiencies in the application. No further processing of the incomplete application shall be undertaken until the Town Manager, or designee, determines that the applicant has remedied the application's deficiencies.

(E) Referral Agencies

In accordance with Table X-X.X, applications shall be referred to any of the below referral agencies the Town Manager or their designee determines is necessary to the complete and comprehensive review of the request. Referral of applications to other agencies shall be for a minimum time frame of fourteen (14) days. However, the time frame for review and comment may be extended if the application presents technical issues which require additional review, additional information is provided by the applicant, or the application is modified. Referral agencies include, but are not limited to, the following:

- (a) Bureau of Land Management (BLM)
- (b) Colorado Department of Transportation (CDOT)
- (c) Colorado Division of Reclamation, Mining & Safety
- (d) Colorado Division of Water Resources
- (e) Colorado Parks and Wildlife
- (f) Colorado State Forest Service
- (g) Ditch companies
- (h) Fire Protection District(s) or department(s)
- (i) Ouray County Departments (Assessor, Clerk & Recorder, Attorney, Health Department, Building Department, Road & Bridge, Sheriff Office, etc.) as appropriate
- (j) Town of Ridgway Departments (Town Clerk, Town Attorney, Engineering Department, Building Department, Public Works Department, Police Department, etc.) as appropriate
- (k) Water Conservation District(s)
- (I) San Miguel Power Authority
- (m) School district(s)
- (n) Soil Conservation District
- (o) Utility service providers and districts
- (p) US Army Corp of Engineers
- (q) US Environmental Protection Agency (EPA)
- (r) US Forest Service
- (s) Xcel Energy / Public Service of Colorado
- (t) Any other entity or agency deemed necessary by the Town Manager or their designee

(F) Staff Report

The Town Manager or their designee shall review the application to determine if the proposal satisfies the applicable standards. The Town Manager or their designee shall prepare a staff report discussing whether the applicable standards of the Ridgway Municipal Code have been satisfied. The staff report should identify issues raised through staff and referral agency review, potential

mitigation requirements, any recommended conditions for approval, and any additional information pertinent to the review of the application.

(G) Notice Requirements

All public notices of hearings required by this Section shall include the date, time, place, and purpose of the hearing, a general description of the property affected, and any other information deemed appropriate to apprise the public of the general nature of the action proposed. Errors or inaccuracies in the notice shall not be deemed sufficient cause to postpone or invalidate a hearing except where such errors are substantive in material and are found to have reasonably mislead or misinformed the public.

(a) Notice by Posting

When notice by posting is required for a public hearing by Table X-X.X, notice of the hearing shall be posted at Town Hall ten (10) days before the hearing and posted, visible from each street frontage abutting the property, for at least ten (10) days prior to the hearing in addition to any other notice required by Town regulations.

(b) Mineral Estates Notice.

Per 24-65.5-103, C.R.S. if the surface estate and mineral estate are severed, the owners of severed mineral estates shall be entitled to notification of not less than thirty (30) days before the date scheduled for the public hearing for the application. A copy of the notice shall be given to the Town along with the applicant's certification of compliance with said notification requirements. Provided this notice is not required if notice was previously sent and such certification previously provided with respect to the same surface development, or the application is only platting an additional single lot, unless a mineral estate owner has requested notice pursuant to 24-6-402(7), C.R.S.

(H) Public Hearings

When a PUD application requires a public hearing before the Planning Commission or the Town Council in accordance with Table X-X.X, the following shall apply:

- (a) The Town shall set the date and time of a public hearing. Notice of the public hearing shall be issued in accordance with Table X-X.X and Section XXX.XX, Notice Requirements.
- (b) At the public hearing, the reviewing body shall review the application for conformance with the applicable review standards and approval criteria for the request.
- (c) Any public hearing or other action of the body may be continued or postponed at any time to a specified date and time in order to permit preparation of additional information for further review by the reviewing body.
- (d) When required, the Planning Commission recommendation shall be forwarded to the Town Council. Following a public hearing, the Town Council shall approve, approve with conditions, or deny the application or continue the matter to a date certain.
- (e) The applicant shall bear the burden of presenting sufficient competent evidence at the public hearing to support the standards for approval set forth by this Ridgway Municipal Code. Any decision by the reviewing body to recommend, or to act to, approve, conditionally approve, or deny an application shall be based upon a consideration of all evidence presented during the public hearing. Where evidence presented is contradictory, the reviewing body shall weigh such evidence and judge the credibility and sufficiency of the evidence prior to rendering a decision.

(I) Post Approval

- (a) Review. Prior to recording of the approved documents, the applicant shall submit all final documents reflecting any conditions of approval to the Town Manager or their designee for final review and acknowledgement.
- (b) Recording. Any documents required to be recorded with the Ouray County Clerk and Recorder shall be fully executed by the applicant and filed for execution by the Town and recorded. Recording of all documents shall be completed within a reasonable period of time from the date of approval by the approving body.
- (c) Effective Upon Recording. The approval does not become effective until all approved documents have been properly recorded with the Ouray County Clerk and Recorder.

7-6-4 PUD ZONING [New language]

(A) General Provisions

An application for a PUD zoning is a type of rezoning. A PUD zoning application shall be accompanied by a PUD development plan and a PUD development guide. The review process for PUD zoning applications are set forth in Section X-XX, Review Procedures. Upon approval, the applicable zoning district standards shall be those established by the PUD development plan and the PUD development guide.

(B) Review Procedures

(1) Review Flowchart. Figure X, PUD Zoning Flowchart, depicts the PUD zoning application review process described in greater detail in this section.

Figure X, PUD Zoning Flowchart

[Insert Flowchart]

- (2) Pre-Application Meeting. A pre-application meeting shall be held in accordance with the provisions set forth in Section X-XX, Pre-Application Meeting.
- (3) Application Submittal Requirements. The following are the application materials required to be submitted for a PUD zoning request. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.
 - (i) Basic PUD Application Materials. All materials set forth in Section X-XX, Basic PUD Application Materials.
 - (ii) PUD Written Description. A written description of the proposal shall be submitted with a PUD zoning application including and addressing the following information:
 - a. The names and addresses of owner, applicant and representative;
 - General project concept and purpose of the request including, but not limited to, the character of the PUD, character and density of residential uses, and an explanation of how employee housing needs associated with the PUD will be met within the PUD and elsewhere;
 - c. Relationship of the proposed PUD development to the existing land uses and adjacent property land uses;

- d. The expected schedule and phasing of the project including an explanation of how the phasing plan will satisfy basic needs of residents, visitors and future business owners of the project;
- e. Compliance with the Master Plan;
- f. Source of and legal right to water. Written confirmation of service availability from a water and sanitation provider or district if the property lies within a service boundary;
- g. Method of wastewater treatment and disposal;
- h. Method of fire protection;
- i. Names and addresses of severed mineral rights owners on the affected property and mineral rights lessees; names and addresses of water rights owners;
- j. Description of natural and manmade hazards which may exist on the property;
- k. Discussion of impacts on services, including but not limited to county services, town services, and schools;
- I. Discussion of impacts on existing flora and fauna, air quality, wildlife, historic lands or sites, drainage or mineral extraction;
- m. A list of the modifications of standard zoning standards and regulations being requested and justification for such requests; and
- n. A statement of proposed financing.
- (iii) PUD Development Plan. The development plan for a PUD zoning application must depict and contain the following information:
 - a. The size of the plan shall be prepared at a size that is legible for reasonable review and interpretation, as determined by the Town Manager or designee;
 - b. A scale that is one (1) inch equals two hundred (200) feet or another suitable scale if approved by the Town Manager or designee;
 - c. Name or identifying title of the proposed development or use;
 - d. Legal description, date of preparation, north arrow, scale, and legend;
 - e. Vicinity map at a suitable scale;
 - f. Certification of taxes paid;
 - g. Total area of the site, in acres and square footage. If there are two or more lots included in the PUD, the gross and net acreage of individual lots, open space, common areas, and rights-of-way;
 - h. Name, address, telephone number, and e-mail address of the applicant, person preparing the map or plan, designer, engineer, surveyor, and any other consultants of the applicant;
 - i. The following signature and certificate blocks:
 - 1) Certification of title showing the applicant is the landowner, contract purchaser or option-holder;
 - Certification by the project surveyor certifying to the accuracy of the survey and plat;
 - 3) Certification of the Ridgway Planning Commission approval;

- 4) Certification for approval of the Ridgway Town Council; and
- 5) Certification for the Ouray County Clerk and Recorder.
- j. Existing land uses and zoning on adjoining properties;
- k. Public or private sources of utility services and facilities including a statement concerning proposed financing and, where appropriate, types of security anticipated to assure installation of such facilities;
- I. Location and size of all existing and proposed land uses, including proposed densities, where applicable;
- m. Proposed use and gross floor area of structures and anticipated number of employees if commercial or industrial uses;
- n. Depiction of all natural and man-made water courses, retention areas, streams and lakes. Any known one hundred-year (100-yr) flood plains affecting the property shall also be delineated as per the national Flood Plain Insurance Map or those maps provided by the US Army Corp of Engineers or another recognized source;
- o. Building envelopes in hazardous areas to protect natural resources, if deemed appropriate by the county;
- p. Areas where geologic hazard, mineral resources, wildfire hazards, or other natural hazards may exist;
- q. Land to be used for common areas devoted to community use, and land dedicated to the town;
- r. The maximum height of all buildings;
- s. Areas that are to be conveyed, dedicated or reserved as public parks or open space, recreational areas, and as sites for schools or other civic uses;
- t. Topography at ten-foot (10') contours, with delineation of areas having slopes twenty percent (20%) or more and other significant topographic conditions at more defined contours;
- u. The traffic and circulation network, off-street parking areas, service areas, loading areas and major points of access including the widths, lines, and names of all existing and proposed streets, drives, alleys, and roads on or affecting the site, and names of existing streets and alleys, if known, on or adjoining the property. The general location and right-of-way widths for all arterials and collectors shall be shown;
- v. A landscape plan identifying the location, spacing, size and proposed plant material and species schedule;
- w. Conceptual building elevations identifying the architectural intent and the means by which the intent will be achieved;
- x. Names and right-of-way width of each street or other right-of-way, even if for private maintenance and responsibility;
- y. Uses and grantees of all existing and proposed easements and rights-of-way on or adjacent to the parcel, shown by location and dimension;
- z. Primary control points, or descriptions and "ties" to such control points to which all dimensions, angles, bearings, and similar data on the plat shall be referred;

- aa. Location and description of monuments;
- bb. Tract boundary lines, right-of-way lines of streets, easements, and other rightsof-way, and property lines of residential lots and other sites, with accurate dimensions, bearings or deflection angels and radius, arcs, and central angles of all curves;
- cc. Number to identify each lot, parcel, tract, outlot or site, such as lot and block numbers;
- dd. Preliminary street and road plans and profiles; and
- ee. The location, size and character of proposed signs, lighting and advertising devices.
- (iv) PUD Development Guide
 - a. General. All PUD applications must include a proposed development quide that will be applicable only to that particular PUD and not to any other zone district or development. The development guide shall formally establish the standards and requirements for development within the entire PUD. The standards and requirements for development in the approved development quide may be different from the standards and practices established by this Ridgway Municipal Code if the requested modifications from those regulations are, in the opinion of the Town Council, reasonable as well as necessary to the overall project development, and not detrimental to the town or the residents thereof. The regulations and standards contained within this Ridgway Municipal Code, existing or as may be amended, shall be applicable to any matter which is not addressed in the approved development guide. Each PUD owner as well as their heirs, successors, or assigns shall be bound by all matters, covenants, restrictions, terms and conditions contained in the approved and recorded development plan and development guide, and the same shall run with the land. The PUD development guide may be included as notation sheets within the PUD development plan or submitted as a separate document to be recorded with the PUD materials.
 - b. Contents of Development Guide. If no amendments or modifications are proposed for a particular standard or regulation, the standard or regulation set forth in this Ridgway Municipal Code shall apply to all uses and areas within the PUD. The development guide for all PUD applications must contain, at a minimum, provisions regarding the following development features:
 - Objective, purpose and intent. The development guide shall further public health, safety, and the general welfare; facilitate the efficient utilization of land; ensure that there shall be an appropriate relationship with surrounding land and generally encourage compatibility with overall town planning objectives.
 - 2) Ridgway Municipal Code. The development guide shall supersede the Ridgway Municipal Code to the extent there are conflicts between the development guide and the Ridgway Municipal Code.
 - 3) Definitions. Any term or word not defined within this Ridgway Municipal Code shall be defined within the PUD development guide. Any term not explicitly defined by the development guide shall default to the terms and words defined in Section X-X, Definitions, of this Ridgway Municipal Code.

- 4) Land use planning areas. Land use planning areas and the uses permitted within each planning area.
- 5) Dimensional Standards. Dimensional standards for each land use planning area including setbacks, building height, lot size, lot width, and densities.
- 6) Streets. Street scape and cross-section design depicting the total right-ofway width, vehicle travel lanes, surface material, landscaping and/or sidewalk as required by this Ridgway Municipal Code.
- 7) Public facilities. Utilities and services (including water, sewer, roads, electric, gas, telephone, fiber optic, police, fire, medical, solid waste, schools, and snow storage and removal) and the financing for construction, installation, and/or maintenance of those facilities and services.
- 8) Estimated construction costs and proposed method of financing of the streets and related facilities, water distribution system, sewage collection system, storm drainage facilities, and such other utilities as may be required of the applicant by the town.
- 9) Signs and outdoor advertisement. Signs shall conform to the requirements in effect for the underlying zone pursuant to Section X-X, Sign Regulations, except that the PUD development guide may include amendments to those standards when it is determined by the Town Manager or designee that such amendments will result in better relationship of the signs to the general layout and design of the PUD.
- 10) Parking. On-and off-street parking & loading area requirements for each use and planning area. If no standards are proposed, the standards set forth in this Ridgway Municipal Code shall apply to all uses and areas within the PUD.
- 11) Landscaping. Landscaping design guidelines which enhance the PUD project shall include design standards and criteria for the construction of parks, trails, rights-of-way (where applicable), common areas, and non-residential uses. Such standards shall identify species, layout, maintenance, and design that will survive the Ridgway climate and geography.
- 12) Accessory structure and uses. Any desired accessory structure or use may be allowed within a PUD provided any potential impacts of the structure or use are mitigated to an acceptable level.
- 13) General development schedule. A general development schedule of construction of each phase including necessary public improvements for each phase.
- c. Supplemental Submittal Materials
 - 1) Domestic water supply and wastewater treatment systems complying with the standards of Section X-X-X, Design Standards, and the State Division of Water Resources regulations.
 - 2) Proposed covenants, conditions, and restrictions.
 - 3) Erosion control plan and drainage report.
 - 4) Mechanism for maintaining and preserving open space and common areas.
- (v) Supplemental Materials. The following items are also required to be submitted to the Town of Ridgway:

- a. Proof of minimum guarantee water supply.
- (vi) Additional Requirements.

Any additional information that may be reasonably requested by the Town Manager or designee and determined to be necessary to enable an adequate and comprehensive evaluation of the application.

(4) Completeness Review.

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section X.XX, Completeness Review.

(5) Evaluation by Staff and Review Agencies.

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section X.XX, Referral Agencies and review the application for conformance with the requirements and standards of this Section and Chapter 7, Land Use Regulations.

(6) Staff Report.

A staff report shall be prepared and provided to the reviewing body in accordance with Section X.XX, Staff Report.

(7) Review and Recommendation by Planning Commission.

The Planning Commission shall review the PUD Zoning application in a manner consistent with Table X-XX to evaluate compliance with applicable standards. Following their review of the application, the Planning Commission shall provide a recommendation to approve, approve with conditions, or deny the application to the Town Council based on the criteria set forth in Section X-XX, Approval Criteria.

- (i) The Planning Commission may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to providing a recommendation to the Town Council.
- (8) Review and Action by Town Council.

The final decision to approve, approve with conditions, or deny a PUD Zoning Application shall be made by the Town Council in a manner set forth in Table X-XX and be based upon the review criteria set forth in Section X-XX Approval Criteria.

- (i) The Town Council may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Town Council prior to making a final decision.
- (9) Recordation.

The applicant shall cause the PUD development plan and PUD development guide to be recorded with the Ouray County Clerk and Recorder as required by Section X-X-X, Post Approval.

(C) Approval Criteria [Replaced current approval criteria in Sec. 7-3-16(B) with the following more robust criteria.]

The following criteria shall be found to be met by the application and supplemental materials in order for the Planning Commission and/or Town Council to recommend approval or approve a PUD zoning application and associated development plan and development guide:

- (1) There is a legitimate need for the proposed development to be processed as a PUD;
- (2) The PUD does not negatively impact the immediate area, including employee housing requirements;
- (3) An exception from the zoning and subdivision regulations and requirements is warranted by virtue of the design and amenities incorporated in the development plan and development guide;
- (4) The land surrounding the proposed PUD can be planned in coordination with the proposed PUD;
- (5) The proposed PUD zoning is consistent with the applicable portions of the Master Plan in the reasonable judgement of the approving body;
- (6) Existing and proposed utility services are adequate for the proposed development and that the methods of financing, construction and maintenance are acceptable to the county;
- (7) The PUD creates a desirable and stable environment, and does not cause unacceptable air, water or noise pollution; and
- (8) The overall PUD design concept as well as the general phasing scheme are suitable to the land, community, and local economy.

7-6-5 MAJOR PUD AMENDMENT [New language]

(A) General Provisions

- (1) Major PUD amendments include any modification or amendment to an approved PUD development plan or development guide which:
 - (a) Modifies the approved phasing plan;
 - (b) Modifies a use or density established by the PUD; or
 - (c) Removes or substantially modifies any standard or plan provision.
- (2) Amendments and modifications to an approved PUD development plan and/or development guides may be requested in accordance with this Section X.XX, Major PUD Amendment.
- (3) No amendments may be made to an approved PUD development plan and/or development guide during the construction of the improvements governed by the PUD.

(B) Review Procedures

(1) Review Flowchart. Figure X, Major PUD Amendment, depicts the major PUD amendment application review process described in greater detail in this section.

Figure XX, Major PUD Amendment Flowchart

[Insert Flowchart]

(2) Pre-Application Meeting. A pre-application meeting may be held in accordance with the provisions set forth in Section X-XX, Pre-Application Meeting.

- (3) Application Submittal Requirements. The following are the application materials required to be submitted for a major PUD amendment request. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.
 - (i) Basic PUD Application Materials. All materials set forth in Section X-XX, Basic PUD Application Materials.
 - (ii) Written Narrative
 - a. General description of the amendment(s) being requested including the proposed amendments to the PUD general description, PUD development plan, and/or PUD development guide.
 - b. Written narrative and description of how the proposed PUD amendment(s) comply with the standards of this Ridgway Municipal Code and the criteria set forth in Section XXX, Approval Criteria.
 - (iii) PUD Development Plan.

All materials and information required to be included in a PUD zoning request as sort forth in Section X.XX, PUD Development Plan, shall be submitted with a major PUD amendment request.

(iv) PUD Development Guide.

All materials and information required to be included in a PUD zoning request as set forth in Section X.XX, PUD Development Guide shall be submitted with a major PUD amendment request.

- (v) Supplemental Materials. The following items are also required to be submitted to the Town of Ridgway.
 - a. Proof of minimum guaranteed water supply.
- (vi) Additional Requirements.

Any other information deemed necessary by the Town Manager or designee to assist in the review of the application.

(4) Completeness Review.

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section X.XX, Completeness Review.

(5) Evaluation by Staff and Review Agencies.

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section X.XX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

- (6) Staff Report. A staff report shall be prepared and provided to the reviewing body in accordance with Section X.XX, Staff Report.
- (7) Review and Recommendation by Planning Commission.

The Planning Commission shall review the major PUD Amendment application in a manner consistent with Table X-XX to evaluate compliance with applicable standards. Following their review of the application, the Planning Commission shall provide a recommendation to approve, approve with conditions, or deny the application to the Town Council based on the criteria set forth in Section X-XX, Approval Criteria.

- (i) The Planning Commission may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to providing a recommendation to the Town Council.
- (8) Review and Action by Town Council.

The final decision to approve, approve with conditions, or deny a PUD Zoning Application shall be made by the Town Council in a manner set forth in Table X-XX and be based upon the review criteria set forth in Section X-XX Approval Criteria.

- (i) The Town Council may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Town Council prior to making a final decision.
- (9) Recordation.

The applicant shall cause the PUD development plan and PUD development guide to be recorded with the Ouray County Clerk and Recorder as required by Section X-XX, Post Approval.

(C) Approval Criteria

The approval criteria for a PUD zoning application set forth in Section X.XX, Approval Criteria for a PUD Zoning request shall be found to be met by the application and supplemental materials in order for the Planning Commission and/or Town Council to recommend or approve a major PUD amendment application and associated development plan and development guide.

7-6-6 MINOR PUD AMENDMENT [New language]

(A) General Provisions

- (1) Minor PUD amendments include any modification or amendment to an approved PUD development plan or development guide which does not constitute a major PUD amendment as defined in Section XXX, General Provisions.
- (2) No minor PUD amendment shall affect the rights of the residents, occupants and owners of the PUD to maintain and enforce all provisions of law or in equity, except as to those lawfully modified, removed or released.
- (3) Minor amendments and/or modifications to an approved PUD development plan and/or development guides may be requested in accordance with this Section XXX, Minor PUD Amendment.
- (4) No amendment may be made to an approved PUD plan and/or approved development guide during the construction of the improvements governed by the PUD.

(B) Review Procedures

(1) Review Flowchart. Figure X, Minor PUD Amendment, depicts the minor PUD amendment application review process described in greater detail in this section.

Figure XX, Minor PUD Amendment Flowchart

[Insert Flowchart]

(2) Pre-Application Meeting. A pre-application meeting may be held in accordance with the provisions set forth in Section X-XX, Pre-Application Meeting.

- (3) Application Submittal Requirements. The following are the application materials required to be submitted for a minor PUD amendment request. The Town Manager or designee may waive or alter any of the submittal requirements if they are determined to be inappropriate or unnecessary to determining if the application satisfies applicable standards.
 - (a) Basic PUD Application Materials. All materials set forth in Section X-XX, Basic PUD Application Materials.
 - (b) Written Narrative
 - General description of the amendment(s) being requested including the proposed amendments to the PUD general description, PUD development plan, and/or PUD development guide.
 - (ii) Written narrative and description of how the proposed PUD amendment(s) comply with the standards of this Ridgway Municipal Code and the criteria set forth in Section XXX, Approval Criteria.
 - (c) PUD Development Plan.
 - (i) Updated PUD development plan depicting the proposed minor amendment(s), as applicable. The requirements of a PUD development plan identified in Section X-XX, PUD Development Plan should be used as a template.
 - (d) PUD Development Guide.
 - Updated PUD development guide depicting the proposed minor amendment(s), as applicable. The requirements of a PUD development guide identified in Section 5.04.B.3.d, PUD Development Guide should be used as a template.
 - (e) Supplemental Materials. The following items are also required to be submitted to the Town of Ridgway.
 - (i) Proof of minimum guaranteed water supply.
 - (a) Additional Requirements.

Any other information deemed necessary by the Town Manager or designee to assist in the review of the application.

(4) Completeness Review.

The Town Manager or designee shall review the application for completeness in accordance with the provisions of Section X.XX, Completeness Review.

(5) Evaluation by Staff and Review Agencies.

Upon determination of completeness, the Town Manager or designee shall refer the application to additional reviewing agencies as set forth in Section X.XX, Referral Agencies and review the application for conformance with the requirements and standards of this Municipal Code.

- (6) Staff Report. A staff report shall be prepared and provided to the reviewing body in accordance with Section X.XX, Staff Report.
- (7) Review and Recommendation by Planning Commission.

The Planning Commission shall review the minor PUD Amendment application in a manner consistent with Table X-XX to evaluate compliance with applicable standards. Following their review of the application, the Planning Commission shall provide a recommendation to approve, approve with conditions, or deny the application to the Town Council based on the criteria set forth in Section X-XX, Approval Criteria.

- (i) The Planning Commission may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to providing a recommendation to the Town Council.
- (8) Review and Action by Town Council.

The final decision to approve, approve with conditions, or deny a minor PUD Amendment shall be made by the Town Council in a manner set forth in Table X-XX and be based upon the review criteria set forth in Section X-XX Approval Criteria.

- (i) The Town Council may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Town Council prior to making a final decision.
- (9) Recordation.

The applicant shall cause the PUD development plan and PUD development guide to be recorded with the Ouray County Clerk and Recorder as required by Section X-XX, Post Approval.

(C) Approval Criteria

The following criteria shall be found to be met by the application and supplemental materials in order for the Planning Commission and/or Town Council to recommend or approve a minor PUD amendment application and associated development plan and development guide:

- (1) The minor PUD amendment is consistent with the efficient development and preservation of the entire PUD;
- (2) The minor PUD amendment is consistent with the applicable portions of the Master Plan in the reasonable judgement of the approving body;
- (3) The minor PUD amendment does not affect in a substantially adverse manner either the enjoyment of land abutting upon or across a street from the PUD; and
- (4) The minor PUD amendment protects the public interest.

Chapter 7: Land Development Regulations

SECTION 7 – ANNEXATION

7-7-1 APPLICATION OF MUNICIPAL CODE

- (A) This Section 7, Annexation, shall be known and cited as the "Ridgway Annexation Ordinance".
- (B) Unless otherwise provided by an agreement or by ordinance governing the annexation of property into the Town, the ordinances, resolutions, rules and regulations of the Town shall remain fully valid and effective as to any property annexed into the Town.

7-7-2 PURPOSE

- (A) The purpose of the Ridgway Annexation Ordinance, is to establish a procedure to bring land under the jurisdiction of the Town of Ridgway in compliance with the Colorado Municipal Annexation Act of 1965, as amended ("Act"). Section 31-12-101, et seq., C.R.S.
- (B) This Section, in part, provides supplemental requirements for annexation pursuant to the Act and is not to be construed as altering, modifying, eliminating or replacing any requirement set forth in the Act or any requirements set forth in other portions of the Ridgway Municipal Code. In the event of a conflict between the Act, the provisions of this Section, or any requirements set forth in other portions of the Ridgway Municipal Code, the more stringent provision shall control.
- (C) For purposes of defining the certain words or phrases used herein and interpreting this S, the provisions of Section 31-12-103, C.R.S., shall apply, which provisions are incorporated herein by this reference.

7-7-3 STATEMENT OF POLICY AND REVIEW CRITERIA

It shall be the general policy of the Town with respect to annexations and the consideration of annexation petitions that:

- (A) Annexation is a discretionary act. Except for the initiated petition for the annexation of an enclave, the Town shall exercise its sole discretion in the annexation of territory to the Town.
- (B) The land to be annexed and the uses proposed for the land shall conform to the goals, policies and strategies of the Master Plan and to the land uses depicted on the Future Land Use Map, as amended.
- (C) Certain public facilities and amenities are necessary and must be constructed as part of any territory annexed to the Town in order that the public needs may be served by such facilities. These facilities include, but not by way of limitation, streets, bridges, public parks and recreation areas, school sites and storm drainage facilities. The annexation of lands to the Town shall not to create any additional cost or burden on the then-existing residents of the Town to provide such public facilities in any newly annexed area.
- (D) The petitioner for annexation shall be responsible for paying the Town's full cost for processing the annexation petition, from initial discussion with Town staff before submittal of the petition through the approval and recording of the final annexation documents, in the event of the Town Council's approval of annexation.

- (E) Annexed areas will not divide tracts of land to prevent further annexation of adjoining parcels (for example, leaving a "gap" or a "strip" of land between property to be annexed and the adjoining property).
- (F) Adequate water rights are to be deeded to the Town, as determined necessary by the Town, at the time of annexation, to provide sufficient water for the annexed property and the uses thereon.
- (G) The annexation process can be complex. A property owner considering an annexation petition may wish to consult with an attorney familiar with municipal annexation law. While the Town staff will cooperate with the property owner in the process of complying with state law or the Land Development Regulations, the Town cannot be bound by any representations made by the Town staff regarding the status of or the requirements of state law or the Land Development Regulations. As a general rule and except in extraordinary circumstances, annexation petitions should be accompanied by a request for zoning and, when appropriate, a sketch plan or other application(s), which may be needed pursuant to Chapter 7, Land Development Regulations.
- (H) The property owner may request that the annexed property be placed in a specific zone district, or the Town may initiate a zoning action as part of the annexation process. However, no zoning action shall become effective prior to the effective date of the annexation ordinance concerning the property.
- (I) The Town may conduct zoning and subdivision review for the area proposed to be annexed after the Town Council adopts a resolution finding the petition for annexation (or annexation election) to be in substantial compliance with the state law and that the area is eligible for annexation. The Town Council shall not pass any ordinance approving a request for zoning and/or subdivision until an ordinance annexing the property to the Town has been approved by the Town Council.
- (J) The petitioner(s) shall enter into an annexation agreement with the Town for the development of the property to be annexed.

7-7-4 RESPONSIBILITIES OF APPLICANT

In addition to other duties imposed upon all applicants by these Land Development Regulations and the Act, as amended, all applicants shall have the following responsibilities:

- (A) The applicant is responsible for having a representative at all meetings where the request is reviewed. Failure to have a representative present is cause to have the item withdrawn from the agenda of that meeting.
- (B) The applicant shall consult with the Town Manager or designee to discuss any special conditions pertaining to the annexation and to obtain an annexation petition prior to submitting an annexation petition to the Town.

7-7-5 ANNEXATION PROCEDURES

(A) Eligibility

Eligibility for annexation shall be determined by conformity with the requirements of the Act, including but not limited to Sections 31-12-104 and 31-12-105, C.R.S., and as determined by the Town Council in its sole discretion.

(B) Annexation Process Summary

The annexation process shall be as follows:

(A) Pre-Application Meeting

- (B) Submittal of Application and Petition
- (C) Resolution of Substantial Compliance and Setting the Public Hearing
- (D) Evaluation and Review of the Application and Petition
- (E) Planning Commission Consideration of Zoning
- (F) Town Council Consideration of Annexation Agreement, Annexation Ordinance, and Zoning
- (G) Post Approval Requirements

(C) Pre-Application Meeting

The application process begins with a preapplication conference with the Planner and other appropriate Town staff to determine the feasibility of the annexation request. Following this informal meeting, the petitioner shall submit a letter of intent requesting annexation, the annexation petition, the completed annexation application form, annexation maps, applicable fees and supporting documents, as provided in this Chapter.

(D) Application and Petition Submittal Requirements

All of the following information and materials shall be submitted to the Town of Ridgway in a form acceptable to the Town Manager or designee.

(a) Annexation Application Materials

The following materials are required for all applications regulated by Section 7, Annexation, unless waived by the Town Manager or their designee.

- (i) Application Form. An application form for the request shall be obtained from the Town. Completed application forms and accompanying materials shall be submitted to the Town by the owner or applicant.
 - a. Authorized Agent. If the applicant is not the owner of the land based on Ouray County Assessor records, the applicant shall submit a letter signed by the owner consenting to the submission of the application(s).
 - b. Applicant is Not the Sole Owner. If the applicant is not the sole owner of the land, the applicant shall submit a letter signed by all owners or an association representing all the owners, by which all owners consent to or join in the application.
- (ii) Fees as required by Section 7-X General Provisions.
- (iii) Proof of Ownership. Proof of Ownership in the form of a copy of the property deed or a title commitment which has been issued within sixty (60) days of the application submittal along with copies of all documents listed in the exceptions.
- (iv) Legal Description. Legal description of the property subject to the development application.
- (v) Vicinity Map. A map locating the project limits, parcel(s), and property within Ridgway. The vicinity map shall clearly show the boundaries of the subject property and all property within a three-mile radius of the subject property.
- (vi) General Written Narrative. A general written narrative identifying the development team, existing conditions of the property, proposed uses, density, lot layout, end users, financing, public dedications (including rights-of-way, parks, open space, infrastructure), and describing the purpose of the project, how the request meets the applicable approval criteria, furthers the goals and objectives specified in the

Master Plan, and identifying any potential impacts on adjacent properties and public infrastructure and how those impacts are proposed to be mitigated.

- (b) Petition for annexation. A Petition for Annexation, in a form acceptable to the Town Attorney and complying with the requirements of the Act. The Town may provide a standard form petition. The Petition shall be signed by 100% of the owners of the private property described in the Petition.
- (c) Annexation map. All annexation maps shall be made with an engineer's scale, minimum scale to be one (1) inch represents one hundred (100) feet and shall be on a reproducible medium with outer dimensions of twenty-four (24) by thirty-six (36) inches. The annexation map shall contain the following information:
 - a. The date of preparation, the scale and a symbol designating true north.
 - b. The name of the annexation.
 - c. The names, addresses and phone numbers of the applicant and the person responsible for preparing the annexation map.
 - d. The legal description.
 - e. Distinction of the boundary that is contiguous to the Town and the length of same.
 - f. Lot and block numbers if the area is already platted.
 - g. Existing and proposed easements and rights-of-way.
 - h. Existing water courses with adequate easements for flood control.
 - i. Existing and requested zoning and acreage of each requested zone.
 - j. Ownership of all parcels within and adjacent to the annexation.
 - k. Mailing addresses of all property owners within two hundred (200) fee of the annexation.
 - I. Affidavit concerning the amount and historical use of all water rights owned.
- (d) Annexation Impact Report. Using information available at this stage of the development process, the application is to be accompanied by a narrative report assessing the effect of the proposed annexation upon the community and existing services and facilities. It shall detail the possible need for any expansion of those services and facilities to accommodate the development proposed for the property being annexed. The narratives shall be one or more paragraphs in length, and adequate to explain the needs, concepts, and proposed solutions for each of the following.
 - a. An assessment of the community needs for the proposed annexation and land use.
 - b. The economic impact to the Town of the proposed annexation. This is to include an analysis of short-term and long-term revenues to the Town to be generated by the development, short-term and long-term expenses of the Town likely to be incurred as a result of the annexation and development, and proposals to mitigate any negative impacts.
 - c. The school impact including an estimate of the number of students to be generated by development of the property, capital construction required to educate the students, and proposals to mitigate any negative school impacts.
 - d. The source of water, both potable and non-potable, and sanitary sewer systems anticipated to serve the property, including a description of any regional facilities that must be constructed or upgraded to serve the development on the property.

- e. The impact on the existing transportation system and proposals to mitigate any negative transportation impacts upon the community (arterial and collector street improvements, intersection improvements, intersection signalization, alternative modes of transportation, etc.)
- f. The impact of the proposed development on the existing storm drainage system and proposals to mitigate any negative drainage impacts upon the community (historic rainfall drainage patterns, detention and retention areas, storm sewer requirements, discharged irrigation ditches, floodways and floodplains, etc).
- g. The impact of the proposed development on law enforcement and proposals to mitigate any impact upon the existing law enforcement services (special security needs, additional officers required, additional equipment requirements, etc.).
- h. The impact of the proposed development on the fire district and proposals to mitigate any impact upon the existing fire protection services (special fire hazards, fire prevention, fire detection, emergency access, additional equipment requirements, additional manpower requirements, additional fire stations, etc.).
- i. The impact of the proposed development on town park facilities and recreation programs and proposals to mitigate any impact upon the existing facilities and programs.
- j. The impact of the proposed development on the environment of the town and proposals to mitigate any negative impact (identify environmentally sensitive areas, endangered species, significant habitats, etc.).
- k. The short-term and long-term economic development potential for the property (numbers of jobs to be created, sales and use tax generation, property tax generation, utility revenue generation, incentives to be offered, etc.).
- I. The compatibility of the proposed development with the town's current and future transportation infrastructure and road network and proposals for mitigating any negative impact.
- m. The compatibility of the proposed development with the Master Plan and any plan amendments that may be necessary for the proposed development.
- n. The compatibility of the proposed development with the Land Development Regulations and Ridgway Municipal Code and any deviations in setbacks, space requirements, and permitted uses that may be required for the proposed development.
- o. A review of existing and adjacent land uses, areas of compatibility or conflict, and possible mitigation measures that may be required for the proposed development.
- (e) Concept development plan map. The concept development plan map(s) shall be a neat, clear, permanent, legible and reproducible document and shall contain the following:
 - a. The boundary of the area to be developed;
 - b. A written legal description of the area to be developed;
 - c. The general location of each proposed land use on the property and the percentage of the whole for each use. General location of land uses may be shown as irregular graphic shapes depicting the approximate size and relationship to adjacent land uses. A table shall be used to list densities and land use by type, including the area of each, the density of residential development and the maximum and minimum lot sizes, and the maximum square footage of commercial and industrial buildings and the maximum and minimum lot sizes;

- d. Existing and proposed arterial and collector streets and their relationship to the principal land uses on the site;
- e. Existing and proposed major utility lines or facilities and their relationship to the principal land uses on the site;
- f. Contour lines at 10 foot intervals, except when there are significant geographical features on the land and a different interval is determined to be more appropriate; and
- g. Significant natural or manmade features on the site and contiguous to the property, including but not limited to, bluffs, tree galleries, lakes and ponds, irrigation ditches watercourses and wetlands.
- (f) For all annexations in excess of ten (10) acres, the applicant shall obtain from the school district governing the area to be annexed a statement of the effect of the annexation upon the school district, including an estimate of the number of students generated by the proposed annexation and the capital construction required to educate such students.
- (g) Property tax statement. A copy of the prior year's property tax statement for all property to be annexed.
- (h) Public hearing notification envelopes. In addition, the applicant shall provide such envelopes for the County Commissioners, County Attorney, and School District.
- (i) Surrounding and interested property ownership report.
- (j) Statement of conformance to the Master Plan. A narrative of how the project conforms to the Future Land Use Classification and the goals, policies and strategies identified in the Master Plan.
- (k) Water rights. A "Water Rights Report" for the property prepared by a qualified water engineer or water attorney detailing the water rights appurtenant to and severed from the property to be annexed and their historical use. The report must include both surface (tributary) and subsurface (non-tributary and not non-tributary groundwater). The applicant shall provide to the Town a signed warranty deed(s) for sufficient water rights as defined by the Town Engineer and in a form acceptable to the Town Attorney to provide the domestic needs of property to be developed as a result of the annexation. In addition the applicant shall provide to the Town a signed standard form warranty deed for the transfer of all subsurface (non-tributary) water rights to the Town. The timing and form of required water rights dedication may be modified in the Annexation Agreement.
- (I) Application for zoning of property to be annexed. The petitioner must submit a completed Zoning Map Amendment application, and all required submittal requirements as set forth in Section 7-5-X, Map Amendment of this Chapter.

(E) Completeness Review

The Town Manager or designee shall review the petition for annexation and all other submitted materials for completeness as follows:

- (a) Within ten (10) days following receipt of a petition or application, the Town Manager or designee shall administratively review the application and determine whether it includes all the application content requirements of the Ridgway Municipal Code for the requested application type.
- (b) All plans, reports, maps, and other information required for the application type must be complete and legible. A failure of the application to meet the requirements of the Act, Chapter 7, Land Use Regulations and the Ridgway Municipal Code may delay the processing of the application until the application is sufficient and deemed complete.

- (c) When the Town Manager or designee determines that the application is complete as submitted, the Town Manager or designee shall process the application for review in accordance with the provisions set forth in this Section 7, Annexation.
- (d) In the event the Town Manager or designee determines that the application is incomplete, the Town Manager or designee shall inform the petitioner in writing of the deficiencies in the application. No further processing of the incomplete application shall be undertaken until the Town Manager, or designee, determines that the applicant has remedied the application's deficiencies.

(F) Substantial Compliance

- (a) Annexation petition referral to Town Council. Upon the Town staff's determination that the petition and supporting documentation are complete and in compliance with provisions of this Chapter, the Act, and the Ridgway Municipal Code, the Town Manager or designee shall refer the petition to the Town Council for review and consideration.
- (b) Town Council determination of substantial compliance. The Town Council shall consider at a regular or special meeting whether the petition is in substantial compliance with provisions of the Act.
 - a. If the petition is found to be in substantial compliance with the Act, the Town Council may, by the adoption of a Resolution of Substantial Compliance, set the annexation and zoning, for a public hearing as provided in the Act.
 - b. If the petition is found to not be in compliance with the Act, no further action shall be taken, except that the findings shall be made by resolution of the Town Council.

(G) Evaluation and Review of Application and Petition

Town Staff shall analyze the feasibility of annexing the proposed property, such analysis including but not limited to, the ability to serve with streets, water, sanitary sewer, storm sewer, parks and recreation, schools, law enforcement and fire protection. The analysis shall also consider the following: compliance with the Town's Comprehensive Plan, codes and policies; sources of revenue from the property; the Town's costs to serve development proposed for the property; and any other related matters.

(H) Notice of Public Hearing

After adoption by the Council of a Resolution of Substantial Compliance, the Town shall provide notice of the public hearing as provided in the Act and Chapter 7, Land Development Regulations.

(I) Planning Commission Review

The Planning Commission shall review the Map Amendment application in a manner consistent with Section 5, Zoning Regulations to evaluate compliance with applicable standards. Following their review of the application, the Planning Commission shall provide a recommendation to approve, approve with conditions, or deny the application to the Town Council based on the criteria set forth in Section X-XX, Approval Criteria.

a. The Planning Commission may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Planning Commission prior to providing a recommendation to the Town Council.

(J) Town Council

The final decision to approve, approve with conditions, or deny a Annexation, Annexation Agreement, and initial zoning request shall be made by the Town Council in a manner consistent with the Act.

(i) The Town Council may, in its sole discretion, continue or postpone the public hearing to a specified date and time in order to permit preparation of additional information for further review by the Town Council prior to making a final decision.

(K) Post Approval

- (a) Review. Prior to recording of the approved documents, the applicant shall submit all final documents reflecting any conditions of approval to the Town Manager or their designee for final review and acknowledgement.
- (b) Recording. Any documents required to be recorded with the Ouray County Clerk and Recorder shall be fully executed by the applicant and filed for execution by the town and recorded. Recording of all documents shall be completed within a reasonable period of time from the date of approval by the approving body.
- (c) Effective Upon Recording. A plat does not become effective until it is properly filed for recording with the Ouray County Clerk and Recorder.



Chapter 7: Land Development Regulations

SECTION 8 – DEFINITIONS

7-8-1 DEFINITIONS [Combined terms from Sections 6-3-1, 7-3-2, and 7-4-4. New terms and definitions will be added and updated during the update process.]

The following words and terms shall be defined as follows for the purposes of these Land Development Regulations:

ACCESSORY USE: A use which is subordinate to, clearly incidental to, customarily in connection with, and ordinarily located on the same premises as the permitted use. Home occupations which meet the criteria set out in subsection 7-3-18(A), including daycare facilities with eight or fewer children, shall be considered an accessory use to a residence in all districts.

ADAPTIVE CONTROLS: Devices such as timers, motion-sensors and light-sensitive switches used to actively regulate the emission of light from light fixtures.

APPLICANT: [New term to be defined]

ART AND CRAFT STUDIO: The workshop of an artist, sculptor, photographer, craftsperson, furniture maker, glass blower, potter or cabinet maker primarily used for on-site production of unique custom goods by hand manufacturing involving the use of hand tools and small-scale equipment, which may include an accessory gallery. The primary use of art and craft studios is the retail sale of the custom goods as produced on-site, as evidenced through allocation of customer floor area or gross sales receipts of the business.

BOARDING OR ROOMING HOUSE: A building or portion thereof which is used to accommodate, for compensation, one or more boarders or roomers, not including members of the occupant's immediate family who might be occupying such building. "Compensation" includes compensation in money, services or other things of value.

BUILDING LINE: A line parallel to a property line beyond which no exposed portion of a building extends. The first three feet of unroofed terraces or patios, sills, cornices and chimneys; temporary awnings; free standing walls, rails or fences; the first one foot of a roof eave; and the first four feet of an open fire escape; need not be considered in determining the building line.

CONDOMINIUM: A building or buildings consisting of separately owned air space units of a multi-unit property. Generally, the units or portions of the units are stacked one above another. In addition to the interest acquired in a particular unit, each unit owner has an undivided interest in the land or buildings as parts thereof used in common by all the unit owners (common elements). This does not prohibit the ownership of common areas by a homeowners association holding title to such areas for and on behalf of the owner of a condominium unit.

CONDOMINIUMIZATION: The development or use of the land and existing structures as a condominium project, regardless of the present or prior use of such lands and structures and regardless of whether substantial improvements have been made to structures.

DEPENDENT MANUFACTURED HOME: A manufactured home without toilet, lavatory or bathing facilities.

DORMITORY: A building used as group living quarters for students or religious adherents as an accessory use for a bona fide college, university, boarding school, seminary, convent, monastery or other similar institutional use.

DWELLING: A building or portion of a building that is designed or used exclusively as the living quarters for one or more families, and that complies with all applicable building and safety codes. This definition includes factory-built housing that does not meet the definition of a manufactured home, provided the

structure meets all applicable building and safety codes and is mounted on a permanent structure and connected to all required utilities.

DWELLING, CLUSTER DEVELOPMENT: A development type that concentrates single-family, duplex, or townhouse dwellings (in groups of two) on smaller lots than would otherwise be allowed in the zone district in return for the preservation of sensitive natural areas, agricultural or ranch land, trail or recreational easements, and/or common open space within the same site, on a separate lot, or in an easement.

DWELLING, CO-HOUSING DEVELOPMENT: A residential development that does not meet the definition of a Group Home, that includes a group of individual dwelling units of varying sizes, the largest containing less than 1,500 square feet of floor area, that are not constructed on a frame or capable of being transported on their own wheels, and in which individual units may or may not have partial or complete kitchens. The development must include one or more community building(s) with a community kitchen and dining room intended for communal use on a regular basis, and in which most or all residents generally agree to share in the provision of regular communal services such as cooking meals or providing childcare.

DWELLING, DUPLEX: A single structure, located on a single lot, containing two dwelling units, neither of which meets the definition of a townhouse dwelling or an accessory dwelling unit.



Sample duplex dwelling

DWELLING, FOURPLEX: A single structure, located on a single lot, containing four dwelling units, none of which meets the definition of a townhouse dwelling unit or an accessory dwelling unit.



Sample fourplex dwelling

DWELLING, LIVE/WORK: A structure containing an integrated living and working space that is intended to function predominantly as business workspace with residential use area occupied by the business owner or operator. The unit typically has a store front, with the workspace, public display area, or show room on the ground floor of the unit and the majority of the residence area is located either on the upper floor if there are two floors, or the back of the unit if there is only one floor.

DWELLING, MULTIPLE FAMILY: Five or more dwelling units, within a single building and located on a single lot, including apartments and condominiums. This definition also includes any number of dwelling units located within a single building that contains a nonresidential primary use on the ground floor of the building, and that does not meet the definition of employee housing.



Sample multiple family dwelling

DWELLING, SINGLE-FAMILY DETACHED: A dwelling unit, located on a separate lot or tract that has no physical attachment to any other building containing a dwelling unit located on any other lot or tract, and that does not meet the definition of a manufactured home.



Sample single family detached dwelling

DWELLING, TOWNHOUSE: A single-family dwelling at least two stories in height that is attached to at least one other single-family dwelling at least two stories in height by an unpenetrated vertical wall running from ground level or below ground level to at least the top of the highest floor designed for human occupancy, and that has a pedestrian entrance leading directly from the ground floor of the dwelling unit to a street fronting the lot on which the dwelling unit is located. Individual townhouse dwellings may be located on separate lots, or a group of two or more townhouse dwellings may be located on a single lot.



DWELLING, TRIPLEX: A single structure, located on a single lot, containing three dwelling units, none of which meets the definition of a townhouse dwelling unit or an accessory dwelling unit.



Sample triplex dwelling

DWELLING UNIT: An area in a building containing cooking, living and sanitary facilities designed for use and used by a single family for residential purposes, including related accessory structures. The term dwelling shall not include hotels, motels, homeless shelters, boarding and rooming houses, dormitories, seasonal overflow shelters, tents, or other structures designed or used primarily for temporary occupancy. DWELLING UNIT, ACCESSORY: A dwelling unit located within, attached to, or detached from the principal dwelling, that contains no more than 800 square feet of gross floor area, the use of which is associated with and subordinate to the principal dwelling and that is located upon the same lot as the principal dwelling.

EMPLOYEE HOUSING: A dwelling unit that contains no more than 450 square feet of gross floor area, located within the same structure as a nonresidential use and above or behind the nonresidential use, in which the use of the dwelling units is secondary and subordinate to the nonresidential use and restricted for occupancy only by the employees of the nonresidential use.

FACTORY-BUILT HOUSING: Any structure, or component of a structure, designed primarily for residential occupancy, either permanent or temporary, that is wholly or in substantial part made, fabricated, formed, or assembled in manufacturing facilities for installation, or assembly and installation, on the building site, and that does not meet the definition of a manufactured home. Factory-built housing shall either comply with the Town's adopted building codes or the Colorado Division of Housing adopted Building Codes for Modular Homes, as set forth in CDOH Rule 2, Codes and Standards, at 8 CCR 1302-14.

FAMILY: One or more individuals occupying a single dwelling unit and living as a single housekeeping unit with a maximum of eight adults. This includes groups of eight or fewer persons whose right to live together is protected by the federal Fair Housing Amendments Act.

GAS STATION: Any building or lot having facilities for the sale of gasoline and other fuels for use by motor vehicles, and which may include incidental facilities for service and minor repair of motor vehicles.

GOVERNMENT BUILDINGS AND FACILITIES: Any building or facility owned and operated by the United States of America, the state of Colorado, the Town of Ridgway, or any agency or political subdivision thereof.

GROSS FLOOR AREA: The heated area of a building measured along the outside enclosing walls, excluding interior parking areas and outdoor common areas.

GROUP HOME: One or more dwelling units in which more than eight unrelated individuals or related and unrelated individuals live, where physical assistance and/or supervision, care or treatment is provided by resident and/or nonresident professional support personnel as a continual benefit. This definition does not include a hotel, motel, boarding or rooming house, facility housing juvenile or adult offenders, or a facility for persons with drug or alcohol addictions that are not in a treatment program, but includes any group of eight or more persons whose right to live together is protected by the federal Fair Housing Amendments Act. Group home shall include state licensed personal care and alternative care personnel.

HIGH-WATER MARK: The boundary dividing a river bed from a river bank and defined as the line on the bank up to which the presence and action of water are so usual and long conditioned as to impress on the bed a character distinct from that of the bank with respect to the nature of the ground surface, soil and vegetation.

HOME OCCUPATION: Any commercial activity, whether for profit or nonprofit, conducted within a dwelling unit.

HOMEOWNERS' ASSOCIATION: Any entity, whether corporation, partnership, nonprofit, unincorporated association, or other entity existing for the purpose of maintaining commonly owned facilities and/or enforcing private protective covenants whose members or shareholders are the property owners involved.

HOTELS AND MOTELS: Any building or portion thereof containing six or more guest rooms used, designed to be used, let or hired out for occupancy by persons on more or less a temporary basis.

LOT: A unit into which land is divided on a subdivision plat, including a condominium unit.

LOT WIDTH: Measured at the frontage of that abutting public street which provides actual access to the lot.

MAJOR ADDITION: An addition to or renovation of a structure in which the total gross floor area of the proposed addition or renovation area is 50 percent or more of the total gross floor area of the existing structure before addition or renovation.

MANUFACTURED HOME: A factory-built structure that is built on a permanent chassis, is designed and constructed to permit lawful long-term occupancy as a dwelling, whether attached or unattached to a permanent foundation, that meets requirements of the National Manufactured Housing Construction and Safety Standards Act of 1974", 42 U.S.C. Section 5401, et seq., as amended (commonly referred to as the "HUD Code".).

MIXED-USE SITE: An undivided or combination of undivided lots under one or more ownership or lease agreement used for a mixture of commercial, industrial, institutional, and residential uses.

MULTIFAMILY RESIDENTIAL SITE: An undivided or combination of undivided lots under one or more ownership or lease arrangements occupied by multiple dwelling units.

MANUFACTURED HOME PARK: A single site, parcel, or lot operated and used for the location of two or more manufactured homes intended for use as residences.

NATIVE VEGETATION: Vegetative species that occur naturally in a particular region, ecosystem, and habitat.

NONCONFORMING USE: A use which does not comply with the use regulations, dimensional requirements or other regulations of these Zoning Regulations.

NONRESIDENTIAL SITE: An undivided or combination of undivided lots under one or more ownership or lease agreement used for commercial, industrial, or institutional uses.

PERSON: means any individual, firm, partnership, corporation, association, LLC, or other entity, including to the extent allowed by law, the United States and the State of Colorado, and any agency or political subdivision thereof.

PLANNING COMMISSION: The Planning and Zoning Commission of the Town.

PUBLIC UTILITY SERVICE FACILITIES: Transmission and distribution facilities for natural gas, electricity, water, sewer, drainage, telephone, and cable television necessary to provide service to customers located in the various districts of the Town, such as pipes, lines, mains, wires, transformers, valves, and other related appurtenances, but not including buildings, offices, and production or generation facilities.

SETBACK: The perpendicular distance between a property line and the building line.

SHORT-TERM RENTAL: Rental of all or a portion of a residential dwelling unit for periods of less than 31 days. This definition of short-term rentals excludes hotels, motels, lodges, and bed and breakfasts.

SINGLE-FAMILY RESIDENTIAL SITE: An undivided or combination of undivided lots under one ownership occupied by a single-family residential structure and related accessory structures.

STRUCTURE HEIGHT: A be determined as follows for application of the limitations as set forth herein:

(a) The height of any structure shall be determined by measuring the vertical distance between the elevation of the lowest point of the natural grade abutting any exterior wall or supporting structure and the highest point of the coping of a flat roof or to the deck line of a mansard roof or to the average height of the highest gable or a pitched or hipped roof. Structures that do not have roofs shall be measured to the height of the structure.

(b) The height of each separate terrace or step for terraced or stepped buildings shall be considered for purpose of application of these limits.

(c) Allowable building height may be increased by six inches if the roof design includes raised heel trusses. *[Relocated from footnote to Table at Sec. 7-3-15(A).]*

SUBDIVISION: A parcel of land which is divided into two or more parcels, lots, tracts or other interests including condominiums; townhouses, other common interest ownership properties; and apartment complexes or other development involving more than one primary building; and any act creating such results. Provided, however, the following shall not be considered to be a subdivision for the purpose or application of these regulations:

- (1) A division of land which creates cemetery lots;
- (2) The creation of separate but undivided interests in a tract of land such as joint tenancy, tenancy in common, tenancy in entirety, trust, lien, mortgage, deed of trust or other security interest, unless such separate interests apply to less than all of the tract;
- (3) An interest severing the oil, gas, minerals or water from the surface estate;
- (4) Creation of a utility easement or an easement unrelated to the use of the surface;
- (5) Any division of property created by acts of a Town;
- (6) Boundary adjustments which resolve a disputed boundary or boundary survey problem such as overlaps or gaps, so long as the boundary adjustment or transaction does not result in the transfer from one parcel to another of an area in excess of 10,000 square feet.

SUBDIVIDE: Any act which is intended to or does result in the creation of a subdivision, and SUBDIVIDER: Any person performing such act or processing a subdivision pursuant to this Section X-XX

SUBDIVISION, XXXX: [Many new definitions will be added under Subdivision to address the new subdivision processes added to the Section 5, Subdivision Regulations.]

SUBDIVISION, MINOR: A minor subdivision shall include a resubdivision of a structure of two or fewer units, a minor relocation of a property line, a correction of a survey or engineering error, and the conversion of an existing structure into townhomes or condominiums.

TOWN: means Town of Ridgway, Colorado, and any authorized officer, employee or agent thereof.

TOWNHOME: An individually owned residential unit that has an undivided interest in common with other unit owners in the common elements of a project including land and infrastructure. Townhouse ownership includes the structure, from foundation to roof in an unbroken vertical plane, and the land on which the foundation of the Townhouse is constructed. In order for footings to be considered a foundation in any location, that area must have an unbroken vertical plane to the roof and must be physically attached to the building. Townhouse units or portions thereof cannot be stacked one above another. Nothing shall be construed to prohibit the ownership of common areas by a homeowners association holding title to such areas for and on behalf of the individual owners of a townhouse unit.

TRAVEL HOME: Any movable or relocatable dwelling unit with a living area of less than 500 square feet or which is required to have a license plate.

TRAVEL HOME PARK: A park or campground for the temporary use of travel homes, including, but not limited to, campers, motorhomes, pick-up truck campers, trailers and trailer coaches.

USE: The activity or purpose for which property, a building or other structure is designed, arranged, intended, occupied or maintained.

USE BY RIGHT: A use which is permitted or allowed in the district involved, without review, and complies with the provisions of these Zoning Regulations and other applicable Town ordinances and regulations.

WORKFORCE HOUSING: Housing that is available for purchase or rent on terms that are affordable to households earning between 80 percent and 120 percent of area median income (AMI) as determined by the U.S. Department of Housing and Urban Development (HUD) and published annually for the County. The cost of for sale workforce housing (including principal, interest, taxes, insurance, utilities, and

homeowners' association fees) or for rent workforce housing (including rent and utilities) does not exceed 30 percent of those households' gross annual incomes.

YARD, FRONT: A yard extending between the side lot lines across the full width of the lot and lying between the front lot line and any portion of any structure on the lot. In those instances where a lot abuts two (2) streets, such as a corner lot or a double frontage lot, the town manager shall designate which yard constitutes the front yard based on the existing development patterns within the neighborhood.

YARD, REAR: A yard extending between the side lot lines across the full width of the lot and lying between the rear lot line and any portion of any structure on the lot.

YARD, SIDE: A yard extending between the front and rear lot lines along the full length of the lot and lying between the side lot line that abuts a public way or private street and any portion of any structure on the lot.

AGENDA ITEM #5

PLANNING COMMISSION

MINUTES OF THE REGULAR MEETING

NOVEMBER 29, 2022

CALL TO ORDER

The Planning Commission convened both in-person at 201 N. Railroad Street, Ridgway, Colorado and via Zoom Meeting, a virtual meeting platform, pursuant to the Town's Electronic Participation Policy, due to the COVID-19 pandemic.

The Chairperson called the meeting to order at 5:30 p.m. Commissioners Franz, Liske, Nelson, Petruccelli, Mayor Pro-Tem Meyer, Mayor Clark and Chairperson Montague were in attendance.

WORK SESSION

1. Presentation of Initial Draft of Proposed Updates to Chapter 7 "Planning and Zoning"

Memorandum dated November 23,2022 outlining the three functions of the municipal code and Proposed Chapter 7 Draft Updates, prepared by TL Dlubac, CPS of Community Planning Strategies LLC; Power Point Presentation, Chapter 7 Conceptual Draft, prepared by Katie Kent, CPS of Community Planning Strategies LLC

Planners Kent and Dlubac presented the proposed updates to Chapter 7, "Planning & Zoning" and explained the purpose of the updates is to depict and separate the functions for administration process, procedures and standards which will enhance the Users' ability to navigate through Chapter 7 of the Ridgway Municipal Code. They reviewed the approach for making the updates, chapter layout and policy changes. The Planning Commission discussed the proposed updates, asked questions and received clarification from staff and the planners. Residents Tom McKenney and Joan Chismire participated in the discission.

The Commissioners <u>agreed that the planners should move forward with the proposed draft.</u> Mr. Dlubac requested the Planning Commission members submit comments regarding the updates to him or the Town Manager by December 16 and noted a Developer/Applicant Open House should occur before the proposed updates are finalized. Planner Dlubac noted the final draft will be presented to the Planning Commission at the Regular Meeting on January 31 for recommendation to the Town Council.

APPROVALOF THE MINUTES

2. Approval of the Minutes from the Regular Meeting of October 25,2022

ACTION:

Commissioner Liske moved to <u>approve the Minutes from October 26, 2022.</u> Mayor Pro-Tem Meyer seconded the motion. On a call for the roll call vote, the motion carried unanimously.

OTHER BUSINESS

3. Update Regarding Regular Meeting Schedule

The Commissioners <u>agreed to defer the December Regular Planning Commission Meeting to January 10,</u> <u>2023.</u> The January Regular Planning Commission Meeting will be held as scheduled on January 31, 2023.

4. Updates from Planning Commission Members

Planning Commission November 29, 2022 Page 2

The Chairperson reminded the Commissioners that the Town Staff Christmas party will be held on December 9th.

ADJOURNMENT

The meeting adjourned at 7:45 p.m.

Respectfully submitted,

Karen Christian Deputy Clerk